



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet CFB Comox FFTA Source Control Proje Projet de contrôle à la source dans l'AELI de la BFC Comox	
Solicitation No. - N° de l'invitation EZ113-210191/B	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client	Date 2021-02-01
GETS Reference No. - N° de référence de SEAG PW-\$PWY-031-8900	
File No. - N° de dossier PWY-0-43021 (031)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Pacific Standard Time PST on - le 2021-02-23 Heure Normale du Pacifique HNP	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Leung, Janie	Buyer Id - Id de l'acheteur pwy031
Telephone No. - N° de téléphone (778) 919-3273 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DND - CFB Comox, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Amendment 005 is raised address questions.

Questions and Answers

Q1. On the site visit phone call it was stated that working hours are 8:30 am to 5:30 pm. In the documents it is stated as 7 am to 5 pm, can you clarify the working hours and does this include the ability to work Saturday?

A1. Addressed in Amendment 002. The posted tender documents, Specifications, and Drawings take precedence over any information provided during the Bidder's Meeting. The hours of work remain as per Specification Section 01 11 00, 1.13, which state that the working hours are 07:00 to 19:00 Monday to Saturday, **inclusive**.

Q2. The RFP docs state that the project is to start 20 days after the contract has been finalized. On the site visit call it was stated that this was intended to be a summer project. Can you verify the expected onsite start date for the project?

A2. The intent is to complete the project during the dry season, especially the excavation portions of the work. The Specifications (01 11 00 1.12) text is as follows: "Work to be initiated: as soon as practical, and no later than 20 days, after Contract notice."

The Proponent must supply a schedule for the work. See 01 11 00 Sections 1.12.3 and 1.12.4 for Substantial Performance and Final Completion deadlines. The Substantial Completion deadline and Certificates of Destruction (supporting the Certificate of Completion) are considered most likely to drive the schedule and require the earliest possible start date.

Examples of Work that are required prior to mobilization or other site Work components includes but are not limited to

- pre-Work submissions (01 33 00),
- preconstruction (Kickoff) meeting (01 31 19 Section 1.6) and
- project design components (01 11 00 and 01 25 20).

Q3. Is the contractor responsible for any post stabilization analytical verification that the stabilized material has met a leachate threshold?

A3. No

Q4. Will any post stabilization analytical verification be completed for the project?

A4. Canada may sample the stabilized material for the record only, post stabilization analytical verification is not a requirement for this contract.

Q5. Is it acceptable that the QP PFAS individual that is chosen by the contractor be from outside of Canada, even if they cannot meet the security clearance requirements for CFB Comox? Further to this, is it required that the QP PFAS visit the project site?

A5. The Specifications do not stipulate citizenship or residency of the QP-PFAS, nor do they stipulate mandatory site visits by the QP-PFAS. The QP-PFAS must determine, within their professional college/associations code of ethics, the necessary information required to provide technically sound evaluations of the work, as required. See 01 11 55 Section 1.2.58.2 for requirements related to QP-PFAS familiarity with applicable regulations. There is a security requirement for this project as per Special Instruction SI21 in the RFP document.

Q6. Is it the responsibility of the Contractor to provide a project Environmental Monitor or will the Owner's onsite Rep be completing that role?

A6. Monitoring is a necessary component of the Contractor's Work as detailed in many parts of the Specifications. For more details, Proponents are directed to 01 32 43 (Environmental Protection) and to the EMP in Annex C. The EMP Section 4 specifically covers environmental responsibilities and stipulates that the Contractor retain an Environmental Monitor.

Q7. Is there a water source available onsite for project use?

A7. The only nearby water source available during the work is the fire hydrant to be removed/replaced during the work. Alternate water sources may be arranged by request and coordination via the Departmental Representative, but have not been identified at this time.

Q8. At what volume and rate can the "owner supplied" water treatment contractor accept contaminated water from the FFTA Source Control Project?

A8. In addition to the requirements in 02 61 00.01, see 01 35 13.43 Section 1.13 for details regarding maximum daily volumes and maximum turbidity for provision to the DND WTU.

Solicitation No. - N° de l'invitation
EZ113-210191/B

Amd. No. - N° de la modif.
005

Buyer ID - Id de l'acheteur
PWY031

Client Ref. No. - N° de réf. du client

File No. - N° du dossier
PWY-0-043021

CCC No./N° CCC - FMS No./N° VME

Q9. Will waste water from the specified wheel wash systems be considered “PFAS contaminated”, and require transport to, and treatment at, the water treatment facility?

A9. Yes

Q10. Can you confirm what type of waste water is generated from fire fighting training? This information is necessary to design the holding tanks.

A10. Only potable water is intended for fire fighting training at CFB Comox. However, an accidental release of AFFF during training exercise cannot be ruled out, so it is possible that the training water could potentially contain PFAS. No data is available regarding post-training water quality.

All other terms and conditions remain unchanged.