

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 01 00 10 - General Instructions.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .3 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
 - .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
 - .7 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
 - .8 As-built drawings:
 - .1 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).

- .2 Submit to Departmental Representative for approval and make corrections as directed.
- .3 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Provide one set of special tools required to service equipment as recommended by manufacturers.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not used.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Departmental Representative will record these demonstrations on video tape for future reference.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 01 00 10 - General Instructions.

1.2 REFERENCE STANDARDS

- .1 Canadian Standards Association (CSA)
 - .1 CSA B79-08 (R2018), Floor, Area and Shower Drains, and Cleanouts for Residential Construction.
- .2 National Research Council Canada (NRC)
 - .1 National Plumbing Code of Canada 2015 (NPC).

1.3 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-installation Meetings:
 - .1 Convene pre-installation meeting 1 week prior to beginning work of this Section and on-site installation, with contractor's representative and Departmental Representative to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building construction subtrades.
 - .4 Review manufacturer's written installation instructions and warranty requirements.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for plumbing products and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Indicate on drawings to indicate materials, finishes, method of anchorage, number of anchors, dimensions construction and assembly details and accessories.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Manufacturers' Field Reports: manufacturers' field reports specified.

1.5 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.

- .2 Operation and Maintenance Data: submit operation and maintenance data for plumbing specialties and accessories for incorporation into manual.
 - .1 Description of plumbing specialties and accessories, giving manufacturers name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .2 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect plumbing materials from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2 - PRODUCTS

2.1 FLOOR DRAINS

- .1 Trench Drains: to CSA B79.
- .2 Trench Drain Assembly:
 - .1 General:
 - .1 The surface drainage system shall be polymer concrete channel system with ductile iron edge rails.
 - .2 Materials:
 - .1 Channels shall be manufactured from polyester resin polymer concrete with an integrally cast-in ductile iron edge rail, minimum properties of polymer concrete will be as follows:
 - .1 Compressive strength: 14,000 psi
 - .2 Flexural strength: 4,000 psi
 - .3 Tensile strength: 1,500 psi
 - .4 Water absorption: 0.7%
 - .5 Frost proof: yes
 - .6 Dilute acid and Alkali resistant: yes
 - .7 B177 salt spray test compliant: yes
 - .2 The system shall be 12" (300 mm) nominal internal width with a 14.2" (390 mm) overall width and a built-in slope of 0.5%. Channel invert shall have developed "V" shape. All channels shall be interlocking with a male/female joint.
 - .3 Channel shall withstand loading to proper load class as outlined by EN 1433. Grate type shall be appropriate to meet the system load class specified and intended application. Grates shall be secured using 'Powelok' boltless locking system. Channel and grate shall be certified to meet the specified EN 1433 load class. The system shall be installed in accordance with the manufacturer's instructions and recommendations.
 - .3 Refer to schedule for sizes.

- .3 Ductile Iron Slotted Grate:
 - .1 Materials:
 - .1 The covers shall be manufactured from ductile iron and have minimum properties as follows:
 - .1 Independently certified to meet Load Class F to EN 1433 - 200,000 lbs. - 4,182 psi
 - .2 Ductile iron to ASTM A536 - Grade 65-45-12
 - .3 Intake area of 813 sq.cm per ½ metre of grate
 - .2 The overall width of 13.25" (336 mm) and overall length of 19.67" (500 mm). Slots measure at a maximum of 0.74" (19 mm).
 - .2 Grate:
 - .1 Grate is slotted ductile iron, Ductile iron ASTM A536 - Grade 65-45-12. After removal of grates there shall be uninterrupted access to the trench to aid maintenance.
 - .3 Installation:
 - .1 The trench drain system and gates shall be installed in accordance with the manufacturer's installation instructions and recommendations.

2.2 ELECTRONIC TRAP SEAL PRIMER - TSP

- .1 Electronic activated type, brass construction with "O" ring seals, 13 mm (NPT ½) female inlet & 13 mm (NPT ½) female outlet drip line connection with air female inlet & 13 mm (NPT ½) female outlet drip line connection with air gap, viewing holes, and removable filter screen. Trap primer shall have no flow adjustment. Operating range shall be 138 kPa (20 psi) to 861 kPa (125 psi). Operates on pre-set 24 h clock with manual override switch/test button. Unit shall have 120 V solenoid valve and calibrated manifold for equal water distribution. One (1) to five (5) drain taps per unit.
- .2 Identify on as-built drawings the location of each trap seal primer.
- .3 Ensure all trap seal primers are accessible for maintenance purposes and are connected to cold waterline. Trap line shall be from top of cold water line and include a service valve.
- .4 Trap seal primer shall be surface mounted on block wall in Class 1 Division 1 explosion proof PVC enclosure. All piping between man hole and trap seal primer enclosure shall be Class 1 Division 1 explosion proof rated to maintain rating.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for plumbing specialties and accessories installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.3 INSTALLATION

- .1 Install in accordance with National Plumbing Code of Canada (NPC) and local authority having jurisdiction.
- .2 Install in accordance with manufacturer's instructions and as specified.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Divisions 21, 22, 23, 25, 26, 28 & 33.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet for fixtures and equipment.
- .3 Shop Drawings.
 - .1 Submit shop drawings to indicate:
 - .1 Equipment, including connections, fittings, control assemblies and ancillaries. Identify whether factory or field assembled.
 - .2 Wiring and schematic diagrams.
 - .3 Dimensions and recommended installation.
 - .4 Pump performance and efficiency curves.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Manufacturers' Field Reports: manufacturers' field reports specified.
- .7 Closeout submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals, include:
 - .1 Manufacturers name, type, model year, capacity and serial number.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list with names and addresses.

1.3 QUALITY ASSURANCE

- .1 Pre-Installation Meeting:
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section and on-site installations in accordance with Section 01 32 16.19 - Construction Progress Schedule - Bar (GANTT) Chart.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .2 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
 - .3 Divert unused materials from landfill to metal recycling facility as approved by Departmental Representative.
 - .4 Unused sealant materials must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
 - .5 Fold up metal and plastic banding, flatten and place in designated area for recycling.

PART 2 - PRODUCTS

2.1 SUMP PUMP SUBMERSIBLE

- .1 Class 1, Division 01 explosion rated completed with all Class 1, Division 01 explosion proof rated accessories.
- .2 Capacity: as indicated.
- .3 Construction: duplex CSA approved, housing epoxy coated cast iron, stainless steel stainless steel shaft, non-clog bronze impeller, mechanical shaft seal.
- .4 Motor: as indicated hermetically sealed, with automatic overload protection.
- .5 Control: integral diaphragm type level control, buoyant case and switch.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 INSTALLATION

- .1 Make piping and electrical connections to pump and motor assembly and controls as indicated.
- .2 Ensure pump and motor assembly do not support piping.
- .3 Align vertical pit mounted pump assembly after mounting and securing cover plate.

3.3 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Check power supply.
 - .2 Check starter protective devices.

- .2 Start-up, check for proper and safe operation.
- .3 Check settings and operation of hand-off-auto selector switch, operating, safety and limit controls, audible and visual alarms, over-temperature and other protective devices.
- .4 Adjust flow from water-cooled bearings.
- .5 Adjust impeller shaft stuffing boxes, packing glands.

3.4 START-UP

- .1 General:
 - .1 In accordance with Section 01 91 13 - General Commissioning Requirements: General Requirements, supplemented as specified herein.
 - .2 Procedures:
 - .1 Check power supply.
 - .2 Check starter O/L heater sizes.
 - .3 Start pumps, check impeller rotation.
 - .4 Check for safe and proper operation.
 - .5 Check settings, operation of operating, limit, safety controls, over-temperature, audible/visual alarms, other protective devices.
 - .6 Test operation of hands-on-auto switch.
 - .7 Test operation of alternator.
 - .8 Adjust leakage through water-cooled bearings.
 - .9 Adjust shaft stuffing boxes.
 - .10 Adjust leakage flow rate from pump shaft stuffing boxes to manufacturer's recommendations.
 - .11 Check base for free-floating, no obstructions under base.
 - .12 Run-in pumps for 12 continuous hours.
 - .13 Check installation, operation of mechanical seals, packing gland type seals. Adjust as necessary.
 - .14 Adjust alignment of piping and conduit to ensure full flexibility.
 - .15 Eliminate causes of cavitation, flashing, air entrainment.
 - .16 Measure pressure drop across strainer when clean and with flow rates as finally set.
 - .17 Replace seals if pump used to degrease system or if pump used for temporary heat.
 - .18 Verify lubricating oil levels.

3.5 PV - SANITARY PUMPS

- .1 Application tolerances:
 - .1 Flow: plus 10%; minus 0%.
 - .2 Pressure: plus 10%; Minus 5%.
- .2 PV Procedures:
 - .1 Fill sump at rate slower than capacity of pump #1.
 - .2 Record levels at which pump #1 starts and stops. Determine flow rate by observing time taken to down water level.
 - .3 Fill sump at rate faster than capacity of pump #1 but slower than capacities of pumps #1 and #2 operating in parallel.
 - .4 Record levels at which pumps start and stop - water level rising and water level falling.
 - .5 Verify operation of alternator.
 - .6 Adjust water level controls as necessary.
 - .7 Fill sump at rate faster than capacities of pumps #1 and #2 operating in parallel.

- .8 Record levels at pump starts and stops - water level rising and falling.
- .9 Check operation of alternator.
- .10 Adjust level controls as necessary.
- .11 Check level at which high water level alarm starts and stops. Adjust as necessary.
- .3 Check removability of pumps for servicing without interfering with installation or operation of other equipment.
- .4 Verify non-clog capability and maximum size of solids, using procedures recommended by manufacturer.

3.6 REPORTS

- .1 In accordance with Section 01 91 13 - General Commissioning Requirements: reports, supplemented as specified.
- .2 Include:
 - .1 PV results on approved PV Report Forms.
 - .2 Product Information report forms.
 - .3 Pump performance curves (family of curves) with final point of actual performance.

3.7 TRAINING

- .1 In accordance with Section 01 91 13 - General Commissioning Requirements: Training of O&M Personnel, supplemented as specified.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Divisions 21, 22 & 23.

1.2 REFERENCE STANDARDS

- .1 American Society of Mechanical Engineers International (ASME)
 - .1 ASME B16.15-2018, Cast Copper Alloy Threaded Fittings, Classes 125 and 250.
 - .2 ASME B16.18-2018, Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ASME B16.22-2018, Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.
 - .4 ASME B16.24-2016, Cast Copper Alloy Pipe Flanges and Flanged Fittings: Class 150, 300, 400, 600, 900, 1500 and 2500.
- .2 ASTM International (ASTM)
 - .1 ASTM A307-14, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .2 ASTM B 88M-14, Standard Specification for Seamless Copper Water Tube (Metric).
 - .3 ASTM F1960-19a, Standard Specification for Cold Expansion Fittings with PEX Reinforcing Rings for Use with Cross-linked Polyethylene (PEX) and Polyethylene of Raised Temperature (PE-RT)
- .3 American Water Works Association ((AWWA)
 - .1 AWWA C111/A21.11-17, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
- .4 CSA Group (CSA)
 - .1 CSA B137.5-13, Crosslinked Polyethylene (PEX) Tubing Systems for Pressure Applications.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data
 - .1 Provide manufacturer's printed product literature and datasheets for insulation and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials.
- .2 Place materials defined as hazardous or toxic in designated containers.

PART 2 - PRODUCTS

2.1 PIPING

- .1 Domestic hot, cold and recirculation systems, within building.
 - .1 Above ground:
 - .1 Copper tube, hard drawn, type K: to ASTM B88M.
 - .2 Buried or embedded:
 - .1 Copper tube, soft annealed, type K: to ASTM B88M, in long lengths and with no buried joints.

2.2 FITTINGS

- .1 Bronze pipe flanges and flanged fittings, Class 150 and 300: to ASME B16.24.
- .2 Cast bronze threaded fittings, Class 125 and 250: to ASME B16.15.
- .3 Cast copper, solder type: to ASME B16.18.
- .4 Wrought copper and copper alloy, solder type: to ASME B16.22.
- .5 NPS 1½ and smaller:
 - .1 Wrought copper to ASME B16.22; with 301 stainless steel internal components and EPDM seals. Suitable for operating pressure to 1380 kPa.

2.3 JOINTS

- .1 Rubber gaskets, latex-free 1.6 mm thick: to AWWA C111.
- .2 Bolts, nuts, hex head and washers: to ASTM A307, heavy series.
- .3 Solder: 95/5 tin copper alloy.
- .4 Teflon tape: for threaded joints.
- .5 Dielectric connections between dissimilar metals: dielectric fitting, complete with thermoplastic liner.

2.4 BALL VALVES

- .1 NPS 2 and under, screwed:
 - .1 Class 150.
 - .2 Forged Brass body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle as specified Section 23 05 23.01 - Valves - Bronze.
- .2 NPS 2 and under, soldered:
 - .1 To ANSI/ASME B16.18, Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle, with NPT to copper adaptors as specified Section 23 05 23.01 - Valves - Bronze.
- .3 NPS 2 and under, mechanical:
 - .1 To CSA B137.5 and ASTM F1960.

- .2 Lead free brass body.

PART 3 - EXECUTION

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install in accordance with Ontario and local authority having jurisdiction.
- .2 Install pipe work in accordance with Section 23 05 15 - Common Installation Requirements for HVAC Pipework, supplemented as specified herein.
- .3 Assemble piping using fittings manufactured to ANSI and Standard Council of Canada (SCC) standards.
- .4 Install CWS piping below and away from HWS and HWC and other hot piping so as to maintain temperature of cold water as low as possible.
- .5 Connect to fixtures and equipment in accordance with manufacturer's written instructions unless otherwise indicated.
- .6 Valves
 - .1 Isolate equipment, fixtures and branches with ball valves.
 - .2 Balance recirculation system using lockshield globe valves. Mark settings and record on as-built drawings on completion.

3.3 PRESSURE TESTS

- .1 Test pressure: greater of 1 times maximum system operating pressure or 860 kPa.

3.4 FLUSHING AND CLEANING

- .1 Flush entire system for 8 h. Ensure outlets flushed for 2 hours. Let stand for 24 hours, then draw one sample off longest run. Submit to testing laboratory to verify that system is clean copper to Federal potable water guidelines. Let system flush for additional 2 hours, then draw off another sample for testing.

3.5 PRE-START-UP INSPECTIONS

- .1 Systems to be complete, prior to flushing, testing and start-up.
- .2 Verify that system can be completely drained.

- .3 Ensure that pressure booster systems are operating properly.
- .4 Ensure that air chambers, expansion compensators are installed properly.

3.6 DISINFECTION

- .1 Flush out, disinfect and rinse system to requirements of authority having jurisdiction.
- .2 Upon completion, provide laboratory test reports on water quality for Departmental Representative approval.

3.7 START-UP

- .1 Timing: start up after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
- .2 Provide continuous supervision during start-up.
- .3 Start-up procedures:
 - .1 Establish circulation and ensure that air is eliminated.
 - .2 Check pressurization to ensure proper operation and to prevent water hammer, flashing and/or cavitation.
 - .3 Monitor piping HWS and HWC piping systems for freedom of movement, pipe expansion as designed.
 - .4 Check control, limit, safety devices for normal and safe operation.
- .4 Rectify start-up deficiencies.

3.8 PERFORMANCE VERIFICATION

- .1 Scheduling:
 - .1 Verify system performance after pressure and leakage tests and disinfection are completed, and Certificate of Completion has been issued by authority having jurisdiction.
- .2 Procedures:
 - .1 Verify that flow rate and pressure meet Design Criteria.
 - .2 TAB HWC in accordance with Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .3 Adjust pressure regulating valves while withdrawal is maximum and inlet pressure is minimum.
 - .4 Sterilize HWS and HWC systems for Legionella control.
 - .5 Verify performance of temperature controls.
 - .6 Verify compliance with safety and health requirements.
 - .7 Check for proper operation of water hammer arrestors. Run one outlet for 10 seconds, then shut of water immediately. If water hammer occurs, replace water hammer arrestor or re-charge air chambers. Repeat for outlets and flush valves.
 - .8 Confirm water quality consistent with supply standards, and ensure no residuals remain as result of flushing or cleaning.
- .3 Reports:
 - .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements: Reports, using report forms as specified in Section 01 91 13 - General Commissioning (Cx) Requirements: Report Forms and Schematics.

- .2 Include certificate of water flow and pressure tests conducted on incoming water service, demonstrating adequacy of flow and pressure.

3.9 OPERATION REQUIREMENTS

- .1 Co-ordinate operation and maintenance requirements including, cleaning and maintenance of specified materials and products with Section 23 05 15 - Common Installation Requirements for HVAC Pipework.

3.10 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Divisions 21, 22, 23, 31, 32 & 33.

1.2 REFERENCE STANDARDS

- .1 ASTM International (ASTM)
 - .1 ASTM B 32-08 (R2014), Standard Specification for Solder Metal.
 - .2 ASTM B 306-13, Standard Specification for Copper Drainage Tube (DWV).
 - .3 ASTM C 564-14, Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings.
- .2 CSA Group (CSA)
 - .1 CSA B67-1972(R1996), Lead Service Pipe, Waste Pipe, Traps, Bends and Accessories.
 - .2 CAN/CSA-B70-19, Cast Iron Soil Pipe, Fittings and Means of Joining.
 - .3 CAN/CSA-B125.3-18, Plumbing Fittings.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36-13, Commercial Adhesives.
- .4 National Research Council Canada (NRC)
 - .1 National Plumbing Code of Canada 2015 (NPC).
- .5 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168-A2005, Adhesive and Sealant Applications.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials in accordance with Section 01 74 19 - Waste Management and Disposal.

PART 2 - PRODUCTS

2.1 SUSTAINABLE MATERIAL

- .1 Adhesives and Sealants:
 - .1 Maximum VOC limit 30 g/L to SCAQMD Rule 1168 and GSES GS-36.

2.2 COPPER TUBE AND FITTINGS

- .1 Above ground sanitary and Type DWV to: ASTM B306.
 - .1 Fittings:
 - .1 Cast brass: to CAN/CSA-B125.3.
 - .2 Wrought copper: to CAN/CSA-B125.3.
 - .2 Solder: to ASTM B32.

2.3 CAST IRON PIPING AND FITTINGS

- .1 Buried sanitary and vent minimum NPS 2, to: CAN/CSA-B70, with one layer of protective coating.
 - .1 Joints:
 - .1 Mechanical joints:
 - .1 Neoprene or butyl rubber compression gaskets: to CAN/CSA-B70 or ASTM C564.
 - .2 Stainless steel clamps.
 - .2 Hub and spigot:
 - .1 Caulking lead: to CSA B67.
 - .2 Cold caulking compounds.
- .2 Above ground sanitary and vent: to CAN/CSA-B70.
 - .1 Joints:
 - .1 Hub and spigot:
 - .1 Caulking lead: to CSA B67.
 - .2 Mechanical joints:
 - .1 Neoprene or butyl rubber compression gaskets with stainless steel clamps.

2.4 INTERIOR CONCRETE EFFLUENT PIPING, MANHOLES AND FITTINGS

- .1 Provide interior concrete effluent piping, manholes, and fittings below slab in hangar meeting specifications of exterior below grade effluent piping of Divisions 32 and 33.
- .2 Coordinate manhole depth requirements with contractor verified interior concrete effluent piping inverts.
- .3 Provide benching in manholes to achieve positive drainage.
- .4 Interior manhole covers located in fixed wing and rotary wing hangars shall be non-perforated.
- .5 Submit shop drawing mock-up of interior manhole assemblies for review.

PART 3 - EXECUTION

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 In accordance with Section 23 05 15 - Common installation requirements for HVAC pipework.
- .2 Install in accordance with National Plumbing Code and local authority having jurisdiction.

3.3 TESTING

- .1 Pressure test buried systems before backfilling.
- .2 Hydraulically test to verify grades and freedom from obstructions.

3.4 PERFORMANCE VERIFICATION

- .1 Cleanouts:
 - .1 Ensure accessible and that access doors are correctly located.
 - .2 Open, cover with linseed oil and re-seal.
 - .3 Verify that cleanout rods can probe as far as the next cleanout, at least.
- .2 Test to ensure traps are fully and permanently primed.
- .3 Storm water drainage:
 - .1 Verify domes are secure.
 - .2 Ensure weirs are correctly sized and installed correctly.
 - .3 Verify provisions for movement of roof system.
- .4 Ensure that fixtures are properly anchored, connected to system and effectively vented.
- .5 Affix applicable label (storm, sanitary, vent, pump discharge etc.) c/w directional arrows every floor or 4.5 m (whichever is less).

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 19 - Waste Management and Disposals.

END OF SECTION