

Parks Canada Agency  
Refection of Gauron and Lafleur Bridges on Lachine  
Canal

Project N° CLAC-1524  
Addendum n° 02

THIS ADDENDUM COMPLETES, MODIFIES OR ELIMINATES CERTAIN ELEMENTS OF THE TENDER DOCUMENTS, WHICH THE ADDENDUM REFERS TO. IT IS AN INTEGRAL PART OF THE TENDER DOCUMENTS.

**MODIFICATIONS ON PLANS AND SPECIFICATIONS**

The current precisions are provided, following questions received from contractors during the site visit, and other written questions received.

**1. PRECISIONS**

**1.1 Precisions if prior reinforcement is required**

As mentioned in Addendum 01, no prior reinforcement is necessary. However, work on the gussets must be done when there is no traffic on the bridge during full closures. In addition, work must be done on one gusset at a time. Requirements and constraints are provides in section 05 12 33 STRUCTURAL STEEL FOR BRIDGE

**1.2 Lead base paint**

The paint contains lead as mentioned in section 01 29 00 PAYMENT article 2.6. and is valid for all articles of section 2.6 including article 2.6.20. Section 02 83 12 REMOVAL OF LEAD-BASED PAINT COATINGS MAXIMUM PRECAUTIONS of the specification provides the requirements for paint removal.

**1.3 Deadline section 01353-2**

The deadlines for standards compliance of traffic-control devices are 33 weeks and those in article 1.7.1.1 of the estimate 01 11 00 WORK SUMMARY are 35 weeks. No correction to be made.