

2021-01-19

Page 1

PART 1 - GENERAL**1.1 RELATED REQUIREMENTS**

- .1 Not Used.

1.2 REFERENCE STANDARDS

- .1 U.S. Environmental Protection Agency (EPA) / Office of Water
 - .1 EPA 832R92005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.4 INSTALLATION AND REMOVAL OF MATERIAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.5 DEWATERING

- .1 Provide temporary drainage and pumping facilities to keep excavations and site free from standing water.

1.6 WATER SUPPLY

- .1 Departmental Representative will provide continuous supply of potable water for construction use.
- .2 Arrange for connection with appropriate utility company and pay costs for installation, maintenance and removal.
- .3 Departmental Representative will pay for utility charges at prevailing rates.

1.7 TEMPORARY HEATING AND VENTILATION

- .1 Not Used.

1.8 TEMPORARY POWER AND LIGHT

- .1 Departmental Representative will provide and pay for temporary power during construction for temporary lighting and operating of power tools, depending on building availability.
 - .2 Arrange for connection with appropriate utility company. Pay costs for installation, maintenance and removal.
 - .3 Temporary power for electric cranes and other equipment requiring in excess of above is responsibility of Departmental Representative.
 - .4 Provide and maintain temporary lighting throughout project. Ensure level of illumination on all floors and stairs is not less than 162 lx.
-

2021-01-19

Page 2

1.9 TEMPORARY COMMUNICATION FACILITIES

- .1 Not Used.

1.10 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

PART 2 - PRODUCTS**2.1 NOT USED**

- .1 Not Used.

PART 3 - EXECUTION**3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL**

- .1 Not Used.

END OF SECTION
