

1 General

1.1 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CGSB 1.189M-84, Primer, Alkyd, Wood, Exterior.
 - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-O121-M1978, Douglas Fir Plywood.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 SITE SAFETY FENCING

- .1 Contractor to provide site safety fencing around construction site at ground level to separate construction zone from public.
- .2 Size of compound to be determined by Contractor, but it must contain all construction and construction related activities within the compound, except parking for workers.
- .3 Contractor to provide 1800mm high fence.
- .4 Contractor to provide double gates at entrance complete with lock.
- .5 Contractor to lock gate after every days activities are completed.
- .6 Contractor to post notices for both construction zone and personal protective equipment requirements.
- .7 Remove fence when directed.

1.4 DUST CONTROL BARRIERS

- .1 Provide tack mats at access points between construction zone and entrance to building. Replace when ineffective.
- .2 Provide negative ventilation of area's within dust control barriers, directly exhausting outside.
- .3 Dust control barriers shall be used wherever dust or odour will be generated by construction.

1.5 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades where a change in elevation of greater than 900mm exists.
- .2 Provide as required by governing authorities.

1.6 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished interior and exterior building components and equipment during demolition and construction. Protect floors, doors, walls, ceilings, building equipments, furnishings, flashings, windows and landscaping elements which may be affected or damaged by the Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

1.7 PROTECTION OF LANDSCAPE ELEMENT

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Be responsible for damage incurred due to lack of or improper protection.

END OF SECTION
