

1 General

1.1 FIRES

- .1 Fires and burning of rubbish on site not not permitted.

1.2 DISPOSAL OF WASTES

- .1 Do not bury rubbish and waste materials on site.
- .2 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers.
- .3 All construction wastes shall be disposed of properly, and shall to the greatest extent possible be diverted from landfills. Disposal certificates to be obtained and submitted to the Departmental Representative.

1.3 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air beyond application area, by providing temporary enclosures.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

1.4 SMOKING RESTRICTIONS

- .1 Smoking is not permitted inside the building or on site, at any time or at any stage of construction. Failure to comply will result in removal from site.

1.5 ENVIRONMENTAL PERMIT APPROVAL

- .1 Comply with requirements contained in the Newfoundland & Labrador Department of Municipal Affairs and Environment, environmental approval permit for the project.

END OF SECTION
