

1 General

1.1 RELATED REQUIREMENTS

- .1 Section 02 41 19.13 - Selective Building Demolition

1.2 DEFINITIONS

- .1 Remove and Turn Over: Detach items from existing construction and deliver them to Departmental Representative ready for reuse
- .2 Remove and Reinstall: Carefully detach items from existing construction, prepare them for reuse, safely store them onsite and reinstall them where indicated.

2 Products

2.1 SALVAGED ITEMS

- .1 Items salvaged by Constructor for reinstallation include, but are not limited to:
 - .1 Prefinished metal siding.
 - .2 Prefinished Metal siding trims.
 - .3 Extruded polystyrene insulation.
- .2 Confirm with Departmental Representative any additional items that appear salvageable prior to disposal.

3 Execution

3.1 SALVAGE

- .1 Remove and handle salvageable items on site to minimize damage and to ensure that usability is maintained.
- .2 Clean all salvaged items thoroughly prior to installation.
- .3 Place materials on pallets or wrap in protective film to ensure that loose pieces and projections do not cause injury to personnel, and that salvaged items remain as complete units.

END OF SECTION
