



**RETURN BIDS TO:
RETOURNER LES SUBMISSION À :**

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-866-246-6893

Bid Email: soumissionsouest-bidswest@canada.ca

This is the only acceptable email address for responses to bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. PCA is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 003 TO A
INVITATION TO TENDER**

**RÉVISION 003 À UNE
INVITATION À SOUMISSIONNER
DEMANDE D'OFFRES À
COMMANDES**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Offer remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'offre demeurent les mêmes.

Issuing Office - Bureau de distribution :
Parks Canada Agency
Calgary, AB

Title - Sujet : Upscheek Tashee - Wayii Construction – Pacific Rim National Park Reserve	
Solicitation No. - N° de l'invitation : 5P420-20-0443/A	Date : March 18, 2021
Amendment No. - N° de modification : 003	
Client Reference No. - N° de référence du client : 1552	
GETS Reference No. N° de reference de SEAG : PW-21-00947972	
Solicitation Closes - L'invitation prend fin : At - à : 2:00 PM On - le : March 25, 2021	Time Zone - Fuseau horaire MDT - HAR
F.O.B. - F.A.B. : Plant - Usine : <input type="checkbox"/> Destination : <input checked="" type="checkbox"/> Other - Autre : <input type="checkbox"/>	
Address Enquiries to - Adresser toutes demande de renseignements à : Rebecca Chen	
Telephone No. - N° de telephone : (587) 439-3529	Fax No. -N° de télécopieur : (866) 246-6893
Email Address – Courriel : rebecca.chen2@canada.ca	
Destination of Goods, Services, and Construction - Destination des biens, services, et construction : See Herein – Voir ici	
TO BE COMPLETED BY THE BIDDER - À REMPLIR PAR LE SOUMISSIONNAIRE	
Vendor/ Firm Name - Nom du fournisseur/ de l'entrepreneur :	
Address - Adresse :	
Telephone No. - N° de telephone :	Fax No. - N° de télécopieur :
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur	
Signature :	Date :

Amendment 003

This amendment is being raised to distribute the mandatory site visit information, questions and answers and to make changes to the tender package.

A. Mandatory Site Visit Attendees

Vendor	Representative's Name
Hazelwood	Ian Todd
Luxton Construction Inc.	Wayne Perepelitt
Pirate Excavating	Brad King
1211307 BC Ltd.	Tanya Movato
A.C.L. Construction	Janis Meirans
WCL	Dean Windley
Roc-Star Enterprises Ltd.	Max Gerth
Western Shoreline Projects	Lance McCollough
Western Watershed Design Inc.	Scott McGuinty
Bowerman Excavating	Robert Campbell
IWCE	Geoff Schulson

B. Question and Answer

Q65 From Site visit: Stump removal clarification.

A65 See response to question 31 in amendment 2

Q66 From Site visit: Bottom loop access clarification

A66 Turn around loop from permanent access on lower west end of project site (access 52) to previous access further to the west is available to contractors. The trail along this section (approximately 250m) has been prepared to base course elevation. If this access loop is used, the contractor is to reinstate to same condition at no cost to Parks.

Q67 Item 50 (Wood Safety Railings) – please confirm the species and lumber grade of lumber/wood required and if it is to be pretreated in any way. The IFT Specification 32 31 14 states “treated debarked log posts” and “debarked log rails”. The plans show 140x140 timber post and 38x140 rails. Neither mention species and or lumber grade.

A67 Lumber for these items will be Cedar, Grade No. 2. Either Red Cedar or Yellow Cedar is acceptable, but this must be consistent throughout – not a mixture of the two.

Q68 Item 35 (19.8m x 600mm CSP Culvert) – please confirm the wall thickness in mm for the proposed culvert. Nothing listed on plans nor IFT Specification 33 42 13.

A68 Galvanized or Aluminized Type II CSP with a Minimum Wall Thickness of 2.0 mm

Q69 The plans state “all pipes to be filled with 300mm of spawning gravel”. However, the General Instructions 1.17.8 states “this work does not require a DFO permit” and at the mandatory site meeting the DR stated the same due to no fisheries values for this project. Please confirm that the spawning gravel is required or not.

A69 "Spawning gravel" is not required. However, the drainage culverts DO need to be partially embedded (back-filled with trail subbase) to ensure that all new crossings allow for amphibian/small wildlife passage. Approximately 1/3 of the culvert needs to be embedded.

Q70 For the nonwoven geotextile the plans show TE-6, while the Price Table (# 29, 32A, 42) state Armtex 200. Please confirm which is to be used, or if they are equivalents.

A70 See revised price table in amendment 2

Q71 The General Instructions 1.11.3 state pavement markings are to be included in this contract. The IFT Specification 32 17 23 states centerline pavement markings but do not give any detail. I do not see any pavement markings for the proposed trail surface on any of the plan sheets. Plan sheet X-02 does have a detail drawing for the proposed highway widening to accommodate the proposed barriers which does not appear to eradicate the existing highway white line marking. Please confirm if there is any pavement markings and if so provide detail drawing. If there are pavement markings for the proposed highway widening or the proposed trail, are we to include in Item 15 & 16 respectively?

A71 See response to question 57 in amendment 2

Q72 Item 51 roadbox for slope inclinometer (and replacement of existing road box at BH17-09) – I do not see a BH17-09 on any of the plan sheets. There is a BH14-09 on the existing highway and a PH17-05 on the proposed trail. The IFT Specification 32 12 16 calls for a "steel road box (bolt-down, flush mount manhole)". Please confirm the proposed location(s) of the road box and provide a detail drawing.

A72 BH14-09 is mislabeled – Updated dwgs now show BH17-09. Bolt-down box has been specified and will be installed as per manufacturer's written recommendations.

Q73 Item 47 – please confirm the dimensions, in mm, of the required signs.

A73 Diamond shape sign (curves, steep grades, etc): 450mm X 450mm
Rectangular tabs: 600mm X 300mm

Q74 The IFT Specification 31 32 19 and the Combined price table state for the biaxial geogrid TE-BX20PP or equivalent, yet the plans show TE-BX30PP. Please confirm which is to be utilized.

A74 Drawings revised to read TE-BX20PP.

Q75 A drawing that displays thermoplastic MMA (Methyl Methacrylate) paint on new asphalt is not found. Is this needed anywhere?

A75 See response to question 57 in amendment 2

Q76 Is burning permitted onsite?

A76 No

C. Tender Package Revisions

Revised drawings

ADD: Escarpment Trail Design IFT Rev 1 2021-03-12 (002)

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED