



**RETURN BIDS TO:
RETOURNER LES SUBMISSION À :**

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-866-246-6893

Bid Email: soumissionsouest-bidswest@canada.ca

This is the only acceptable email address for responses to bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. PCA is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 002 TO A
INVITATION TO TENDER**

**RÉVISION 002 INVITATION À
SOUMISSIONNER
DEMANDE D'OFFRES À
COMMANDES**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the offer remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'offre demeurent les mêmes.

Issuing Office - Bureau de distribution :
Parks Canada Agency
Calgary, AB

Title - Sujet : Crandell Mountain Campground Stage 1 – Waterton Lakes National Park	
Solicitation No. - N° de l'invitation : 5P420-20-0404/A	Date : March 31, 2021
Amendment No. - N° de modification : 002	
Client Reference No. - N° de référence du client :	
GETS Reference No. N° de référence de SEAG : PW-21-00949517	

Solicitation Closes - L'invitation prend fin : At - à : 2:00 PM On - le : April 8, 2021	Time Zone - Fuseau horaire MDT
--	--

F.O.B. - F.A.B. : Plant - Usine : <input type="checkbox"/> Destination : <input checked="" type="checkbox"/> Other - Autre : <input type="checkbox"/>		
Address Enquiries to - Adresser toutes demande de renseignements à : Brinthan Balakumar		
Telephone No. - N° de telephone : 587-832-1894	Fax No. -N° de télécopieur : (866) 246-6893	Email Address – Courriel : Brinthan.balakumar@canada.ca
Destination of Goods, Services, and Construction - Destination des biens, services, et construction : See Herein		

TO BE COMPLETED BY THE BIDDER - À REMPLIR PAR LE SOUMISSIONNAIRE

Vendor/ Firm Name - Nom du fournisseur/ de l'entrepreneur :	
Address - Adresse :	
Telephone No. - N° de telephone :	Fax No. - N° de télécopieur :
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur	
Signature :	Date :

Solicitation No. - N° de l'invitation :
5P420-20-0404/A

Amd. No. - N° de la modif. :
002

Contracting Authority - Autorité contractante :
Brinthan Balakumar

Client Ref. No. - N° de réf. du client :

Title – Titre :
Crandell Mountain Campground Stage 1 – Waterton Lakes National Park

Amendment 002

This amendment is raised to extend the solicitation end date, answer bidder questions, make revisions to the tender package.

A. Solicitation End Date

The closing date for tender 5P420-20-0404/A is extended from April 1, 2021 to **April 8, 2021 at 2:00PM** Mountain Daylight Time (MDT).

B. Question and Answers

Q5. Is the contractor responsible for securing a location to haul excavated material from the beds, or will one be provided within the park to deposit the fill?

A5. Excavated material has been included in the applicable earthworks quantities including stripping, asphalt removal, and common excavation. The Contractor may stockpile useable excavated material on site for use in future phases of campground construction. Waste material shall be disposed of offsite as stipulated in the relevant specifications.

Q6. Is there a stockpile of topsoil for the contractor to use to fill the beds, or are they responsible to source on outside the park?

A6. No. The Contractor shall use topsoil that has been stripped as part of the Works.

Q7. Is the intent to cover the entire bed area with mulch after planting occurs?

A7. Yes. Mulch is included under Pay Item # 16 - Planting Bed c/w Planting Material and Bed Preparation.

Q8a. Does item #16 in the Unit Price table include only the plantings noted in the Planting Schedules on Drawing L-201 and L-202? Unit Price Table Bid item #17 shows a quantity of 900 owner-supplied, contractor installed plantings, but the owner-supplied items on planting schedules on L-201 and L-202 add up to 4,422. Which is correct?

A8a. 1. Yes. However, there are some revisions to those quantities. Unit price table quantities are amended as follows:

- a. Planting Bed c/w Planting Material and Bed Preparation – 6,200 m2
- b. Rare Plant Species Planting (Owner Supplied, Contractor Installed) – 4,422 each

2. Table in Specification 01 11 00, Section 1.10.4.1, should list 1,442 Geyer's Onions. Current quantity of 1,142 is a typo.

These revisions are reflected in the "Tender Package Revisions" section of this amendment.

Q8b. The details for Viewpoints 1&2 on L-201 refer to L-200 planting schedule, but L-200 has not been included in the drawing set, so can we assume these "Large Shrub Bed" areas are not included in contract?

A8b. Large Shrub Bed Planting Schedule has been added to drawing L-201 Revision T1, and the applicable area has been added to the Unit Price Table.

Q8c. Can you provide detail for the Plantings referenced in L-202, as no planting plan has been included for these items?

A8c. No planting plan will be provided. The Contractor shall install the plantings to evenly cover the entire area while reaching total planting targets.

Solicitation No. - N° de l'invitation :
5P420-20-0404/A

Amd. No. - N° de la modif. :
002

Contracting Authority - Autorité contractante :
Brinthan Balakumar

Client Ref. No. - N° de réf. du client :

Title – Titre :
Crandell Mountain Campground Stage 1 – Waterton Lakes National Park

Q9. The electrical spec states to provide 38mm x 140mm planks for protection over the underground electrical conduits. Is underground burial marker tape acceptable instead of wood planks?

A9. Planks are for areas of reduced cover as per CEC C22.1-18 12-012-3. Warning tape is required in all trenches regardless of whether mechanical protection is provided.

Q10. The drawings show that the underground conduit is to be rigid PVC conduit. Note 1 for the washroom building detail on drawing E-301 mentions to transition conduit to rigid PVC before conduit rises above grade. Is DBII conduit acceptable below grade?

A10. Buried conduits are permitted to be DB2 unless specifically noted on the drawings to be other materials. DB2 conduits are to transition to RPVC prior to rising above grade.

Q11. Are we to provide a junction box for the power and control conduits every 30 meter as stated or only provide junction boxes where shown on the electrical layout drawings? If we provide them every 30m we would need 168 small junction boxes and 16 big junction boxes.

A11. Required junction boxes are to be as shown on the Drawings. Contractor is permitted to provide additional junction boxes (at their own cost) for ease of installation if preferred.

C. Tender Package Revisions

1) Drawings - 20210129 CMC ST1 DRAWINGS IFT

IN: Sheet 53

DELETE: Drawing L-201

REPLACE WITH: L-201 T1

2) Specifications - 2021.02.25 CMC ST1 Specifications IFT

IN: Section 01 11 00 1.10.4.1 Row 1

DELETE:

Latin name	Common name	Target Quantity	Container Size	Propagule source	Estimated delivery date	Delivery format
<i>Allium geoyeri var geoyeri</i>	Geyer's Onion	1142	4" pot	Plants /Seed Salvaged from site	March 31-September 30, 2021	shipped in pots or other method approved by PCA Project Authority

REPLACE WITH:

Latin name	Common name	Target Quantity	Container Size	Propagule source	Estimated delivery date	Delivery format
<i>Allium geoyeri var geoyeri</i>	Geyer's Onion	1442	4" pot	Plants/Seed Salvaged from site	March 31-September 30, 2021	shipped in pots or other method approved by PCA Project Authority

3) DSP-5P420-20-0404

ADD: Photos-5P420-20-0404

4) **APPENDIX 1 – COMBINED PRICE FORM**

Section: UNIT PRICE TABLE

The amount for line item 16 and 17 has been changed as follows:

Solicitation No. - N° de l'invitation :
5P420-20-0404/A

Amd. No. - N° de la modif. :
002

Contracting Authority - Autorité contractante :
Brinthan Balakumar

Client Ref. No. - N° de réf. du client :

Title – Titre :
Crandell Mountain Campground Stage 1 – Waterton Lakes National Park

Previous:

16	32 93 10	Planting Bed c/w Planting Material and Bed Preparation	m ²	5,800	\$	\$
17	32 93 10	Rare Plant Species Planting (Owner Supplied, Contractor Installed)	ea	900	\$	\$

Updated:

16	32 93 10	Planting Bed c/w Planting Material and Bed Preparation	m ²	6,200	\$	\$
17	32 93 10	Rare Plant Species Planting (Owner Supplied, Contractor Installed)	ea	4,422	\$	\$

Bidders are instructed to make this change accordingly. If this is missed in the bidders bid, Canada will make this change on behalf of the bidder and use the unit price provided to obtain the correct total extended price.

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED