



- PROFILE VIEW
SCALE: H 1:250 V:25

1. PIPING SHALL BE HYDROSTATICALLY TESTED AS SPECIFIED PRIOR TO BACKFILLING.
2. DEPARTMENTAL REPRESENTATIVE SHALL EXAMINE SITE, PIPING, TRENCH, BEDDING MATERIAL & FIELD JOINTS PRIOR TO BACKFILLING.
3. TRENCHING TO BE DONE IN ACCORDANCE WITH N.S. DEPARTMENT OF LABOUR REGULATIONS. BACKSLOPE TRENCH WALLS FOR WORKER SAFETY. VERTICAL TRENCH WALLS 1.2m & 45° SIDE SLOPE TO EXISTING SURFACE.

