

PART 1 - GENERAL

- | | | |
|---|----|---|
| <u>1.1 SECTION INCLUDES</u> | .1 | Barriers. |
| | .2 | Traffic Controls. |
| <u>1.2 INSTALLATION AND REMOVAL</u> | .1 | Provide temporary controls in order to execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.3 GUARD RAILS AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and barricades around open excavations. |
| | .2 | Provide barricades along wharf structure when wheelguard is removed. |
| | .3 | Provide as required by governing authorities. |
| <u>1.4 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent harbour facilities. |
| <u>1.5 PUBLIC TRAFFIC FLOW</u> | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public. |
| <u>1.6 FIRE ROUTES</u> | .1 | Maintain access to property including overhead clearances for use by emergency response vehicles. |
| <u>1.7 PROTECTION FOR OFF-SITE AND PUBLIC</u> | .1 | Protect surrounding private and public property from damage during |

PROPERTY performance of work.

.2 Be responsible for damage incurred.

END OF SECTION

TEMPORARY BARRIERS

Floating Dock Construction AND ENCLOSURES

Section 01 56 00

SAR Station, Twillingate, NL

Page 3 of 3

Project No. R.089926.008

March 2021
