

Part 1 General**1.1 QUALIFICATIONS OF TAB PERSONNEL**

- .1 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.
- .2 Submit names of personnel to perform TAB to Departmental Representative within 90 days of award of contract.
- .3 Provide documentation confirming qualifications, successful experience.
- .4 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-.
- .5 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .6 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .7 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .8 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .9 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.2 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.

- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.3 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.4 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.5 PRE-TAB REVIEW

- .1 Review Contract Documents before project construction is started confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.6 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.7 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.8 START OF TAB

- .1 Notify 7 Departmental Representative days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.
- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.

- .2 Liquid systems:
 - .1 Flushed, filled, vented.
 - .2 Correct pump rotation.
 - .3 Strainers in place, baskets clean.
 - .4 Isolating and balancing valves installed, open.
 - .5 Calibrated balancing valves installed, at factory settings.
 - .6 Chemical treatment systems complete, operational.

1.9 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 Hydronic systems: plus or minus 10%.

1.10 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2% of actual values.

1.11 INSTRUMENTS

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

1.12 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.13 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.
 - .4 Summaries.

1.14 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.

- .2 System schematics.
 - .3 Submit 6copies of TAB Report to Departmental Representative for verification and approval, in both official languages English Frenchin D-ring binders, complete with index tabs.
- 1.15 VERIFICATION**
- .1 Reported results subject to verification by Departmental Representative.
 - .2 Provide personnel and instrumentation to verify up to 30% of reported results.
 - .3 Number and location of verified results as directed by Departmental Representative.
 - .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.
- 1.16 SETTINGS**
- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
 - .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.
- 1.17 COMPLETION OF TAB**
- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative .
- 1.18 AIR SYSTEMS**
- .1 Standard: TAB to most stringent of this section TAB standards of SMACNA AABC NEBB ASHRAE.
 - .2 Do TAB of systems, equipment, components, controls specified Division 23
 - .3 Qualifications: personnel performing TAB qualified to standards of AABC NEBB
 - .4 Quality assurance: perform TAB under direction of supervisor qualified NEBB by to standards of AABC.
 - .5 Measurements: to include as appropriate for systems, equipment, components, controls
 - .6 Locations of equipment measurements: to include as appropriate
 - .7 Locations of systems measurements to include as appropriate
- 1.19 POST-OCCUPANCY TAB**
- .1 Participate in systems checks twice during Warranty Period - #1 approximately 3months after acceptance and #2 within 1month of termination of Warranty Period.

Part 2 Products**2.1 NOT USED**

.1 Not used.

Part 3 Execution**3.1 NOT USED**

.1 Not used.

END OF SECTION