

Amendment 002

1. Q. Can we get a pay item for full depth asphalt removal? There are areas that the pulverizing equipment will not be able to access as well as the asphalt will be required to be removed and separated for all culvert installations.

A. Item to follow requirements of OPSS.PROV 510. Payment at the contract price shall be full compensation for all labour, equipment and materials necessary to do the work, including but not limited to saw cutting, excavation, removal and disposal of asphalt.

Surplus material to be disposed of off-site. Item to be provisional, subject to approval by the Departmental Representative.

Please see revised Appendix 1 Combined Price Form

2. Q. As it does not appear as all of the MH's & CB's have been shown on the contract drawings, will PWGSC please consider adding an item for adjustments to Catchbasin/Maintenance Holes Frame & Grates that would be paid by the Each?

A. A provisional item has been added for adjustment to existing manholes/catchbasins. The Contractor is to bid a unit rate for this work to be completed. Departmental Representative to advise of structures to be adjusted on site.

Please see revised Appendix 1 Combined Price Form