

Wharf Reconstruction (Phase II)

Grand Bank, NL

2021-04-04

PART 1 - GENERAL

1.1 SCOPE OF WORK
AND GROUNDING

- .1 The Electrical Contract includes all electrical work at the site including but not limited to:
1. The removal of all existing electrical equipment, devices, wiring, conduit, etc. as indicated on electrical drawings.
 2. Supply and installation of new shore power junction boxes, coverplates, receptacles, labels, power pedestals, etc. as indicated.
 3. Supply and installation of new conduit and fittings for a complete installation.
 4. Supply and installation of new multi-metering system as indicated.
 5. Installation of light fixtures on wooden poles and jib crane.
 6. Supply and installation of conduits and wiring to power pedestals, jib crane and light poles as indicated.
 7. Supply and installation of new wooden poles as indicated.
 8. Trenching as indicated on Civil drawings.
 9. Other work as indicated on drawings and in this specification.

PART 2 - PRODUCTS

NOT APPLICABLE TO THIS SECTION

PART 3 - EXECUTION

NOT APPLICABLE TO THIS SECTION