

Wharf Reconstruction (Phase II)
Grand Bank, NL

2021-04-04

PART 1 - GENERAL

- | | |
|-----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>1.1 GENERAL</u> | <ul style="list-style-type: none">.1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws..2 Store volatile waste in covered metal containers, and remove from premises at end of each working day..3 Prevent accumulation of wastes which create hazardous conditions..4 Provide adequate ventilation during use of volatile or noxious substances. |
| <u>1.2 MATERIALS</u> | <ul style="list-style-type: none">.1 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer. |
| <u>1.3 CLEANING DURING CONSTRUCTION</u> | <ul style="list-style-type: none">.1 Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis..2 Provide on-site garbage containers for collection of waste materials and debris..3 Remove waste materials and debris from site on a daily basis. |
| <u>1.4 FINAL CLEANING</u> | <ul style="list-style-type: none">.1 In preparation for acceptance of the Work perform final cleaning..2 Inspect finishes, fitments and equipment. Ensure specified workmanship and operation..3 Broom clean exterior paved and concrete surfaces; rake clean other surfaces of grounds. |