



RETURN BIDS TO:

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-877-558-2349

Bid E-mail Address: pc.soumissionsami-bidsrpc.pc@canada.ca

This is the only acceptable email address for responses to the bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. The Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

REVISION 001 TO AN INVITATION TO TENDER

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

Issuing Office:

Parks Canada Agency
National Contracting Services

Halifax, Nova Scotia

Title: Tobey Dock Reconstruction, Georgian Bay Islands National Park	
Solicitation No.: 5P468-21-0063/A	Date: 27 August 2021
Amendment No.: 002	
Client Reference No.: 2061	
GETS Reference No.: PW-21-00965317	

Solicitation Closes: At: 14:00 On: 07 September 2021	Time Zone: EDT
---	------------------------------

F.O.B.: Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
Address Enquiries to: Jaime Creaser	
Telephone No.: 902-266-8592	Fax No.: 1-877-558-2349
Email Address: Jaime.Creaser@canada.ca	
Destination of Goods, Services, and Construction: See Herein	

TO BE COMPLETED BY THE BIDDER

Vendor/ Firm Name:	
Address:	
Telephone No.:	Fax No.:
Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):	
Signature:	Date:

Solicitation No.:
5P468-21-0063/A

Amendment No.:
002

Contracting Authority:
Jaime Creaser

Client Reference No.:
2061

Title:
Tobey Dock Reconstruction, Georgian Bay Islands National Park

Amendment 002

This amendment is raised to revise the bid closing date, to make changes to the drawings and mitigation measures, to provide bidders' conference information, and to distribute questions and answers.

1. Bid Closing Date

The closing date for solicitation 5P468-21-0063/A is extended from 31 August 2021 until 07 September 2021 at 14:00 Eastern Daylight Time (EDT).

2. Drawings

The Drawings have been revised and are included in DSP 002 5P468-21-0063. A summary of changes is listed below:

DELETE: Drawing 3330-2 Sheet 2.0 Revision 4

REPLACE WITH: Drawing 3330-2 Sheet 2.0 Revision 5

3. Mitigation Measures

INSERT: 34. Develop and implement a response plan to avoid a spill of deleterious substances.

4. Bidders' Conference Information

Bidders' Conference Attendees

Vendor	Representative's Name
Louis Bray Construction	Chase Albright
Dean Construction	Yash Kotadiya
Tri-Phase	Thilini Silva

Contact information for the attendees are available upon request and approval from the vendors.

BIDDERS' CONFERENCE MEETING MINUTES

HELD ON: Tuesday, August 17th, 2018; 9:00 a.m.

HELD AT: WebEx video and Teleconference

No.	Item
1.0	Sign-in Attendance Sheet
1.1	– An attendance sheet was completed identifying participants of the meeting.
2.0	Welcome and Purpose
2.1	– Paige welcomed the prospective bidders to the park. The purpose of the meeting was to provide prospective bidders with an overview of the scope and operational constraints of the project, and provide an opportunity for questions and answers.
3.0	Introductions

No.	Item
3.1	– Introductions were conducted including members from: Parks Canada, E7 (consultant), Contractors.
4.0	Outline Project Brief
4.1	Scope of Work <ul style="list-style-type: none">- The project includes removal of the existing rubble mound, building 3 steel sheet pile cells, with 2 bridge sections and a concrete deck on top.- The contractor is to disconnect, store and reinstall the existing floating dock, and reconnect to the existing ramp- More details can be found in the documents on BuyandSell
5.0	Operational Constraints & Questions
5.1	Operational Constraints Overview <ul style="list-style-type: none">– The dock is located approx. 15-20 min by boat from Honey Harbour, in fairly protected water– The dock is on the east side of Beausoleil Island– Honey Harbour is a small community about 20 mins off of Hwy.400, 40 mins from Midland– Tobey Dock is the main point of arrival for park visitors, both for day use and campers.
5.2	Park Staff, Park Visitors & Access <ul style="list-style-type: none">– Park staff will only be allowed in the construction area if they have business at the site, provided they have taken any necessary orientation and have the proper PPE– Park visitors may be present until Thanksgiving. Contractor to ensure site security.
5.3	Construction Schedule <ul style="list-style-type: none">– Pre-construction meeting TBD – aim for early Sept. 2021– Project to be completed by Dec. 31, 2021
5.4	Environmental Precautions <ul style="list-style-type: none">– Basic Impact mitigations to be in place during construction. The BIA (Basic Impact Analysis) will be provided to the successful bidder upon award.
6.0	Questions and Answers
6.1	– Questions should be sent to the contracting officer, refer to SI02 of the Invitation to Tender. The Q&A from this meeting will also be posted on the BuyandSell.
7.0	Meeting Adjourned

5. Questions and Answers

Q1. There is insufficient information provided in drawings for armour stone & rip rap. Unit of measurement is lump sum in unit price table. It is difficult to judge the exact or nearby quantity. Please provide adequate details on this issue.

A1. The quantity is not identified but is limited to possible material in the existing pier. (we don't know how much of the material is boulders, rip rap or granular fill.) The intent indicated in section 35 31 and 01 11 00 1.4.16 is to place all suitable reclaimed Armour Stone and Rip Rap material at the toe of the SSP cells. We will issue an amendment drawing indicating the areas and limits of where the Rip Rap and Armour stone is to be placed.

Solicitation No.:
5P468-21-0063/A

Amendment No.:
002

Contracting Authority:
Jaime Creaser

Client Reference No.:
2061

Title:
Tobey Dock Reconstruction, Georgian Bay Islands National Park

Q2. Can you please share photos of the site so we have a realistic idea of the conditions?

A2. Photos of the site will be shared in an amendment after the bidders' conference (see folder DSP 002 5P468-21-0063).

Q3. What's the accommodation for labourers on site there?

A3. In the park itself, we have camping and cabins. The contractor would be responsible for their own accommodations. The park is not making any provisions for that. Traditionally, we have recommended contractors stay in the Midland area or Honey Harbour/Port Severn.

Q4. How many Contractors are in the call today?

A4. It's an optional bidders conference, so it is not mandatory for all bidders to attend. Post-meeting note: three (3) Contractors were in fact on the call, not two (2).

Q5. When is camping and cabins available to reserve until?

A5. Visitor facilities are open up until and including Thanksgiving weekend.

Q6. Is there any soil report available for the site so we know the refusal of the sheet piling? I'm concerned with soil conditions; do we excavate until it's clear - but that can leave you without any toe material. Especially in cell 3, is there a theory in place to overcome this without digging out the toe to get the sheet to the correct grade?

A6. Most of the lakebed is sand, at least 1.5m of depth of penetration into the material. The only part that we know where there is cobble is around the end of Cell 3, it's just a matter of shifting 1 or 2 out of the way. Part of the contract also includes a requirement for the Contractor to drive test piles.

Q7. Is there a deadline to submit questions?

A7. Refer to SI02 of the Invitation to Tender.

Q8. What type of floats are currently being used? Must the same floatation floats be used?

A8. The existing floating dock is not changing; it is only being relocated. The existing concrete anchors are to be relocated.

Q9. Are there any specifications for the timber used in the existing deck, as we might need to replace some sections when relocating?

A9. None of the existing timber deck is being reclaimed or reused. Only the existing ramp to the floating dock is to be removed and installed at the east end of Cell 3.

Q10. Will a soil report be issued?

A10. No, the Contractor is required to install test piles as indicated in the documents, to confirm the embedment and length of piles.

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED