

| | | |
|--|----------------------|--|
| Channel Re-Dredging Garnish, NL R.118077.001 | TEMPORARY FACILITIES | Section 01 50 00 Page 1 2021-07-07 |
|--|----------------------|--|

- | | | |
|--|----|--|
| <u>1.1 ACCESS</u> | .1 | Provide and maintain adequate access to project site. |
| | .2 | Maintain access roads for duration of contract and make good damage resulting from Contractor's use of roads. |
| <u>1.2 CONTRACTOR'S SITE OFFICE</u> | .1 | Be responsible for and provide own site office, if required, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative. |
| <u>1.3 SANITARY FACILITIES</u> | .1 | Provide sanitary facilities for work force in accordance with governing regulations and ordinances. |
| | .2 | Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition. |
| <u>1.4 POWER</u> | .1 | Arrange, pay for and maintain temporary electrical power supply in accordance with governing regulations and ordinances. |
| | .2 | Supply and install all temporary facilities for power such as pole lines and underground cables to approval of local power supply authority. |
| <u>1.5 WATER SUPPLY</u> | .1 | Arrange, pay for and maintain temporary water supply in accordance with governing regulations and ordinances. |
| <u>1.6 CONSTRUCTION SIGN AND NOTICES</u> | .1 | Contractor or subcontractor advertisement signboards are not permitted on site. |
| | .2 | Only notices of safety or instructions are permitted on site. |

- .3 Safety and Instruction Signs and Notices:
 - .1 Signs and notices for safety and instruction shall be in both official languages.
- .4 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of off-site on completion of project or earlier if directed by Departmental Representative.

1.7 REMOVAL OF
TEMPORARY
FACILITIES

- .1 Remove temporary facilities from site when directed by Departmental Representative.