

Wharf Construction
Bay De Verde, NL
P/N: 723237

Page 2
2021-04-14

2.2 EQUIPMENT
IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 01 - Common Work Results - Electrical.
- .2 Indicate name of load controlled on size 4 nameplate.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Install disconnect switches complete with fuses as indicated.