

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Remove existing wood dock structure, office, active service pole, inactive service pole, miscellaneous poles, small armour stone and scattered boulders in footprint of new laydown area. Contractor shall coordinate with NL Hydro prior to and during removal of active service pole at existing trailer.

1.2 GENERAL
REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.

- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.
- .4 Removal of floating debris from water shall not be carried out utilizing designated safety boat. Contractor shall use separate vessel for debris cleaning, leaving the designated safety boat available for emergency operations at all times.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.
- .3 For all locations where existing coping is designated for removal, all existing machine bolts shall remain.

3.3 DISPOSAL OF
MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site. Provide consent letter from disposal site operator and provide weigh bills of material brought to site to Departmental Representative. Refer to Regulatory Approvals in Appendices.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- .3 All creosote timbers shall be transported and disposed of at the approved waste disposal facility.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.