

Part 1 General

1.1 Reference standards

- .1 CSA Group (CSA)
 - .1 CSA S350-M1980 (R2003), Code of Practice for Safety in Demolition of Structures.
- .2 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Assessment Act (CEAA), 2012
 - .2 Canadian Environmental Protection Act (CEPA), 2012
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34
 - .2 Hazardous Materials Information Review Act, 1985
- .3 National Fire Protection Association (NFPA)
 - .1 NFPA 241 - 96, Standard for Safeguarding Construction, Alteration, and Demolition Operations
- .4 National Research Council Canada (NRC)
 - .1 National Building Code of Canada 2015 (NBC).
 - .2 National Fire Code of Canada 2015 (NFC).
- .5 Underwriters' Laboratories of Canada (ULC)

1.2 Definitions

- .1 Demolition: rapid destruction of building following removal of hazardous materials.
- .2 Hazardous Materials: dangerous substances, dangerous goods, hazardous commodities and hazardous products, may include but not limited to: asbestos PCB's, CFC's, HCFC's poisons, corrosive agents, flammable substances, ammunition, explosives, radioactive substances, or other material that can endanger human health or wellbeing or environment if handled improperly.
- .3 Waste Management Coordinator (WMC): Contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .4 Construction Waste Management Plan (CWM Plan): Written plan addressing opportunities for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19- Construction Waste Management and Disposal.
- .5 Construction Waste Management Report (CWM Report): Written report identifying actual materials that formed CWM Plan for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19- Construction Waste Management and Disposal

1.3 Administrative requirements

- .1 Scheduling:
 - .1 Employ necessary means to meet project time lines without compromising specified minimum rates of material diversion.
 - .2 In event of unforeseen delay notify Departmental Representative.

1.4 Action and informational submittals

- .1 Action Submittals: Provide the following submittals before starting any work of this Section:
 - .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Schedule of Demolition Activities: Coordinate with Section 01 32 16.16- Construction Progress Schedule.

1.5 Quality assurance

- .1 Regulatory Requirements: Ensure Work is performed in compliance with CEPA, CEAA, TDGA, applicable Provincial/Territorial and Municipal regulations.
- .2 Comply with hauling and disposal regulations of Authority Having Jurisdiction.
- .3 Standards: Comply with ANSI A10.6 and NFPA 241.

1.6 Site conditions

- .1 If material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
 - .1 Proceed only after receipt of written instructions have been received from Departmental Representative.
- .2 Notify Departmental Representative before disrupting building access or services.

Part 2 Products - Not Used

Part 3 Execution

3.1 Examination

- .1 Survey existing conditions and correlate with requirements indicated to determine extent of demolition required.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Review Project Record Documents of existing construction provided by Departmental Representative.
- .4 Departmental Representative does not guaranty that existing conditions are the same as those indicated in Project Record Documents.
- .5 Inventory and record the condition of items being removed and salvaged.
- .6 When unanticipated mechanical, electrical, or structural elements are encountered, investigate and measure the nature and extent of the element.
- .7 Verify that hazardous materials have been remediated before proceeding with demolition operations.

3.2 Preparation

- .1 Protection of In-Place Conditions:
 - .1 Keep noise, dust, and inconvenience to occupants to minimum.
 - .2 Protect building systems, services and equipment.

- .3 Provide temporary dust screens, covers, railings, supports and other protection as required.
- .4 Do Work in accordance with Section 01 35 29.06 - Health and Safety Requirements.
- .2 Demolition/Removal:
 - .1 Demolish items as indicated.
 - .2 Evacuate all refrigerant from system prior to removal of chiller. Dispose of captured refrigerant in accordance with Section 01 74 19 - Waste Management and Disposal.
 - .3 Removal of the existing chiller and refrigerant to be completed and in accordance with FHR 2003 Federal Halocarbon Regulations by a certified technician.
 - .4 At end of each day's work, leave Work in safe and stable condition.

3.3 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 00 - Cleaning.
- .3 Refer to demolition drawings and specifications for items to be salvaged for reuse.
- .4 Waste Management: separate waste materials for recycling or reuse in accordance with Section 01 74 19 - Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

Ω End of Section