

## **ADDENDUM NO. 4**

### **Drawings**

1. Drawing E100:  
Delete note:  
“Temporary 3#6 RW90AL Overhead feeder for Staff trailers power. This temporary service shall remain operational for the entire duration until the new construction site is ready for complete switchover.”  
And replace with:  
“Temporary 3#6 RW90AL Overhead feeder for Staff trailers power. This temporary service shall remain operational for the entire duration until the new construction site is ready for complete switchover. Hook up should be within 2 weeks of award of the contract.”
2. Drawing E100, Keynote 2:  
Delete reference to “40A-2P” and replace with “60A-2P”.
3. Drawings E100, Keynote 6:  
Add the following to the existing keynote:  
“Allow for coordination with local Hydro utility supplier to disconnect and re-connecting of existing primary feeders via new pole load break switch through to primary side of the new transformer.”
4. Drawing E401:  
Add keynote #6 to read: “AT6 data cables in garage shall be terminated in the Living Quarters building SSC room telecom rack via below grade duct bank.”
5. Drawing A022:  
For Doors D203 and D205:
  - delete ‘WD’ under Frame Material column,
  - delete ‘PT’ under Frame Material Finish column,
  - delete ‘PT’ under Door Material Finish
  - Replace all noted deletions above with ‘-’.These doors and frames are part of demountable partition system.
6. Drawing A502:  
Add note to read: Waterproofing, drainage board and concrete faced insulation to be applied to the perimeter grade beam foundation walls of the entire Garage/Utility building.
7. Drawing A403:  
For Garage/Utility Building elevations, add arrow notes at portion of exposed grade beam foundation wall below pre-finished metal cladding to read: ‘Concrete faced insulation’.

### **Specifications**

1. 08 80 00:  
Subsection 2.2.5: for Glass Type 4, add to end of sentence: ‘and demountable glazed partitions’.

**END OF ADDENDUM NO. 4**