

R.116306.001
NAFC Paving Update
St. John's, NL

2021-06-25

PART 1 - GENERAL

1.1 GENERAL

- .1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
- .2 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .3 Prevent accumulation of wastes which create hazardous conditions.
- .4 Provide adequate ventilation during use of volatile or noxious substances.

1.2 CLEANING DURING CONSTRUCTION

- .1 Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis.
- .2 Provide on-site garbage containers for collection of waste materials and debris.
- .3 Remove waste materials and debris from site on a daily basis.

1.3 FINAL CLEANING

- .1 In preparation for acceptance of the Work perform final cleaning. Contractor required to complete a "rake" cleaning of the footprint of each work area, ensuring all loose debris, remnants, etc. are removed to the satisfaction of the Departmental Representative.