



Certificate of Authorization  
**DGH Engineering Ltd.**

No. 540      Date: 2021-11-09

DEMOLITION NOTES:

1. ISOLATE AND DRAIN COOLING TOWER AND WATER SIDE FLUID.
2. ISOLATE CHILLED WATER-COOLING SYSTEM.
3. REMOVE AND RECYCLE ALL EXISTING REFRIGERANT FROM CHILLER.
4. COORDINATE DISCONNECTIONS AND EQUIPMENT REMOVAL WITH CHILLER SCHEMATIC.
5. REMOVE INNOTECH CONTROLLERS FOR THE FOLLOWING PANELS: 104, 105, 106.
6. ISOLATE AND REMOVE PUMPS P-3, P-4, P-5, AND P-6.
7. DISCONNECT AND REMOVE EXISTING COOLING TOWER.
8. DISCONNECT AND REMOVE EXISTING CHILLER.
9. DRAIN ALL SUPPLY AND RETURN PIPING IN CRAWLSPACE TO AND FROM AHU-1, AHU-2, AND AHU-3 FROM CHILLER.
10. DISCONNECT AND REMOVE EXISTING SUPPLY PIPING IN CRAWLSPACE TO AND FROM AHU-1, AHU-2, AND AHU-3 FROM CHILLER.
11. DRAIN ALL CHEMICAL FEEDER PIPING, INCLUDING MAKEUP WATER PIPING.
12. DISCONNECT CHEMICAL FEEDER PIPING, TANKS, PUMPS, AND ASSOCIATED CONTROLS. PIPING TO BE RE-USED FOR NEW CHEMICAL FEEDER IN NEW LOCATION.

UPDATED DEMOLITION NOTES ON SHEET D102



**LEGEND**

ITEM	SYMBOL	REMARKS
FITTING - WATER STRAINER		

UPDATED LEGEND ITEM ON SHEETS D104 & H104



Project title

**AAFC MRDC: CHILLER  
& BOILER UPGRADE  
(CHILLER SCOPE ONLY)**

Drawing title

**ADDENDUM 2  
UPDATED NOTE  
& LEGEND**

Drawn by

**RTD**

Designed by

**LL**

Approved by

**JKN**

PWGSC Project Manager

**OWEN VAN WALLEGHEM**

Project no.

**R.111908**

Date

2021-11-09

Sheet

**ADD-2**  
1 OF 1

Revision

**R00**