

Date : December 16, 2021
Projet : Public Services and Procurement Canada
Construction of a new observation tower
Lake Saint-François National Wildlife Area
R.094850

ADDENDUM N° 01

All tenderers shall peruse the precisions, additional information and modifications provided in this Addendum; the additional information and this Addendum become integral part of the plans and specifications. This Addendum includes 2 pages of text and 11 plan sheets (S00 to S10).

PLANS

1. Ref. : General
 - a. Sheet S00 to S10 are reissued with the seal and signature of the engineers.
2. Ref. : Plan sheet S01/S10
 - a. A machinery traffic ban has been added on sheet 01.

TECHNICAL SPECIFICATIONS

3. Ref. : Seals page
 - a. The page is reissued with the seal and signature of the engineers
4. Ref. : Section 01 11 01 – Work related general information
 - a. Article 1.5.2 is amended as follows:

“ .2 The Contractor will need to determine a working method that will limit the traffic flow. The construction zone access must minimize the disturbance of the premises and the environment. **Access to the site must be maintained at all times for the public.** “
 - b. article 1.5.5 is added with the following description :

“ .5 The Contractor shall use the Access Path provided for this purpose to enter the Work Area. The following constraints must be met:

 - .1 Machinery and equipment on crawler moving on the trail shall not exceed a maximum weight of 6800 kg loading included.
 - .2 Machinery and equipment on wheels moving on the trail shall not exceed a maximum weight of 4000 kg loading included.
 - .3 Material may not be dragged to the ground at any time.
 - .4 Machinery and equipment moving on the trail shall not exceed a maximum width of 2.2 m. “
5. Ref. : Section 01 14 00 – Work restrictions
 - a. Article 1.2.1.8 is deleted.
6. Ref. : Section 01 32 16.07 – Construction progress schedule
 - a. Article 1.4.2.6 is added with the following description :

“ .6 Exclusion fence installation : no later than march 1st 2022. “

7. Ref. : Section 01 35 43 – Environmental procedures

a. Article 1.12.2 is amended as follows:

*“ .2 **No later than March 1st 2022**, the contractor must put in place an exclusion fence (sediment barrier, the lower part of which is backfilled). This barrier must be installed at the outer perimeter of the site fence as well as on both side of the access road located **between the parking lot and the work area**, to the satisfaction of the representative of the ministry. “*

b. Article 1.12.2.1 is added with the following description :

“ .1 The Contractor shall ensure that the exclusion fence does not obstruct access to the site by the public. “

8. Ref. : Section 01 52 00 – Construction facilities

a. Article 1.3.2 is amended as follows:

*“ .2 **All areas subject to the circulation of machinery must be covered with a geotextile membrane and 150 mm of gravel to prevent tracking of mud. This requirement also applies to the access road between the parking lot and the work area.** “*

b. Article 1.7.3 is amended as follows:

*“ .3 The contractor must at all times **limit their use of the parking lot to four (4) parking spaces. The rest of the parking lot must be exclusively dedicated to site users.** “*