PSPC Ontario	METAL LOCKERS	Section 10 51 13
Region Project		Page 1
Number R.100644.001	Document Set 2	2021-08-31

## PART 1 - GENERAL

#### 1.1 REFERENCE STANDARDS

- .1 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-44.40-01, Steel Clothing Locker.

#### 1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit submittals in accordance with Section 01 33 00.
- .2 Product Data:
  - .1 Provide manufacturer's printed product literature and data sheets for metal lockers and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
  - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
  - .2 Indicate on drawings: type and class of locker, thicknesses of metal, fabricating and assembly methods, assembled banks of lockers, tops, hooks, shelves, bases, trim, end/back panels, doors, handles, locking method, finishes.
- .4 Samples:
  - .1 Submit duplicate 50  $\times$  50 mm samples of colour and finish on actual base metal.
  - .2 Samples will be returned for inclusion into work.

## 1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
  - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
  - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
  - .2 Store and protect metal lockers from nicks, scratches, and blemishes.
  - .3 Replace defective or damaged materials with new.

## PART 2 - PRODUCTS

## 2.1 MANUFACTURED UNITS

- .1 Lockers: to CAN/CGSB-44.40, Type 2 Double tier locker, Class 1 One complete locker, freestanding.
  - .1 Size: 305 mm wide x 380 mm deep x 1524 mm high, steel thickness No. 20

PSPC Ontario	METAL LOCKERS	Section 10 51 13
Region Project		Page 2
Number R.100644.001	Document Set 2	2021-08-31

MSG.

- .2 Assembly: welded construction.
- .3 Top: sloped.
- .4 Doors: one-piece double-wall envelope construction, steel thickness No .20 MSG.
- .5 Door handle: recessed handle, steel with bright chromium finish.

#### 2.2 ACCESSORIES

- .1 Locking system: supplied by locker manufacturer.
- .2 Options: to CAN/CGSB-44.40, number plates, manufacturer's standard coat hooks, metal zinc-plated finish.
- .3 Integrated bench: Provide manufacturer's standard integral bench, 1220 mm wide x 292 mm deep, mounted to locker framing at height of 470 mm.

#### PART 3 - EXECUTION

## 3.1 EXAMINATION

- .1 Verification of Conditions: verify conditions of substrates and surfaces to receive metal lockers previously installed under other Sections or Contracts are acceptable for product installation in accordance with manufacturer's instructions prior to metal locker installation.
- .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval from Departmental Representative.

#### 3.2 INSTALLATION

- .1 Assemble and install lockers in accordance with manufacturer's written instructions.
- .2 Securely fasten lockers to grounds and nailing strips.
- .3 Install wall trim around recessed locker banks.
- .4 Install filler panels where indicated and where obstructions occur.
- .5 Install finished end panels to exposed ends of locker banks.
- .6 Install locker numbers locks.
- .7 Install integrated bench to locker framing.

PSPC Ontario	METAL LOCKERS	Section 10 51 13
Region Project		Page 3
Number R.100644.001	Document Set 2	2021-08-31

# 3.3 ADJUSTING

- .1 Adjust metal lockers for correct function and operation in accordance with manufacturer's written instructions.
- .2 Lubricate moving parts to operate smoothly and fit accurately.

# 3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 00.
  .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 00.

# 3.5 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by metal locker installation.