
Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 01 32 00 - Construction Progress Documentation

Page 1 of 2

PART 1 **GENERAL**

1.1 **RELATED SECTIONS**

- .1 Section 01 77 00 - Closeout Procedures.

1.2 **SCHEDULES REQUIRED**

- .1 Submit schedules as follows:
 - .1 Construction Progress Schedule.
 - .2 Submittal Schedule for Shop Drawings.
 - .3 Shutdown or closure activity.

1.3 **FORMAT**

- .1 Prepare schedule in form of a horizontal bar chart.
- .2 Provide a separate bar for each major item of work, trade or operation.
- .3 Split horizontally for projected and actual performance.
- .4 Provide horizontal time scale identifying first work day of each week.
- .5 Format for listings: chronological order of start of each item of work.

1.4 **SUBMISSION**

- .1 Submit initial format of schedules within 15 working days after award of Contract.
- .2 Submit schedules in electronic format as PDF files.
- .3 Submit one opaque reproduction, plus 2 copies to be retained by Departmental Representative.
- .4 Departmental Representative will review schedule and return review copy within 10 days after receipt.
- .5 Resubmit finalized schedule within 7 days after return of review copy.
- .6 Submit revised progress schedule with each application for payment.
- .7 Distribute copies of revised schedule to:
 - .1 Job site office.
 - .2 Subcontractors.
 - .3 Other concerned parties.
- .8 Instruct recipients to report to Contractor within 10 days, any problems anticipated by timetable shown in schedule.

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 01 32 00 - Construction Progress Documentation

Page 2 of 2

1.5 CRITICAL PATH SCHEDULING

- .1 Include complete sequence of demolition activities, including provisions for removal of lead based exterior peeling/flaking paint and interior asbestos. Include schedule for final clean-up including provisions for rock/gravel fill and granular base to blend with surrounding topography and structures.
- .2 Show projected percentage of completion of each item as of first day of month.
- .3 Indicate progress of each activity to date of submission schedule.
- .4 Show changes occurring since previous submission of schedule:
 - .1 Major changes in scope.
 - .2 Activities modified since previous submission.
 - .3 Revised projections of progress and completion.
 - .4 Other identifiable changes.
- .5 Provide a narrative report to define:
 - .1 Problem areas, anticipated delays, and impact on schedule.
 - .2 Corrective action recommended and its effect.
 - .3 Effect of changes on schedules of other prime contractors.

1.6 SUBMITTALS SCHEDULE

- .1 Include schedule for submitting shop drawings.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

END OF SECTION