
Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 1 of 6

PART 1 **GENERAL**

1.1 **RELATED SECTIONS**

- .1 Section 01 33 00 – Submittal Procedures.
- .2 Section 01 35 43 - Environmental Procedures.
- .3 Section 01 56 00 - Temporary Barriers and Enclosures.
- .4 Section 02 41 16 – Structure Demolition

1.2 **REFERENCES**

- .1 Codes and standards referenced in this section refer to the latest edition thereof.
- .2 American Society for Testing and Materials (ASTM).
 - .1 ASTM C117, Standard Test Method for Material Finer Than 0.075 mm (No. 200) Sieve in Mineral Aggregates by Washing.
 - .2 ASTM C136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - .3 ASTM D422, Standard Test Method for Particle-Size Analysis of Soils.
 - .4 ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³) (600 kN-m/m³).
 - .5 ASTM D1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³) (2,700 kN-m/m³).
 - .6 ASTM D4318, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- .3 Canadian General Standards Board (CGSB).
 - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
 - .2 CA/CGSB-8.2, Sieves, Testing, Woven Wire, Metric

1.3 **DEFINITIONS**

- .1 Unclassified excavation: excavation of deposits of whatever character encountered in work.
- .2 Topsoil: material capable of supporting good vegetative growth and suitable for use in top dressing, landscaping and seeding.
- .3 Waste material: excavated material unsuitable for use in work or surplus to requirements.
- .4 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of work.

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 2 of 6

.5 Unsuitable materials:

- .1 Weak and compressible materials under excavated areas.
- .2 Frost susceptible materials under excavated areas.
- .3 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136: Sieve sizes to CAN/CGSB-8.1.

<u>Sieve Designation</u>	<u>%Passing</u>
2.00 mm	100
0.10 mm	45-100
0.02 mm	10-80
<u>0.005 mm</u>	<u>0-45</u>

- .2 Coarse grained soils containing more than 20% by mass passing 0.075 mm sieve.

1.4 SUBMITTALS

- .1 Inform Departmental Representative/Architect at least 4 weeks prior to commencing work, of proposed source of fill materials and provide access for sampling.
- .2 Submit 70 kg samples of type of fill specified including representative samples of excavated material.
- .3 Ship samples as directed by Departmental Representative/Architect in tightly closed containers to prevent contamination.

1.5 QUALITY ASSURANCE

- .1 Submit design and supporting data at least 2 weeks prior to commencing work.
- .2 Design and supporting data submitted to bear stamp and signature of qualified professional Departmental Representative registered or licensed in the province of Newfoundland and Labrador.
- .3 Keep design and supporting data on site.
- .4 Do not use soil material until written report of soil test results are reviewed and approved by Departmental Representative/Architect.

1.6 EXISTING CONDITIONS

- .1 Buried services:
 - .1 Before commencing work verify location of buried services on and adjacent to site.

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 3 of 6

- .2 Arrange with appropriate authority for relocation of buried services that interfere with execution of work: pay costs of relocating services.
- .3 Remove obsolete buried services within 2 m of foundations: cap cut-offs.
- .4 Size, depth and location of existing utilities and structures as indicated are for guidance only. Completeness and accuracy are not guaranteed.
- .5 Prior to commencing excavation work, notify Departmental Representative or authorities having jurisdiction to establish location and state of use of buried utilities and structures. Contractor responsible for all underground utility locates.
- .6 Confirm locations of buried utilities by careful test excavations.
- .7 Maintain and protect from damage, water, sewer, gas, electric, telephone and other utilities and structures encountered as indicated.
- .8 Where utility lines or structures exist in area of excavation, obtain direction of Departmental Representative/Architect before removing or re-routing.
- .9 Record location of maintained, re-routed and abandoned underground lines.
- .10 Confirm locations of recent excavations adjacent to area of excavation.

PART 2

PRODUCTS

2.1

MATERIALS

- .1 Backfill Type 3 material (referred to on the drawings as rock/gravel fill): properties to the following requirements:
 - .1 Crushed, pit run or screened stone, gravel or sand.
 - .2 Gradations to be within limits specified when tested to ASTM C136 and ASTM C117. Sieve sizes to CAN/CGSB-8.1.

Sieve Designation	%Passing	
	<u>Type1</u>	<u>Type2</u>
75 mm	-	100
50 mm	-	-
37.5 mm	-	-
25 mm	100	-
19 mm	75-100	-
12.5 mm	-	-
9.5 mm	50-100	-
4.75 mm	30-70	22-85
2.00 mm	20-45	-
0.425 mm	10-25	5-30
0.180 mm	-	-
<u>0.075 mm</u>	<u>3-8</u>	<u>0-10</u>

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 4 of 6

PART 3 **EXECUTION**

3.1 **SITE PREPARATION**

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.

3.2 **PREPARATION/PROTECTION**

- .1 Protect existing features in accordance with Section 01 56 00 - Temporary Barriers and Enclosures and applicable local regulations.
- .2 Keep excavations clean, free of standing water, and loose soil.
- .3 Where soil is subject to significant volume change due to change in moisture content, cover and protect to Departmental Representative's approval.
- .4 Protect natural and man-made features required to remain undisturbed. Unless otherwise indicated or located in an area to be occupied by new construction, protect existing trees from damage. Protect buried services that are required to remain undisturbed.

3.3 **STOCKPILING**

- .1 Stockpile fill materials in areas designated by Departmental Representative. Stockpile granular materials in manner to prevent segregation.
- .2 Protect fill materials from contamination.

3.4 **COFFERDAMS, SHORING, BRACING AND UNDERPINNING**

- .1 Maintain sides and slopes of excavations in safe condition by appropriate methods and in accordance with Section 01 35 30 - Health and Safety Requirements and Occupational Health and Safety Act for the Province of Newfoundland and Labrador.
- .2 Obtain permit from authority having jurisdiction for temporary diversion of water course.

3.5 **DEWATERING AND HEAVE PREVENTION**

- .1 Keep excavations free of water while work is in progress.
- .2 Submit for Departmental Representative review details of proposed dewatering
- .3 Avoid excavation below groundwater table if quick condition or heave is likely to occur. Prevent piping or bottom heave of excavations by groundwater lowering, sheet pile cut-offs, or other means.
- .4 Protect open excavations against flooding and damage due to surface run-off.

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 5 of 6

- .5 Dispose of water in accordance with Section 01 35 43 - Environmental Procedures and in manner not detrimental to public and private property, or any portion of work completed or under construction.
- .6 Provide flocculation tanks, settling basins, or other treatment facilities to remove suspended solids or other materials before discharging to storm sewers, water courses or drainage areas.

3.6 EXCAVATION

- .1 Excavate as required to remove underground foundations or as otherwise directed by Departmental Representative.
- .2 Remove concrete, masonry, paving, walks, demolished foundations and rubble and other obstructions encountered during excavation in accordance with Section 02 41 13 - Selective Site Demolition.
- .3 Keep excavated and stockpiled materials a safe distance away from edge of trench as directed by Departmental Representative.
- .4 Restrict vehicle operations directly adjacent to open trenches.
- .5 Dispose of surplus and unsuitable excavated material off site.
- .6 Do not obstruct flow of surface drainage or natural watercourses.
- .7 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .8 Notify Departmental Representative when bottom of excavation is reached.
- .9 Obtain Departmental Representative approval of completed excavation.
- .10 Remove unsuitable material from trench bottom to extent and depth as directed by Departmental Representative.

3.7 FILL TYPES AND COMPACTION

- .1 Use Type 1 or Type 2 fill (referred to on the drawings as rock/gravel fill) as indicated or specified below.

3.8 BACKFILLING

- .1 Vibratory compaction equipment: approved by Departmental Representative.
- .2 Where possible, areas to be backfilled to be free from debris, snow, ice, water and frozen ground. Coordinate with Departmental Representative.

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 31 23 33.01 – Excavating, Trenching and Backfilling

Page 6 of 6

- .3 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.

3.9 RESTORATION

- .1 Upon completion of work, remove waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.

END OF SECTION