

---

**Decommissioning, Demolition and Site Restoration SSB HQ**  
**Southside Road, St. John's, NL**  
**Project No. R.111146.001**

---

2020/12/01      Section 01 74 21 – Construction/Demolition Waste Management and Disposal      Page 1 of 3

---

**PART 1**      **GENERAL**

**1.1**      **DEFINITIONS**

- .1      Demolition Waste Audit (DWA): Relates to actual waste generated from project.
- .2      Materials Source Separation Program (MSSP): Consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .3      Recyclable: Ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse by others.
- .4      Recycle: Process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .5      Recycling: Process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .6      Reuse: Repeated use of product in same form but not necessarily for same purpose. Reuse includes:
  - .1      Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
  - .2      Returning reusable items including pallets or unused products to vendors.
- .7      Salvage: Removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .8      Separate Condition: Refers to waste sorted into individual types.
- .9      Source Separation: Acts of keeping different types of waste materials separate beginning from first time they became waste.

**1.2**      **MATERIALS SOURCE SEPARATION PROGRAM (MSSP)**

- .1      Prepare MSSP and have ready for use prior to project start-up.
- .2      Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by authorities having jurisdiction.
- .3      Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4      Provide containers to deposit reusable and recyclable materials.

---

**Decommissioning, Demolition and Site Restoration SSB HQ**  
**Southside Road, St. John's, NL**  
**Project No. R.111146.001**

---

2020/12/01      Section 01 74 21 – Construction/Demolition Waste Management and Disposal      Page 2 of 3

---

- .5      Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .6      Locate separated materials in areas which minimize material damage.
- .7      Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.
- .1      Transport to recycling facility.

**1.3                  STORAGE, HANDLING AND PROTECTION**

- .1      Unless specified otherwise, materials for removal become Contractor's property.
- .2      Protect, stockpile, store and catalogue salvaged items.
- .3      Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to approved facility.
- .4      Separate and store materials produced during dismantling of structures in designated areas.
- .5      Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by approved facilities.
- .1      On-site source separation is recommended.

**1.4                  DISPOSAL OF WASTES**

- .1      Do not bury rubbish or waste materials.
- .2      Do not dispose of any waste into waterways, storm, or sanitary sewers.
- .3      Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .4      Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

**1.5                  USE OF SITE AND FACILITIES**

- .1      Execute work with least possible interference or disturbance to normal use of premises.
- .2      Provide security measures approved by Departmental Representative.

**1.6                  SCHEDULING**

- .1      Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

---

**Decommissioning, Demolition and Site Restoration SSB HQ**  
**Southside Road, St. John's, NL**  
**Project No. R.111146.001**

---

2020/12/01      Section 01 74 21 – Construction/Demolition Waste Management and Disposal      Page 3 of 3

---

**PART 2**            **PRODUCTS (NOT APPLICABLE)**

**PART 3**            **EXECUTION**

**3.1**                **APPLICATION**

- .1            Handle waste materials not salvaged, or recycled in accordance with appropriate regulations and codes.

**3.2**                **CLEANING**

- .1            Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2            Clean-up work area as work progresses.
- .3            Source separate materials to be recycled into specified sort areas.

**3.3**                **DIVERSION OF MATERIALS**

- .1            Separate materials to be recycled or turned over to the Departmental Representative, from general waste stream and stockpile in separate piles or containers, as reviewed by Departmental Representative and consistent with applicable fire regulations.
  - .1            Mark containers or stockpile areas.
  - .2            Provide instruction on disposal practices.

**END OF SECTION**