

---

**Decommissioning, Demolition and Site Restoration SSB HQ**  
**Southside Road, St. John's, NL**  
**Project No. R.111146.001**

2021/12/01

Section 22 05 13 – Mechanical Removals

Page 1 of 1

---

**PART 1**      **GENERAL**

**1.1**      **DESCRIPTION OF WORK**

- .1      In general, work of this section consists of all mechanical, materials and associated equipment indicated to be removed.
- .2      Demolition work to be phased and coordinated with Departmental Representative.

**1.2**      **REFERENCE STANDARDS**

- .1      All removal or modification work of mechanical construction to be done in accordance with the safety standards outlined in Canadian Standards Association (CSA):
  - .1      CAN/CSA-B139, Installation Code for Oil Burning Equipment.
  - .2      The Gasoline regulations “Environment and Climate Change Canada”.

**1.3**      **DISPOSAL**

- .1      The Departmental Representative shall have first right of refusal of all materials and equipment removed under work of this section.
- .2      All materials and equipment refused by the Departmental Representative will become the property of the contractor and will be removed from site.

**PART 2**      **PRODUCTS**    **NOT APPLICABLE TO THIS SECTION**

**PART 3**      **EXECUTION**

**3.1**      **GENERAL**

- .1      Schedule all removal of work with Departmental Representative.

END OF SECTION