
Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2020/12/01

Section 02 41 13 - Selective Site Demolition

Page 1 of 3

PART 1 **GENERAL**

1.1 **SECTIONS INCLUDES**

- .1 Methods and procedures for demolishing, salvaging, recycling and removing sitework items designated to be removed in whole or in part, and for backfilling resulting trenches and excavations.

1.2 **RELATED SECTIONS**

- .1 Section 01 33 00 – Submittal Procedures
- .2 Section 01 35 29.06 - Health and Safety Requirements
- .3 Section 01 35 43 - Environmental Procedures
- .4 Section 01 45 00 - Quality Control
- .5 Section 01 74 19 – Construction/Demolition Waste Management and Disposal.

1.3 **SUBMITTALS**

- .1 Shop drawings
 - .1 Submit for approval drawings, diagrams or details showing sequence of demolition work and supporting structures and underpinning, where required by authorities having jurisdiction.
- .2 Hazardous Materials: provide description of Hazardous Materials and Notification of Filing with proper authorities prior to beginning of Work as required.
- .3 Submit plan indicating:
 - .1 Descriptions of and anticipated quantities of materials to be salvaged, reused, recycled and landfilled.
 - .2 Schedule of selective demolition.
 - .3 Number and location of dumpsters.
 - .4 Anticipated frequency of tippage.
- .4 Submit copies of certified weigh bills, bills of landing from authorized disposal sites and reuse and recycling facilities for material removed from upon request from Departmental Representative/Architect.

1.4 **QUALITY ASSURANCE**

- .1 Convene pre-installation meeting one week prior to beginning work of this section to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.

Decommissioning, Demolition and Site Restoration SSB HQ

Southside Road, St. John's, NL

Project No. R.111146.001

2020/12/01

Section 02 41 13 - Selective Site Demolition

Page 2 of 3

- .3 Co-ordination with building subtrades.
- .2 Arrange for site visit with Departmental Representative/Architect to examine existing site conditions adjacent to demolition work, prior to start of Work.
- .3 Hold project meetings every month as a minimum and weekly when work has the potential to affect yard operations.
 - .1 Ensure key personnel, site supervisor, project manager, subcontractor representatives attend.

1.5 SITE CONDITIONS

- .1 In all circumstances ensure that demolition work does not adversely affect adjacent water courses groundwater and wildlife, or contribute to excess air and noise pollution.
- .2 Do not dispose, of waste or volatile materials such as mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers. Ensure proper transportation/disposal procedures are maintained throughout project.
- .3 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers, or onto adjacent properties.
- .4 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authorities.
- .5 Protect trees, plants and foliage on site and adjacent properties where indicated.

1.6 EXISTING CONDITIONS

- .1 Prior to start of any demolition work remove contaminated or hazardous materials as defined by authorities having jurisdiction from site and dispose of at designated disposal facilities

1.7 SCHEDULING

- .1 Employ necessary means to meet project time lines without compromising specified minimum rates of material diversion.
- .2 Notify Departmental Representative in writing when unforeseen delays occur.

Decommissioning, Demolition and Site Restoration SSB HQ

Southside Road, St. John's, NL

Project No. R.111146.001

2020/12/01

Section 02 41 13 - Selective Site Demolition

Page 3 of 3

PART 2 **PRODUCTS (NOT APPLICABLE)**

PART 3 **EXECUTION**

3.1 **PREPARATION**

- .1 Inspect site with Departmental Representative/Architect and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

3.2 **REMOVAL OPERATIONS**

- .1 Remove items as indicated.
- .2 Removal from site
 - .1 Interim removal of stockpiled material will be required by Departmental Representative, if it is deemed to interfere with operations at site.
- .3 Sealing
 - .1 Seal pipe ends and walls of manholes or catch basins as indicated. Securely plug to form watertight seal.
- .4 Backfill
 - .1 Backfill in areas as indicated

3.3 **RESTORATION**

- .1 Restore areas and existing works outside areas of demolition to match conditions of adjacent, undisturbed areas.
- .2 Use soil treatments and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.

3.4 **CLEAN UP**

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Use cleaning solutions and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.

END OF SECTION