

**PART 1**      **GENERAL**

**1.1**      **GENERAL**

- .1 Due to congested nature of site and traffic flow along Southside Road, contractor responsible for all signs, signals, control devices, traffic barriers, flares, lights and traffic signals, construction parking control, designated haul routes, etc., to ensure no impact to existing coast guard operations or vehicle traffic along Southside Road.
- .2 Traffic control plan: Submit a traffic control plan for approval to the Departmental Representative. At no times will double lane closure along Southside Road be permitted. Flagpersons within the working compound and along Southside Road will be required at all times when heavy equipment is operating.
- .3 Contractor's workers not permitted to park personal vehicles on site or within coast guard facility operations. No parking permitted along Southside Road.
- .4 Sidewalks have to remain open (overhead protection along sidewalks is required at the Contractor's expense, in accordance with City regulations).
- .5 Site of work is located adjacent to the main entrance to the CCG operational yard site (which is also used for emergency vehicle access).

**1.2**      **HAUL ROUTES AND SIGNS**

- .1 Establish haul routes for contractor's equipment, to approval of Departmental Representative. In all cases, confine construction traffic to designated haul routes and provide traffic control at critical areas of haul routes which minimizes interference with public traffic.
- .2 Where required, construct necessary traffic control devices for temporary signals required to complete the Work including loop detectors, traffic signal conduits, traffic signal wiring and crosswalk signals.
- .3 Install and operate traffic control signals to direct and maintain orderly traffic flow in areas under Contractor's control affected by Contractor's operations.
- .4 Departmental Representative may direct Contractor to make minor adjustments to traffic control signage to eliminate driver confusion and maintain orderly traffic flow during construction at no additional cost to the Departmental Representative.

---

**Decommissioning, Demolition and Site Restoration SSB HQ**

**Southside Road, St. John's, NL**

**Project No. R.111146.001**

2020/12/01

Section 01 55 26 – Traffic Control

Page 2 of 2

---

**PART 2**

**PRODUCTS (NOT APPLICABLE)**

**PART 3**

**EXECUTION (NOT APPLICABLE)**

**END OF SECTION**