



- DEMOLITION NOTES:**
- 1 REMOVE ALL PLUMBING FIXTURES ON THIS FLOOR. CONTRACTOR TO COORDINATE WITH DEPARTMENTAL REPRESENTATIVE REGARDING DISPOSAL OF PLUMBING FIXTURES.
  - 2 REMOVE ALL HYDRONIC HEATERS, VALVES, HEATING PIPING, THERMOSTATS, PNEUMATIC PIPING, CONTROL WIRING AND ASSOCIATED EQUIPMENT FROM THIS FLOOR.
  - 3 REMOVE ALL VENTILATION, DUCTWORK, FANS, DIFFUSERS CONTROLS, CONTROL WIRING AND ASSOCIATED EQUIPMENT FROM THIS FLOOR.
  - 4 REMOVE ALL PLUMBING, DOMESTIC HOT AND COLD PIPING, DRAINAGE PIPING, VENT PIPING, HOT WATER TANKS, SINKS, VALVES AND ASSOCIATED EQUIPMENT FROM THIS FLOOR.
- GENERAL NOTES:**
1. ALL LOCATIONS ARE TO BE CONSIDERED APPROXIMATE ONLY. CONFIRM ALL LOCATIONS ON SITE AND ADJUST AS REQUIRED.
  2. DRAWINGS ADAPTED FROM SCANNED ORIGINALS OF BUILDING DESIGN AND LAYOUT. DO NOT SCALE FROM DRAWINGS.
  3. COORDINATE WITH ALL OTHER TRADES.
  4. COMPLETION OF A DISMANTLING DECOMMISSIONING OR DESTRUCTION NOTICE" (WITH A COPY IN THE LOGBOOK ON SITE)
  5. DEMOLITION CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE REMOVAL AND DISCARDING OF ALL DEMOLITION WASTE INCLUDING ANY UNFORESEEN ITEMS WITHIN THE SCOPE OF WORK.
  6. DEMOLITION CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AFFECTING THE WORK.
  7. DEPARTMENTAL REPRESENTATIVES SHALL HAVE FIRST RIGHT OF REFUSAL ON ALL EQUIPMENT BEING REMOVED.



0	ISSUED FOR TENDER	16/12/21
revisions		date

project

**DECOMMISSIONING,  
DEMOLITION AND SITE  
RESTORATION SSB HQ  
SOUTHSIDE ROAD  
ST.JOHN'S, NL**

project

drawing

dessin

FOURTH LEVEL FLOOR PLAN  
— DEMOLITION LAYOUT

designed N.C.	conçu
date DECEMBER 2020	
drawn M.K.	dessiné
date DECEMBER 2020	
approved N.C.	approuvé
date DECEMBER 2020	
Tender	Soumission
PWGSC Project Manager	Administrateur de projets TPSCG
project number R.111146.001	no. du projet
drawing no. MD-5	no. du dessin