
Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2021/12/01

Section 26 05 13 – Electrical Removals

Page 1 of 2

PART 1 **GENERAL**

1.1 **DESCRIPTION OF WORK**

- .1 In general, work of this section consists of all electrical, materials and associated equipment indicated to be removed.
- .2 Demolition work to be phased and coordinated with Departmental Representative.
- .3 Contractor to be aware that not all electrical devices are shown on drawings.

1.2 **RELATED WORK**

- .1 Common Work Results - Electrical: Section 26 05 00.

1.3 **REFERENCE STANDARDS**

- .1 All removal or modification work of electrical construction to be done in accordance with the safety standards outlined in the Canadian Electrical Code.

1.4 **DISPOSAL**

- .1 The Departmental Representative shall have first right of refusal of all materials and equipment removed under work of this section.
- .2 All materials and equipment refused by the Departmental Representative will become the property of the contractor and will be removed from site.

PART 2 **PRODUCTS**

PART 3 **EXECUTION**

3.1 **GENERAL**

- .1 Remove all existing electrical equipment including the following:
 - .1 Lighting
 - .2 Exit and emergency lighting
 - .3 Wiring devices
 - .4 Heating
 - .5 Thermostats
 - .6 Panelboards
 - .7 Transformers

Decommissioning, Demolition and Site Restoration SSB HQ
Southside Road, St. John's, NL
Project No. R.111146.001

2021/12/01

Section 26 05 13 – Electrical Removals

Page 2 of 2

- .8 Distribution equipment
- .9 Communication equipment
- .10 Conduits
- .11 Wiring
- .12 Fire Alarm devices, etc.

- .2 Main electrical services shall be disconnected at supply end and wiring removed.
 Coordinate with NF Power.

- .3 Be responsible for the removal of electrical equipment affected by construction of other
 trades.

- .4 Schedule all removal of work with the Departmental Representative.

END OF SECTION