

0	ISSUED FOR TENDER	12/16/21
revisions		date

project

**DECOMMISSIONING,  
DEMOLITION AND SITE  
RESTORATION SSB HQ  
SOUTHSIDE ROAD  
ST. JOHN'S, NL**

project

drawing

dessin

**BACKFLOW PREVENTION  
WATER UPGRADE  
ELECTRICAL SITE PLAN**

designed K.N. conçu

date DECEMBER 2021

drawn R.J. dessiné

date DECEMBER 2021

approved K.N. approuvé

date DECEMBER 2021

Tender Soumission

PWGSC Project Manager Administrateur de projets TPSC

project number no. du projet

**R.111146.001**

drawing no. no. du dessin

**E16**

GENERAL NOTES:

1. CONTRACTOR TO PROVIDE ALL CUTTING, PATCHING AND PAINTING TO MATCH EXISTING. SEE SPECIFICATION FOR DETAILS. COORDINATE ON SITE.
2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND CONDITIONS ON SITE BEFORE PROCEEDING WITH ANY PORTION OF THIS WORK. DO NOT SCALE FROM DRAWINGS. CONTRACTOR TO ASSESS WORK AREA IN ADVANCE WITH DEPARTMENTAL REPRESENTATIVE FOR COORDINATION OF RELATED DAILY WORK SCHEDULES, PARKING, BUILDING ACCESS, AND STORAGE OF EQUIPMENT.
3. WORK SHALL BE SCHEDULED DURING NORMAL WORKING HOURS CONTRACTOR MAY WORK AFTER NORMAL WORKING HOURS AS COORDINATED BY DEPARTMENTAL REPRESENTATIVE. BUILDING TO REMAIN OPERATIONAL DURING CONSTRUCTION.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEAN UP AND DISPOSALS OF WORK AREA ON A DAILY BASIS. AFTER EACH WORKING SHIFT BUILDING TO BE CLEANED AND FREE OF DEBRIS. BUILDING GARBAGE BINS ARE NOT TO BE USED.
5. ANY ELECTRICAL SYSTEM SHUTDOWN TO BE SCHEDULED AFTER NORMAL BUSINESS HOURS AND SHALL BE COORDINATED WITH DEPARTMENTAL REPRESENTATIVE. SUFFICIENT NOTICE SHALL BE GIVEN. 5 WORKING DAYS NOTICE IS REQUIRED FOR ANY DISRUPTION.
6. WORK TO BE CARRIED OUT IN CONSIDERATION OF CLIENT COMFORT AND OPERATIONS.
7. ALL WIRING TO BE INSTALLED IN CONDUIT AS INDICATED.


8. ACCESS TO FACILITY TO BE COORDINATED WITH DEPARTMENTAL REPRESENTATIVE.

9. PROVIDE TYPED REVISED PANELBOARD DIRECTORIES FOR ALL PANELBOARDS WHERE BRANCH CIRCUITS WERE REMOVED, ADDED OR MODIFIED.

10. LABEL ALL EQUIPMENT WITH LAMACOID TAGS AS PER SPECIFICATION.

11. ALL EXISTING ELECTRICAL EQUIPMENT REMOVED TO BE TURNED OVER TO CANADA. IF CANADA REFUSES THEN CONTRACTOR TO REMOVE FROM SITE AND DISPOSE OF.

BROKEN LINE INDICATES EXISTING CONDUIT  
SOLID LINE INDICATES NEW CONDUIT



ELECTRICAL SITE PLAN

SCALE : 1:300

0m 5m 10m 15m 20m 25m 30m