



Parks  
Canada      Parcs  
Canada

**RETURN BIDS TO:**

Parks Canada Agency Bid Receiving Unit  
National Contracting Services

Bid Fax: 1-855-983-1808

Bid E-mail Address:

[soumissionsami-bidsrpc@pc.gc.ca](mailto:soumissionsami-bidsrpc@pc.gc.ca)

This is the only acceptable email address for responses to the bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. The Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 002 TO AN  
INVITATION TO TENDER**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

**Issuing Office:**

Parks Canada Agency  
National Contracting Services

Halifax, Nova Scotia

<b>Title:</b> Mechanical Systems Upgrade, Battle of the Restigouche National Historic Site	
<b>Solicitation No.:</b> 5P468-21-0158/B	<b>Date:</b> 04 February 2022
<b>Amendment No.:</b> 002	
<b>Client Reference No.:</b> 1408	
<b>GETS Reference No.:</b> PW-22-00984378	

<b>Solicitation Closes:</b> At: 14:00 On: 02 March 2022	<b>Time Zone:</b> EST
---	--------------------------

<b>F.O.B.:</b> Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
<b>Address Enquiries to:</b> Jaime Creaser	
<b>Telephone No.:</b> 902-266-8592	<b>Fax No.:</b> 1-855-983-1808
<b>Email Address:</b> <a href="mailto:Jaime.Creaser@pc.gc.ca">Jaime.Creaser@pc.gc.ca</a>	
<b>Destination of Goods, Services, and Construction:</b> See Herein	

**TO BE COMPLETED BY THE BIDDER**

<b>Vendor/ Firm Name:</b>	
<b>Address:</b>	
<b>Telephone No.:</b>	<b>Fax No.:</b>
<b>Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):</b>	
<b>Signature:</b>	<b>Date:</b>

**Solicitation No.:**  
5P468-21-0158/B

**Amendment No.:**  
002

**Contracting Authority:**  
Jaime Creaser

**Client Reference No.:**  
1408

**Title:**  
Mechanical Systems Upgrade, Battle of the Restigouche National Historic Site

---

## **Amendment 002**

This amendment is raised to revise the specifications and drawings, and to provide additional information.

### **1. Revisions**

See the below for all revisions and additions.

**ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED**

**Stantec Consulting Ltd.**  
250-1260 Lebourgneuf Boulevard, Quebec City QC G2K 2G2  
Tél. : (418) 626-1688  
Téléc. : (418) 626-5464

File : Mechanical Systems Upgrade  
APC Project : 1408-4  
Addendum No : ME-01  
Date: February 2<sup>nd</sup>, 2022  
Owner : Parks Canada  
Project No.: 157101777

---

This addendum is to be read with and constitutes part of the tender document.

---

This addendum is an integral part of the submission documents to which it refers, by supplementing them, modifying them or eliminating certain elements.

The following amendments are brought to the technical documents submitted during the tender period.

**Details of the Addendum:**

**1. SPECIFICATIONS**

**1.1 General requirements**

**1.1.1 List of Drawings**

.1 The list of drawings is corrected as follows:

- .1 M000 – Front page, site access and storage area, rev. 0 is added.
- .2 The two architecture drawings issued for tender are rev. H.
- .3 The number and the title of the drawing are modified S201 – Structural – Typical Details.
- .4 The two structural drawings are rev. 1.
- .5 The title of the drawing E103 is modified Lighting and Services – Mechanical Room – Demolition.
- .6 The title of the drawing E202 is modified Fire Alarm – Mechanical Room – Demolition/Construction.

### 1.2.1 Section 01 11 00 – Summary of Work

- .1 Section 1.3 is modified: The following sentence is added: This exhibition center contains a permanent exhibition of the remains of the Machault, one of only three French frigates of the 18th century discovered to date and aims to ensure the preservation of these artifacts.
- .2 Section 1.15.1.3.2 is added: Refer to article 1.15.3 for additional requirements during the work on the fire protection system.
- .3 Section 1.15.1.4 is added: The replacement of the remote communication panel of the fire alarm system must be completed before the fire protection system is shut down.
- .4 Section 1.15.2.1 is modified as follows: If the delivery times of the generator and fire pumps allow it, the Contractor will be free to carry out the work on the generator and the work on the fire pumps in parallel or sequentially, in the desired order, provided that the Contractor's schedule provides for a completion date of the work (including the correction of deficiencies) before **March 3rd, 2023** and that the following conditions are met: reduce emergency power supply downtime and minimize the duration of the period when the building will not be covered by the fire protection system.
- .5 Section 1.15.3 is added:
  - .3 Additional requirements during the work on the fire protection system :
    - .1 System Impairment
      - .1 In the event of any shutdown, bypass or reduction in the operation of a fire protection system that will last longer than two (2) hours), an impairment coordinator shall be appointed. In the absence of a specific designee, the on-site Contractor representative shall be considered the impairment coordinator.
      - .2 In the event of any protection system shutdown or impairment, the impairment coordinator shall apply the following procedures.
    - .2 Fire protection system impairment plan:
      - .1 Submit for approval, one month before the start of work on site, a "Fire Prevention Plan" within which there must be a "Fire Protection System Impairment Plan". The latter will have to address the items and procedures below.
    - .3 Determine extent of and duration:
      - .1 Extent of and expected duration of the impairment need to be determined. Minor impairments do not need an approved permit. However, if an unforeseeable event (emergency impairment) occurs while testing, maintaining or making repairs and it will exceed the two (2) hour time limit, a Fire Protection Impairment Permit must be completed.

- .4      Determine increased risk:
  - .1      The areas or buildings involved need to be inspected and the increase in probability of a fire occurrence and risks determined. Additional fire prevention and risk reduction measures should be implemented and enforced to eliminate potential ignition sources and limit the amount of fuel available to the fire.
- .5      Minimize impairments:
  - .1      Only portions of a system that need to be worked upon shall be taken out of service. The entire system is not to be impaired unless there is no other alternative. It may take more time to isolate a particular portion of a system, but there is a significant and worthwhile value to life-safety and property protection in keeping in operation as much of a system as possible.
- .6      Determine alternative measures:
  - .1      In the shutdown of a fire alarm system, alternative measures should be worked out in cooperation with the building manager or designated representative to ensure that all persons in the building can be promptly informed, and the fire department notified, should a fire occur while the alarm system is out of service. When a sprinkler system is shut down, measures that can be taken include but are not limited to the provision of: emergency hose lines and portable extinguishers, extra fire watch service and, where practicable, temporary water connections to the sprinkler system.
- .7      Notify affected parties:
  - .1      In the event of any shutdown or impairment of a fire protection system or part thereof, the Fire Department and building occupants must be notified. Other parties to be notified who could be affected may include, but are not necessarily limited to, the fire alarm monitoring company, the Asset Manager and other tenants in the building. When notifying the Fire Department and the monitoring station, give your name, address and a description of the work and when you expect it to be corrected. The Fire Department should be notified in writing of shutdowns longer than 24 hours.
- .8      Notify building occupants:
  - .1      All building occupants are to be notified in writing that the fire protection systems in the building are not functional. They must also be provided with the alternate procedures to be taken in case of an emergency. These should be outlined within the approved Fire Safety Plan.

- .9 Affix signage:
  - .1 Notices shall be posted at all building entrances and exits, on all floors stating: that the fire protection systems are out of service, the alternate procedures or actions to be taken in case of an emergency and the anticipated duration (start and finish) of the impairment.
- .10 Identify affected systems:
  - .1 A tag shall be used to alert building occupants and to indicate to the fire department that a system, or part thereof, has been removed from service. A clearly visible tag shall be affixed on the exterior of the fire alarm panel and annunciators, at any affected valves at each fire department connection and the system control valve, and other locations required by the authority having jurisdiction, indicating which system, or part thereof, has been removed from service. This is typically achieved by the use of a "NOT IN SERVICE" tag or notice. The tag or notice shall contain the contact information of the individual that impaired the system, the date and time the system was impaired, the reason for the impairment, and the expected date and time to return to service.
- .11 Fire Watch:
  - .1 Where any part of a fire protection system is shut down for service, repairs or is inoperative for more than 2 hours, the impairment coordinator shall provide a sufficient number of trained people to patrol the building until the fire protection system is restored to operating condition.

Fire Watch personnel must tour the entire building each hour and immediately document, upon the completion of each round, that the building inspection was completed. During the patrol of the area, the person should not only be looking for fire, but making sure that the other fire protection features of the building such as egress routes and alarm systems are available and functioning properly. The person completing the rounds will record the time each round was completed and sign or initial each entry in the annexed "Fire Watch Log Sheet".

During hours where a building is occupied, this may be achieved either by the technician(s) in the area or by the building occupants working in the area. During off-work hours or periods where the building is unoccupied, a dedicated fire watch shall be implemented and rounds shall be performed on an hourly (1 hour) basis.
  - .2 Alternatively, one of the following two options could be implemented instead of the Fire Watch:
    - .1 The originally installed fire alarm system be maintained in operation and the interconnection to the Fire Signal Receiving Centre (Fire Alarm Monitoring Company) should

be tested and confirmed. Conventional heat detectors (rate-of-rise) connected to the building's security system could be installed in all areas of the building as a temporary measure during the time of impairment to provide detection and notification to the fire emergency service in the event of a fire during unoccupied hours. Heat detectors shall be verified and tested to confirm operation and for proper notification to the Fire Emergency Services through signal transmission and receipt to the Security monitoring company. This option would only be a temporary mitigation measure for property protection and not one for life safety. This is not to be considered as a Code compliant measure or installation and is a temporary measure only. See option 1 of annexed "Fire Watch Alternatives" document for more details.

- .2 The originally installed fire alarm system be maintained in operation and the interconnection to the Fire Signal Receiving Centre (Fire Alarm Monitoring Company) should be tested and confirmed. Fully integrated, battery-operated wireless smoke alarms connected to the building's security system could be installed in all areas of the building as a temporary measure during the time of impairment to provide detection and notification to the fire emergency service in the event of a fire during unoccupied hours. The smoke alarms shall be verified and tested to confirm operation and for proper notification to the Fire Emergency Services through signal transmission and receipt to the Security monitoring company. This option would only be a temporary mitigation measure for property protection and not one for life safety. This is not to be considered as a Code compliant measure or installation and is a temporary measure only. See option 2 of annexed "Fire Watch Alternatives" document for more details.

.12 Submit mitigating recommendations:

- .1 Recommendations to mitigate any increased risks need to be submitted to the impairment coordinator or designated representative for approval. Mitigations other than fire watch may include, but not necessarily limited to, evacuation of the building or portion of the building affected by the system out of service, the establishment of temporary water supply, establishment and implementation of an approved program to eliminate potential ignition sources and limit the amount of fuel available to the fire.

.13 Verify implemented procedures:

- .1 The impairment coordinator will verify that all procedures identified above have been implemented and are continuously adhered to.

- .14 Authorize the impairment:
  - .1 The impairment coordinator (Asset Manager, on site building manager or a designated representative) will authorize the impairment.
- .15 Recording of the Impairment: A permanent record shall be kept at each fire protection system's main control panel or valve. Each impairment and return to service shall be documented. The technician's name, contact information, impairment date and time, and expected and actual return to service date and time shall be recorded.
- .16 Restoring Systems to Service: When all impaired equipment is restored to normal working order, the impairment coordinator shall verify that the following procedures have been implemented:
  - .1 Any necessary inspections and tests have been conducted to verify that affected systems are operational. The appropriate standard for the impaired fire protection system shall be consulted for guidance on the type of inspection and test required. For example, for water-based fire suppression systems, this shall include a full flow main drain test downstream of all supply valves that were closed and opened. For fire alarm systems, where wiring or circuit boards have been disconnected or reconnected, all possibly affected input and output circuits are to be tested for alarm and trouble function.
  - .2 Notify the Fire Department, the fire signal receiving centre (fire alarm monitoring), and building occupants that the work has been completed and systems are operational and that protection is restored.
  - .3 The Parks Canada representative (Asset Manager / Site Manager) has been advised that protection is restored.
  - .4 The posted notices and impairment tag have been removed.
- .6 The following annex is added: Fire Watch Log Sheet.
- .7 The following annex is added: Fire Watch Alternatives.

## **1.2 Mechanical**

### **1.2.1 Section 21 30 00 – Electrical Fire Pumps**

- .1 Section 2.4.3.1 is added: If the disassembly of certain components of the fire pump is necessary to transport the unit to the mechanical room, the reassembly of these components must be done by a technician certified by the manufacturer of the fire pump in order to maintain ULC and CSA approvals.

- .2 Section 3.4.2 is amended as follows: Perform **start-up** and tests in the presence of **the pump manufacturer's representative and** the appropriate authority representative or Agency Representative, and provide test certificates as required by NFPA 20 standard.

## 2. PLANS

### 2.1 Mechanical

#### 2.1.1 Plan M301 - FIRE PROTECTION - UNDERGROUND FLR – DEMOLITION

- .1 Keynote #5 is modified as follows: *WATER MOTOR GONG TO DEMOLISH AND EVACUATE FROM THE SITE.*  
.2 Plan M301 is reissued with revision 1.

#### 2.1.2 Plan M302 - FIRE PROTECTION - UNDERGROUND FLR - CONSTRUCTION

- .1 The existing water motor gong is dismantled and not to be connected to the new alarm valve. Keynotes #7 and #9 are cancelled.  
.2 Plan M302 is reissued with revision 1.

## 3. ARCHITECTURE

- 3.1 Addendum A-01 in Architecture is attached to this Addendum.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED

### Stantec Consulting Ltd.



Samuel Gagné, ing.  
Mechanical Engineer  
Phone number : 418.210.4507  
samuel.gagne@stantec.com



Philippe Amyot, ing., MBA  
Fire Protection Engineer  
Phone number : 418.210.4448  
philippe.amyot@stantec.com



Stéphane Fournier, ing  
Electrical Engineer  
Phone number : 581.480.5035  
stephane.fournier@stantec.com



## FIRE WATCH LOG SHEET

Persons assigned to Fire Watch duties shall follow the requirements listed on the Fire Watch Duties sheet and shall patrol all unprotected areas of the building every hour to check for signs of fire or smoke conditions. All patrols are to be recorded on this Fire Watch Log Sheet immediately following each round. Records of Fire Watch shall be retained on site for 2 years after they are made, and shall be made available upon request to the Chief Fire Official.

**NOTE:** Start a new Fire Watch Log Sheet for each new day of Fire Watch

If fire or smoke conditions are discovered, alert all building occupants. Notify the local Fire Department by calling **9-1-1 from a safe area.**

_____	System <b>OUT OF SERVICE</b>	Date: _____	Time: _____
Notification to Fire Department – System Out of Service		Date: _____	Time: _____
Notification to Monitoring Agency – System Out of Service		Date: _____	Time: _____

_____	System <b>BACK IN SERVICE</b>	Date: _____	Time: _____
Notification to Fire Department – System Back in Service		Date: _____	Time: _____
Notification to Monitoring Agency – System Back in Service		Date: _____	Time: _____

### NAMES & POSITIONS OF PERSONS CONDUCTING FIRE WATCH:

### INITIALS

1.	_____
2.	_____
3.	_____
4.	_____

**See Reverse for Fire Watch Patrol Log Sheet**



## FIRE WATCH LOG SHEET

**NOTE:** Start a new Fire Watch Log Sheet for each new day of Fire Watch

**Fire Watch Duties Conducted by:** \_\_\_\_\_

(print name & position)

**Fire Watch Commenced:** \_\_\_\_\_ **Date:** \_\_\_\_\_ **Time:** \_\_\_\_\_


ROUNDS	DATE (m/d/y)	START TIME (circle a.m./p.m.)	FINISH TIME (circle a.m./p.m.)	AREAS PATROLLED & COMMENTS	INITIALS
1.	/ /	a.m. p.m.	a.m. p.m.		
2.	/ /	a.m. p.m.	a.m. p.m.		
3.	/ /	a.m. p.m.	a.m. p.m.		
4.	/ /	a.m. p.m.	a.m. p.m.		
5.	/ /	a.m. p.m.	a.m. p.m.		
6.	/ /	a.m. p.m.	a.m. p.m.		
7.	/ /	a.m. p.m.	a.m. p.m.		
8.	/ /	a.m. p.m.	a.m. p.m.		
9.	/ /	a.m. p.m.	a.m. p.m.		
10.	/ /	a.m. p.m.	a.m. p.m.		
11.	/ /	a.m. p.m.	a.m. p.m.		
12.	/ /	a.m. p.m.	a.m. p.m.		
13.	/ /	a.m. p.m.	a.m. p.m.		
14.	/ /	a.m. p.m.	a.m. p.m.		
15.	/ /	a.m. p.m.	a.m. p.m.		
16.	/ /	a.m. p.m.	a.m. p.m.		
17.	/ /	a.m. p.m.	a.m. p.m.		
18.	/ /	a.m. p.m.	a.m. p.m.		
19.	/ /	a.m. p.m.	a.m. p.m.		
20.	/ /	a.m. p.m.	a.m. p.m.		
21.	/ /	a.m. p.m.	a.m. p.m.		
22.	/ /	a.m. p.m.	a.m. p.m.		
23.	/ /	a.m. p.m.	a.m. p.m.		
24.	/ /	a.m. p.m.	a.m. p.m.		

## **Fire Watch Alternatives**

In the first phase of the work on the fire alarm system, the contractor must install the new ULC-certified communicator module and ensure that it is put into operation during the same day to provide continuous coverage of the system thereafter.


Following the addition of the communicator module, the pumps of the fire protection system will be dismantled and the sprinklers will not be functional for a certain period of time. As an alternative to fire watch, the Contractor may provide for the addition of a network of temporary heat/smoke detectors throughout the work period on the fire protection system. Some detectors are already existing but new detectors are needed to provide full coverage. The following sketches show the temporary detectors to be provided for the project, if this alternative is chosen by the Contractor. Refer to plan A01 for views of each floor, to scale.

## Basement




## Alternatives to fire watch

Ground floor



Upper floor



- Existing Smoke Detector
- Existing Thermal Detector
- New Thermal Detector

## Alternatives to fire watch

Two different options for carrying out this **temporary protection** measure are presented below. Regardless of the option chosen, the contractor will have to deactivate at the fire alarm panel the fire protection elements demolished during the work so that the fire alarm panel can be functional and can send alarm messages to the central station if necessary. The temporary system, including the detectors, will need to be tested and confirmed with the central station.

### Option 1: Temporary wired system

Provide conventional wired heat detectors in the building premises as shown in the previous sketches.

All detectors will be installed on the ceiling of each of the rooms and temporary wiring will be installed and connected to each of the detectors. The contractor must provide for the surface fixing of temporary cables in the upper portion of the walls of the access corridors and the various premises. The wiring will have to go through the suspended and openwork ceilings to cross some partitions.

Provide and install a temporary conventional panel or a conventional card at the existing panel to connect the new detectors. This new panel or this new card is connected to the existing main panel and must transfer an alarm signal to the main panel upon detection. All accessories, wiring, programming and start-up will need to be included in the contractor's solution.

The system must be compatible with the existing fire alarm panel and the contractor must provide a plan for the implementation and connection of the various components in the building. This plan must be approved by the manufacturer.

Provide for the complete dismantling of the temporary installation following the work and hand over the equipment to the customer.

Please note that this is not a code-compliant measure or installation, it is only a temporary measure.



## Alternatives to fire watch

### Option 2: Temporary wireless system

Provide integrated battery-operated wireless communication heat or smoke detectors in the building premises as shown in the previous sketches.

All detectors will be installed on the ceiling of each of the rooms and receiving antennas must be installed in strategic locations for optimal reception according to the manufacturer's recommendations. Connect the receiving antennas to the existing fire alarm panel.

The system must be compatible with the existing fire alarm panel and the contractor must provide a plan of location of the detectors and antennas from the manufacturer that will attest to the complete coverage of the building with the wireless network.

All accessories for connection, programming and start-up will have to be included in the contractor's solution.

Do not plan dismantling this temporary system for this option, the customer may keep this system as an additional protection following the work.



AGENCE PARCS CANADA - UNITÉ DE GESTION DE LA GASPÉSIE  
LIEU HISTORIQUE NATIONAL DE LA BATAILLE-DE-LA-RISTIGOUACHE  
PARKS CANADA AGENCY - GASPÉSIE FIELD UNIT  
BATTLE OF THE RESTIGOUACHE NATIONAL HISTORIC SITE  
40, BOULEVARD PERRON OUEST (ROUTE 132), POINTE-À-LA-CROIX, QC, G0C 1L0  
PROJET / PROJECT : 1408

MISE À NIVEAU DES SYSTÈMES MÉCANIQUES  
LIEU HISTORIQUE NATIONAL DE LA BATAILLE-DE-LA-RISTIGOUACHE  
MECHANICAL SYSTEMS UPGRADE  
BATTLE OF THE RESTIGOUACHE NATIONAL HISTORIC SITE  
18-018

Addenda A-01 / Addendum A-01

2021-12-06

#### 1. But / Purpose

- a) Le présent addenda a pour but de modifier les documents de soumissions déjà émis et le soumissionnaire est tenu d'établir l'offre en conséquence. / The purpose of this addendum is to amend the tender documents already issued and the tenderer is required to prepare the tender accordingly.

#### 2. Généralités / Generalities

- a) Sans objet / Not applicable


#### 3. Plans

- a) Page A02 – Plan SOUS-SOL – DEMOLITION : Une note est ajoutée concernant la démolition de la porte dans le corridor. / Sheet A02 – Plan BASEMENT – DEMOLITION : A note is added regarding the demolition of the door in the corridor.
- b) Page A02 – Plan SOUS-SOL – CONSTRUCTION : Une ouverture à boucher est ajoutée dans le mur extérieur. / Sheet A02 – Plan BASEMENT- CONSTRUCTION : An existing opening to be closed is added in the exterior wall.
- c) Page A02 – Plan SOUS-SOL – CONSTRUCTION : Le sens d'ouverture de la porte P4 est modifié. / Sheet A02 – Plan BASEMENT – CONSTRUCTION : The direction of door swing of the door P4 is modified.
- d) Page A02 – LÉGENDE – CONSTRUCTION : La note 8 est ajoutée. / Sheet A02 – LEGEND – CONSTRUCTION : The note 8 is added.

#### **4. Devis / Specifications**

- a) Devis section 08 71 10 : L'article 2.2.1.1 est modifié comme suit :**
  - 2.2.1.1 Serrure Schlage, fonction dépôt, poignée Jupiter, fini 626, cUL 437 ou Serrure Falcon T581D626 ou EZSET BP-504FC-MD-S26D-238 ou équivalent approuvé. (Portes P1 & P2 uniquement)**  
Specifications section 08 71 10 : The article 2.2.1.1 is modified as follow:  
**2.2.1.1 Lever Handle Schlage, storeroom function, model Jupiter, finish 626, cUL 437 or Lever Handle Falcon T581D626 or EZSET BP-504FC-MD-S26D-238 or approved equivalent. (Doors P1 & P2 only)**
- b) Devis section 08 71 10 : L'article 2.2.1.2 est modifié comme suit :**
  - 2.2.1.2 Barre panique Von Duprin 98-L-BE-O6-F-US26D ou Falcon F-24-R-L-US26D ou Hager 4501-RM-FR-US26D (Portes P3 & P4 uniquement)**  
Specifications section 08 71 10 : The article 2.2.1.2 is modified as follow:  
**2.2.1.2 Panic pushbar Von Duprin 98-L-BE-O6-F-US26D ou Falcon F-24-R-L-US26D ou Hager 4501-RM-FR-US26D (Doors P3 & P4 only)**






**VUE EN PLAN - SALLE DES POMPES - DÉMOLITION**  
PLAN VIEW - PUMP ROOM - DEMOLITION

1:25

**IDENTIFICATIONS (DÉMOLITION) / KEYNOTES (DEMOLITION)**

- ① POMPE INCENDIE EXISTANTE À DÉMANTELER C/W TUYAUTERIE ET ACCESSOIRES. PRÉVOIR LA COORDINATION AVEC L'ENTREPRENEUR EN ÉLECTRICITÉ POUR LE DÉBRANCHEMENT DE L'ALIMENTATION ÉLECTRIQUE. CONSERVER TEMPORAIREMENT LES RACCORDS ÉLECTRIQUES EXISTANTS POUR LE RACCORDEMENT TEMPORAIRE DES NOUVELLES POMPES. / EXISTING FIRE PUMP TO DEMOLISH C/W PIPING AND ACCESSORIES. COORDINATE WITH THE ELECTRIC CONTRACTOR FOR THE ELECTRIC DISCONNECTION. TEMPORARILY MAINTAIN THE EXISTING ELECTRICAL CONNECTION FOR THE TEMPORARY CONNECTION OF THE NEW PUMPS.
- ② SECTION DE NOURRICE D'ALIMENTATION D'EAU À DÉMANTELER. COORDONNER L'INTERRUPTION DE SERVICE AVEC LE SERVICE DES INCENDIES ET LE GROUPE DE SECOURS. CONSERVER TEMPORAIREMENT LES RACCORDS D'EAU EXISTANTS POUR LE RACCORDEMENT TEMPORAIRE DES POMPES DE PRÉVENTION / WATER FEEDING SECTION TO DEMOLISH. COORDINATE THE SERVICE INTERRUPTION WITH THE LOCAL FIRE DEPARTMENT AND THE CLIENT REPRESENTATIVE. INFORM THE FIRE DEPARTMENT OF THE SHUT OFF PERIODS AND PREPARE SOME TEMPORARY FIRE PREVENTION MEASURE
- ③ CLAPET D'ALARME SOUS EAU 100mm à DÉMANTELER C/W ACCESSOIRES. PRÉVOIR LA COORDINATION AVEC L'ENTREPRENEUR EN ÉLECTRICITÉ POUR LE DÉBRANCHEMENT ET BRANCHEMENT DES MODULES D'ALARME SUR LE CLAPET D'ALARME. / 100mm WET ALARM VALVE TO DEMOLISH C/W ACCESSORIES. PROVIDE COORDINATION WITH THE ELECTRICAL CONTRACTOR FOR THE DISCONNECTION AND CONNECTION OF ALARM MODULES ON THE ALARM VALVE.
- ④ DEUX POMPES D'APPOINT À DÉMOLIR ET DISPOSER / TWO JOCKEY PUMPS TO DEMOLISH AND EVACUATE FROM THE SITE
- ⑤ CLOCHE HYDRAULIQUE À DÉMOLIR ET DISPOSER / WATER MOTOR GOING TO DEMOLISH AND EVACUATE FROM THE SITE
- ⑥ TOUTE LA BORNE CONTIENANT EXISTANTE L'ENTREPRENEUR GÉNÉRAL DEVRA PROTÉGER LA TUYAUTERIE PENDANT LES TRAVAUX DE DÉMOLITION ET DE RECONSTRUCTION DE LA PLATE-FORME. SE REFERER AU PLAN S-01 POUR LES INTERVENTIONS SUR LA DAULE. / ALL THE SUPPORT CONTAINING EXISTING PIPEWORK MUST BE PROTECTED BY THE GENERAL CONTRACTOR DURING THE CONCRETE SLAB DEMOLITION AND RECONSTRUCTION WORK IN THIS AREA. REFER TO DRAWING S01 FOR THE WORK REQUIRED ON THE SLAB.
- ⑦ DÉMOLIR LES ÉQUIPEMENTS, TUYAUTERIES ET ACCESSOIRES NÉCESSAIRES À L'INSTALLATION DU NOUVEAU MUR. COORDONNER LE PHASAGE DE LA CONSTRUCTION DES NOUVEAUX ÉLÉMENTS TRAVERSANT LE MUR AVEC L'ENTREPRENEUR GÉNÉRAL. / DEMOLISH EQUIPMENT, PIPING AND ACCESSORIES REQUIRED TO INSTALL THE NEW WALL. COORDINATE THE PHASING OF THE CONSTRUCTION OF THE NEW ELEMENTS GOING THROUGH THE WALL WITH THE GENERAL CONTRACTOR.



**VUE ISOMÉTRIQUE - SALLES DES POMPES - DÉMOLITION**  
ISOMETRIC VIEW - PUMP ROOM - DEMOLITION

CE DOCUMENT D'INGÉNIERIE EST LA PROPRIÉTÉ DE STANTEC EXPERTS-CONSEILS LTD. IL EST PROTÉGÉ PAR LA LOI SUR LES DROITS D'AUTEUR ET TOUTE FORME D'USURE, SOIT PARTIELLE SOIT TOTALE, EN EST STRICTEMENT PROHIBÉE. SON COPIAGE, SAURETÉ, ADAPTATION PARTIELLE OU TOTALE, EN EST STRICTEMENT PROHIBÉE SANS AVOIR PRÉALABLEMENT OBTENU L'AUTORISATION DES EXPERTS-CONSEILS LTD.

THIS ENGINEERING DOCUMENT IS THE PROPERTY OF STANTEC EXPERTS-CONSEILS LTD. AS SUCH IS PROTECTED BY LAW. IT IS SOLELY INTENDED FOR THE USE MENTIONED HEREIN. IT IS STRICTLY FORBIDDEN TO DUPLICATE OR ADAPT IT EITHER IN PART OR IN ITS ENTIRETY WITHOUT HAVING FIRST OBTAINED STANTEC EXPERTS-CONSEILS LTD'S WRITTEN AUTHORIZATION TO DO SO.

Notes:

1	21-11-06	ADDENDA ME-01	P.A.	-
0	21-11-12	POUR SOUMISSION / FOR TENDER	P.A.	-
REV.	A/Y - M - JJD	DESCRIPTION	Prep.	Vérif.
	DRAW.		Par B.	Par B.

**ÉMISSIONS - RÉVISIONS / ISSUES - REVISIONS**

TOUTES LES DIMENSIONS DEVONT ÊTRE PRISES ET VÉRIFIÉES AVANT DE COMMENCER LES TRAVAUX.  
ALL DIMENSIONS MUST BE TAKEN AND CHECKED BEFORE BEGINNING THE WORKS.

Scénex/Seal

  
Philippe Amyot  
2021-12-06

Client	Parcs Canada Parks Canada
AGENCE PARCS CANADA - UNITÉ DE GESTION DE LA GASPESIE LIEU HISTORIQUE NATIONAL DE LA BATAILLE-DE-LA-RISTIGOUCHE PARKS CANADA AGENCY - GASPESI FIELD UNIT BATTLE OF THE RESTIGOUCHE NATIONAL HISTORIC SITE	
40, boulevard Perron Ouest (route 132), Pointe-à-la-Croix, QC, G1C 1L0	

Ref. client PROJET / PROJECT : 1408-4

MISE À NIVEAU DES SYSTÈMES MÉCANIQUES  
MECHANICAL SYSTEMS UPGRADE


Titre/Titre  
**PROTECTION-INCENDIE SOUS-SOL DÉMOLITION / FIRE PROTECTION - UNDERGROUND FLR - DEMOLITION**

Chargé de projet/Project manager P. Amyot, ing.	Discipline PROTECTION INCENDIE / FIRE PROTECTION
Dess/Draw. J. Plante	Échelle/Scale INDICUÉE / INDICATED
Verif. -	Date 18 12 20
C. Lapointe, ing.	Chargé de projet/Project manager C. Lapointe, ing.
Serv. resp. 15710177	Sequence No 9 de/of 20
Projet/Project M   D   M301   1	Op. Disc. Type Desc./Draw. Rev.

Notes:


LEGENDER DES GICLEURS / SPRINKLERS LEGEND						
IDENTIFICATION	TYPE	FACTOR K / K-FACTOR	RÉPONSE / RESPONSE	TEMPERATURE	NB	REMARQUES / REMARKS
● DROIT / UPRIGHT	5.6		RAPIDE / QUICK	155 F	4	FINI BRONZE / BRONZE FINISH

NOTE: LES GICLEURS DOIVENT ÊTRE INSTALLÉS À MOINS DE 300 mm SOUS LE TOIT OU LA DALLE / SPRINKLERS MUST BE INSTALLED AT 300 mm OR LESS UNDER THE ROOF OR THE SLAB.



VUE EN PLAN - SALLE DES POMPES - ÉTAPE TEMPORAIRE

FLOOR PLAN - PUMP ROOM - TEMPORARY  
1:25  
NOTE: CETTE VUE ILLUSTRE LES TRAVAUX QUI DEVONT ÊTRE EFFECTUÉS AVANT LA CONSTRUCTION DU NOUVEAU MUR PAR L'ENTREPRENEUR GÉNÉRAL. VOIR LA VUE DE CONSTRUCTION POUR PLUS DE DÉTAILS SUR L'INSTALLATION FINALE.  
NOTE: THIS VIEW SHOWS THE WORK THAT NEEDS TO BE DONE BEFORE THE NEW WALL IS BUILT BY THE GENERAL CONTRACTOR. SEE THE CONSTRUCTION VIEW FOR MORE DETAILS ON THE FINAL INSTALLATION.



VUE EN PLAN - SALLE DES POMPES - CONSTRUCTION

FLOOR PLAN - PUMP ROOM - CONSTRUCTION

1:25

VUE ISOMÉTRIQUE - SALLES DES POMPES - CONSTRUCTION

ISOMETRIC VIEW - PUMP ROOM - CONSTRUCTION

IDENTIFICATIONS (TEMPOIRE ET CONSTRUCTION) / KEYNOTES (TEMPORARY AND CONSTRUCTION)	
1	NOUVELLE POMPE INCENDIE. VOIR DEVIS SECTION 21 30 00 POUR SPÉCIFICATIONS. RACONDER LA SOUPAPE DE SURETÉ JUSQU'A DRAIN OUVERT OU À L'AVALOIR DE SOL AS-1 AVEC TUYAUTERIE 3/4". SE REFERER AU PLAN M101 POUR LEUR POSITION. VOIR LA NOTE #16 POUR LE TRANSPORT DE LA POMPE VERS LA SALLE MÉCANIQUE. L'ENTREPRENEUR EN PROTECTION INCENDIE DOIT VALIDER LE PASSAGE POUR LE TRANSPORT DES POMPES AU DÉBUT DES TRAVAUX ET AVISER L'ENTREPRENEUR GÉNÉRAL DE TOUTE CONTRAINE. / NEW FIRE PUMP. SEE SECTION 21 30 00 OF THE BOOK OF SPECIFICATIONS FOR THE PUMP. REFER TO THE OPEN DRAIN OR THE AS-1 FLOOR DRAIN WITH 3/4" PIPING. REFER TO M101 DRAWING FOR THEIR POSITION. SEE NOTE #16 FOR THE PUMP TRANSPORT FROM THE MECHANICAL ROOM. THE FIRE PROTECTION CONTRACTOR MUST CONFIRM THE PASSAGE FOR THE PUMPS TRANSPORT AT THE START OF WORKS AND ADVISE THE GENERAL CONTRACTOR OF ANY CONSTRAINT.
2	TUYAUTERIE VERS LA BORNE FONTAINE EXTERIEURE. / PIPING TO HYDRANT.
3	NOUVEAU CLAPET D'ALARME SOUS EAU 100mm C/W POMPE D'POINT (POA-01) ET GARNITURES. RACONDER LE DRAIN DU CLAPET D'ALARME JUSQU'A DRAIN OUVERT AVEC ROBINET DE VIDANGE 2" NORMALEMENT FERMÉ ET VERS LE RACCORD MURAL 2-1/2" NORMALEMENT FERMÉ. IDENTIFIER LES ROBINETS AVEC DES PLAQUES MÉTALLIQUES PONÇONNÉES TEL QUE SPÉCIFIÉ DANS LA SECTION 23 05 53.01 PORTANT LES INSRIPTIONS "DRAIN SOUPAPE D'ALARME" ET "TEST SOUPAPE D'ALARME". / NEW 100MM WET ALARM VALVE C/W JOCKEY PUMP (POA-01) AND TRIM. CONNECT THE DRAIN OF THE ALARM VALVE TO THE OPEN DRAIN WITH 2" NORMALLY-OPEN VALVE AND TO THE 2-1/2" WALL FITTING WITH PUNCHED METAL PLATES AS SPECIFIED IN SECTION 23 05 53.01 BEARING THE FOLLOWING DESCRIPTIONS: "ALARM VALVE DRAIN" AND "ALARM VALVE TEST" RESPECTIVELY.
4	DEUX NOUVEAUX PANNEAUX DE CONTRÔLE DE POMPE INCENDIE FOURNIS ET INSTALLES PAR L'ENTREPRENEUR EN PROTECTION INCENDIE. RACONDER PAR L'ENTREPRENEUR EN ÉLECTRICITÉ. L'ENTREPRENEUR EN PROTECTION INCENDIE DOIT FAIRE LA PROGRAMMATION DES POINTS D'ALARME. VOIR DEVIS SECTION 21 30 00 POUR SPÉCIFICATIONS. DÉGAGEMENT INDICÉ PAR LE PONTELLÉ A PLAN. TWO NEW FIRE PUMP CONTROL PANELS PROVIDED AND INSTALLED BY THE FIRE PROTECTION CONTRACTOR. CONNECTED BY THE ELECTRICAL CONTRACTOR. THE FIRE PROTECTION CONTRACTOR MUST PROGRAM THE ALARM POINT. SEE SPECIFICATIONS SECTION 21 30 00. REQUIRED CLEARANCE INDICATED BY THE DOTTED LINES ON THE PLAN.
5	NOUVELLE POMPE D'POINT POA-02 FOURNIE ET INSTALLEE PAR L'ENTREPRENEUR EN PROTECTION INCENDIE. RACONNERÉE PAR L'ENTREPRENEUR EN ÉLECTRICITÉ. VOIR DEVIS SECTION 21 30 00 POUR SPÉCIFICATIONS. NEW JOCKEY PUMP POA-02 PROVIDED AND INSTALLED BY THE FIRE PROTECTION CONTRACTOR. WIRED BY THE ELECTRICAL CONTRACTOR. SEE SECTION 21 30 00 OF THE SPECIFICATIONS.
6	NOUVEAU PANNEAU DE CONTRÔLE DE POMPE D'POINT FOURNIT ET INSTALLE PAR L'ENTREPRENEUR EN PROTECTION INCENDIE. RACONNERÉE PAR L'ENTREPRENEUR EN ÉLECTRICITÉ. L'ENTREPRENEUR EN PROTECTION INCENDIE DOIT FAIRE LA PROGRAMMATION DES POINTS D'ALARME. VOIR DEVIS SECTION 21 30 00 POUR SPÉCIFICATIONS. NEW JOCKEY PUMP CONTROL PANEL PROVIDED AND INSTALLED BY THE FIRE PROTECTION CONTRACTOR. CONNECTED BY THE ELECTRICAL CONTRACTOR. THE FIRE PROTECTION CONTRACTOR MUST PROGRAM THE ALARM POINT. SEE SPECIFICATIONS SECTION 21 30 00.
7	SIO
8	SIO
9	INSTALLER ET RACONNER EN PARALLÈLE DU CLAPET D'ALARME. MANGUETTE D'ALARME 1/2" AVEC SOUPAPE D'ALARME. / INSTALL AND CONNECT IN PARALLEL TO THE ALARM VALVE. 1/2" FLUSH MOUNTING ALARM PLUG AND CHAIN.
10	RACCORD SIMPLE 1/2" POUR LE TEST DE LA SOUPAPE D'ALARME. AVEC SOUPAPE MÉTALLIQUE FILETÉ ET CHAÎNETTE. A FILETAGE CORRESPONDANT À CELUI DU SERVICE LOCAL DES INCENDIES. RACCORD PRÉSENTANT LES CARACTÉRISTIQUES SUIVANTES : EN BRONZE. FINI POLI POUR MONTAGE ENCASTRÉ. AVEC PLAQUE INDICATRICE CHROMÉE COMPORTANT L'INSCRIPTION "TEST SOUPAPE D'ALARME" MONTÉE À MÉME LA PLAQUE. INSTALLER À 150mm AU-DESSUS DU NIVEAU DU SOL FINI. SINGLE FLUSH MOUNTING ALARM PLUG AND CHAIN THREADING WITH THE FOLLOWING CHARACTERISTICS: BRONZE, POLISHED FINISH, FOR FLUSH MOUNTING, WITH CHROMED INDICATOR PLATE WITH "ALARM VALVE TEST OUTLET" INSRIPTION ON THE PLATE, THREADED PLUG AND METAL CHAIN. INSTALL AT 150mm ABOVE FINISHED FLOOR.
11	NOUVELLE DRAIN OUVERT SOUS LE CLAPET D'ALARME. VOIR PLAN M101. / NEW OPEN DRAIN UNDER THE ALARM VALVE. SEE DRAWING M101.
12	RACONNER TEMPORAIREMENT SUR L'ALIMENTATION ÉLECTRIQUE D'URGENCE EXISTANTE. LES RACCORDS ÉLECTRIQUES SERONT FAITES PAR L'ENTREPRENEUR EN ÉLECTRICITÉ. CONNECT TEMPORARILY TO EXISTING EMERGENCY ELECTRIC SUPPLY. THE ELECTRICAL CONNECTIONS WILL BE DONE BY THE ELECTRICAL CONTRACTOR.
13	RACONNER TEMPORAIREMENT SUR L'ALIMENTATION ÉLECTRIQUE NORMALE EXISTANTE. LES RACCORDS ÉLECTRIQUES SERONT FAITS PAR L'ENTREPRENEUR EN ÉLECTRICITÉ. CONNECT TEMPORARILY TO EXISTING NORMAL ELECTRIC SUPPLY. THE ELECTRICAL CONNECTIONS WILL BE DONE BY THE ELECTRICAL CONTRACTOR.
14	NOUVELLE TUYAUTERIE D'ESSAI C/W VALVE NORMALEMENT FERMÉE. / NEW TESTING PIPE C/W NORMALLY CLOSED VALVE.
15	NOUVEAU DÉBITMÈTRE VENTURI D'UN DIAMÈTRE DE 6" AVEC CADRE DE LECTURE DE 4-1/2" TEL QUE GERARD ENGINEERING MODÈLE K: VITAUTIC MODÈLE 735. GV OU L'EQUIVALENT APPROUVÉ. RESPECTER LES DÉGAGEMENTS MINIMUMS DE 5 DIAMÈTRES EN AMONT DU COMPTEUR ET 2 DIAMÈTRES EN aval SANS ACCESSOIRES OU CHANGEMENTS DE DIAMÈTRES. OÙ DAVANTAGE SI REQUIS PAR MANUFACTURE. INSTALLER LE CADRE DE LECTURE FACE À L'ÉCOULEMENT ET FORER LE DÉBITMÈTRE EN ECOUTRÉ ET FORER LE CERTIFICAT D'ÉTALONNAGE. / NEW 6" VENTURI METER WITH A 4-1/2" DIAL METER AS GERARD ENGINEERING K: VITAUTIC MODEL 735. GV OR EQUIVALENT APPROVED FOR A MAXIMUM OF 5 DIAMETERS UPSTREAM AND 2 DIAMETERS AFTER THE WATER METER BEFORE ANY DIRECTION CHANGE OR ACCESSORIES, OR MORE IF REQUIRED BY THE MANUFACTURER. ORIENT THE DIAL METER TO ENSURE A SAFE AND EASY READING. TEST THE WATER METER DURING FLOW AND PROVIDE A CALIBRATION CERTIFICATE.
16	CADRE DE PORTE AYANT UNE LARGEUR INTÉRIEURE DE 835mm ET UNE HAUTEUR LIBRE DE 1800 mm. À TENIR EN COMPTE POUR LA CONCEPTION DE L'UNITÉ DE POMPAGE INCENDIE SI LE DÉASSEMBLAGE DE LA POMPE INCENDIE EST NÉCESSAIRE POUR TRANSPORTER LA POMPE VERS LA SALLE MÉCANIQUE. L'HOMOLOGUATION ULC DOIT ÊTRE MAINTENUE SUITE À L'ASSEMBLAGE AU DOOR FRAME WITH AN INTERIOR WIDTH OF 335mm AND HEIGHT OF 1800mm. TO BE CONSIDERED FOR THE DESIGN OF THE PUMPING UNIT IF THE DISASSEMBLY OF THE PUMP IS NECESSARY FOR ITS TRANSPORT IN THE MECHANICAL ROOM. THE ULC APPROVAL MUST BE MAINTAINED UPON ASSEMBLY ON-SITE.
17	LES PERCEMENTS DANS LE NOUVEAU MUR DEVONT ÊTRE EFFECTUÉS PAR L'ENTREPRENEUR EN PROTECTION INCENDIE. / THE OPENINGS IN THE NEW WALL SHALL BE DONE BY THE FIRE PROTECTION CONTRACTOR.

