

---

**February 02, 2022**  
**ADDENDUM NO. 7**  
**Project Number: R.100644.001**

This Addendum shall be attached to and form an integral part of the Contract Documents. The Contents of this Addendum shall be brought to the attention of and read by all concerned. Receipt of this Addendum shall be acknowledged on the Bid Form. The following changes in the bid documents are effective immediately.

The Contract Documents issued by Taylor Hazell Architects Ltd and their consultants are hereby amended as follows:

**1. Specifications- Document Set 2**

1. Section 07 61 00 Sheet Metal Roofing
  1. Clause 3.2.1: Revise '0.34 mm' with '0.43 mm' in the first line.
2. Section 10 14 16 Interior Signage
  1. Clause 2.1.1 Materials. Replace "Lamacoid" with ""rigid phenolic engraving material."
3. Section 22 05 15 Plumbing Specialties and Accessories
  1. Add: "2.16.1.4 DMV-2: 0.95L/s capacity at outlet."

**2. Drawings- Document Set 2**

1. A0.1 COW BARN ASSEMBLIES
  1. ROOF ASSEMBLY TYPES: REPLACE " 0.34mm HI-RIB STEEL " WITH 0.43mm 4-RIB STEEL PANEL (NOMINALLY 762mmLong w/ 19mm high rib)
2. A-C-1.0 INTERIOR SIGNAGE
  1. DETAILS 5&6: REPLACE "GRAVOPLY" WITH "STANDARD RIGID PHENOLIC ENGRAVING MATERIAL"
3. A-C-2.2 COW BARN ROOF PLAN
  1. LEGEND: REPLACE " 0.34mm HI-RIB STEEL " WITH 0.43mm 4-RIB STEEL PANEL (NOMINALLY 762mmLong w/ 19mm high rib)
4. A-C-7.0
  1. The following note to be added to detail 6 for windows: Contractor to coordinate wall framing including openings to accommodate windows. Contractor to provide stamped shop drawings of wall framing and windows. Refer to SK-03 for sample of similar project (Walkerbrae farms) where sub-framing was added for similar type, size and shape of window.

**Attach**

SK-03-WALKERBRAE POLYCARBONATE WINDOW.pdf

**END OF ADDENDUM NO. 7**