



0	ISSUED FOR TENDER	DEC 10 2021
revisions		date

project project

**WHARF CONSTRUCTION
411 AND 412
SKINNERS POND SCH
PRINCE COUNTY
PRINCE EDWARD ISLAND**

drawing dessin

PILE SCHEDULE

designed P.V. conçu

date AUG. 2021

drawn A.D. dessiné

date OCT. 7, 2021

approved approuvé

date

Tender Soumission

PWGSC Project Manager Administrateur de projets TPSGC

project number no. du projet

R.118006.001

drawing no. no. du dessin

S19

PILE SCHEDULE				
PILE NO.	SUPPLIED LENGTH (m)	TIP ELEVATION (m)	LENGTH PLACED IN WORK (m)	BLOWS/LAST 25mm
1 A	11.34	-7.77		
1 B	11.66	-7.77		
1 C	11.34	-7.77		
1 C.1	11.66	-7.77		
1 D.1	11.34	-7.77		
1 F.1	11.66	-7.77		
1 H	11.34	-7.77		
2 A	11.34	-7.77		
2 C	11.34	-7.77		
2 D	11.34	-7.77		
2 F	11.34	-7.77		
2 H	11.34	-7.77		
3 A	11.34	-7.77		
3 B	11.66	-7.77		
3 C	11.34	-7.77		
3 D	11.34	-7.77		
3 E	11.65	-7.76		
3 F	11.34	-7.77		
3 G	11.66	-7.77		
3 H	11.34	-7.77		
4 A	11.30	-7.73		
4 C	11.30	-7.73		
4 D	11.30	-7.73		
4 F	11.30	-7.73		
4 H	11.30	-7.73		
5 A	11.19	-7.62		
5 B	11.43	-7.55		
5 C	11.19	-7.62		
5 D	11.19	-7.62		
5 E	11.59	-7.7		
5 F	11.19	-7.62		
5 G	11.43	-7.55		
5 H	11.19	-7.62		
6 A	11.09	-7.52		
6 C	11.09	-7.52		
6 D	11.09	-7.52		
6 F	11.09	-7.52		
6 H	11.09	-7.52		
7 A	11.22	-7.65		
7 B	11.39	-7.48		
7 C	11.22	-7.65		
7 D	11.22	-7.65		
7 E	11.76	-7.86		
7 F	11.22	-7.65		
7 G	11.39	-7.48		
7 H	11.22	-7.65		
8 A	11.50	-7.93		
8 C	11.50	-7.93		
8 D	11.50	-7.93		
8 F	11.50	-7.93		
8 H	11.50	-7.93		
9 A	11.80	-8.23		
9 B	12.36	-8.44		
9 C	11.80	-8.23		
9 D	11.80	-8.23		
9 E	11.91	-8		
9 F	11.80	-8.23		
9 G	12.36	-8.44		
9 H	11.80	-8.23		
10 A	12.07	-8.5		
10 C	12.07	-8.5		
10 D	12.07	-8.5		
10 F	12.07	-8.5		
10 H	12.07	-8.5		
11 A	12.36	-8.8		
11 B	12.49	-8.57		
11 C	12.36	-8.8		
11 D	12.36	-8.8		
11 E	12.76	-8.83		
11 F	12.36	-8.8		
11 G	12.49	-8.57		
11 H	12.36	-8.8		

PILE SCHEDULE				
PILE NO.	SUPPLIED LENGTH (m)	TIP ELEVATION (m)	LENGTH PLACED IN WORK (m)	BLOWS/LAST 25mm
12 A	12.39	-8.82		
12 C	12.39	-8.82		
12 D	12.39	-8.82		
12 F	12.39	-8.82		
12 H	12.39	-8.82		
13 A	12.31	-8.74		
13 B	12.61	-8.69		
13 C	12.31	-8.74		
13 D	12.31	-8.74		
13 E	12.73	-8.8		
13 F	12.31	-8.74		
13 G	12.61	-8.69		
13 H	12.31	-8.74		
14 A	12.24	-8.67		
14 C	12.24	-8.67		
14 D	12.24	-8.67		
14 F	12.24	-8.67		
14 H	12.24	-8.67		
15 A	12.26	-8.69		
15 B	12.60	-8.67		
15 C	12.26	-8.69		
15 D	12.26	-8.69		
15 E	12.63	-8.71		
15 F	12.26	-8.69		
15 G	12.60	-8.67		
15 H	12.26	-8.69		
16 A	12.28	-8.71		
16 C	12.28	-8.71		
16 D	12.28	-8.71		
16 F	12.28	-8.71		
16 H	12.28	-8.71		
17 A	12.30	-8.73		
17 B	12.67	-8.74		
17 C	12.30	-8.73		
17 D	12.30	-8.73		
17 E	12.64	-8.71		
17 F	12.30	-8.73		
17 G	12.67	-8.74		
17 H	12.30	-8.73		
18 A	12.32	-8.75		
18 C	12.32	-8.75		
18 D	12.32	-8.75		
18 F	12.32	-8.75		
18 H	12.32	-8.75		
19 A	12.34	-8.77		
19 B	12.68	-8.75		
19 C	12.34	-8.77		
19 D	12.34	-8.77		
19 E	12.49	-8.57		
19 F	12.34	-8.77		
19 G	12.68	-8.75		
19 H	12.34	-8.77		
20 J	12.33	-8.76		
20 M	12.33	-8.76		
20 Q	12.33	-8.76		
20a L	12.31	-8.39		
20a N	12.31	-8.39		
21 J	12.02	-8.45		
21 K	12.02	-8.45		
21 P	12.02	-8.45		
21 Q	12.02	-8.45		
22 J	11.64	-8.07		
22 K	11.64	-8.07		
22 P	11.64	-8.07		
22 Q	11.64	-8.07		
23 J	11.26	-7.69		
23 M	11.26	-7.69		
23 Q	11.26	-7.69		
23a L	11.99	-8.09		
23a N	11.99	-8.09		
23b L	11.21	-7.34		
23b N	11.21	-7.34		

PILE SCHEDULE				
PILE NO.	SUPPLIED LENGTH (m)	TIP ELEVATION (m)	LENGTH PLACED IN WORK (m)	BLOWS/LAST 25mm
24 J	10.88	-7.31		
24 K	10.88	-7.31		
24 P	10.88	-7.31		
24 Q	10.88	-7.31		
25 J	10.50	-6.93		
25 K	10.50	-6.93		
25 P	10.50	-6.93		
25 Q	10.50	-6.93		
26 J	10.11	-6.54		
26 M	10.11	-6.54		
26 Q	10.11	-6.54		
26a L	10.74	-6.88		
26a N	10.74	-6.88		
26b L	10.32	-6.47		
26b N	10.32	-6.47		
27 J	10.04	-6.47		
27 K	10.04	-6.47		
27 P	10.04	-6.47		
27 Q	10.04	-6.47		
28 J	10.04	-6.47		
28 K	10.04	-6.47		
28 P	10.04	-6.47		
28 Q	10.04	-6.47		
29 J	10.04	-6.47		
29 M	10.04	-6.47		
29 Q	10.04	-6.47		
29a L	10.32	-6.47		
29a N	10.32	-6.47		
29b L	10.32	-6.47		
29b N	10.32	-6.47		
30 J	10.04	-6.47		
30 K	10.04	-6.47		
30 P	10.04	-6.47		
30 Q	10.04	-6.47		
31 J	10.04	-6.47		
31 K	10.04	-6.47		
31 P	10.04	-6.47		
31 Q	10.04	-6.47		
32 J	10.04	-6.47		
32 M	10.04	-6.47		
32 Q	10.04	-6.47		
32a L	10.32	-6.47		
32a N	10.32	-6.47		
33 A	11.67	-7.65		
33 C	11.67	-7.65		
33 G	11.67	-7.65		
34 A	11.67	-7.65		
34 C	11.67	-7.65		
34 G	11.67	-7.65		
35 A	11.67	-7.65		
35 B	11.67	-7.65		
35 C	11.67	-7.65		
35 D	11.67	-7.65		
35 E	11.67	-7.65		
35 F	11.67	-7.65		
35 G	11.67	-7.65		
36 A	10.34	-6.37		
36 B	10.34	-6.37		
36 C	10.34	-6.37		
36 D	10.34	-6.37		
36 E	10.34	-6.37		
36 F	10.34	-6.37		
37 A	10.34	-6.37		
37 F	10.34	-6.37		
38 A	10.34	-6.37		
38 F	10.34	-6.37		