

Construction & Refurbishment of Bay Class  
SAR Lifeboat Marine Infrastructures  
Burin, NL  
R.116548.001

2022-01-17

PART 1 - GENERAL

1.1 GENERAL

- .1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
- .2 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .3 Prevent accumulation of wastes which create hazardous conditions.
- .4 Provide adequate ventilation during use of volatile or noxious substances.

1.2 MATERIALS

- .1 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.

1.3 CLEANING DURING CONSTRUCTION

- .1 Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis.
- .2 Provide on-site garbage containers for collection of waste materials and debris.
- .3 Remove waste materials and debris from site on a daily basis.

1.4 FINAL CLEANING

- .1 In preparation for acceptance of the Work perform final cleaning.
- .2 Inspect finishes, fitments and equipment. Ensure specified workmanship and operation.

---

Construction & Refurbishment of Bay Class  
SAR Lifeboat Marine Infrastructures  
Burin, NL  
R.116548.001

---

2022-01-17

- .3 Broom clean exterior paved and concrete surfaces; rake clean other surfaces of grounds.