



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:**

PWGSC/TPSGC Acquisitions
Sherwood Business Centre
161 St. Peters Road/
161, rue St. Peters
2nd Floor, Suite 204/
2ième étage, pièce 204
Charlottetown
Prince Edward Island
C1A 5P7
Bid Fax: (902) 566-7514

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

**Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Sherwood Business Centre
161 St. Peters Road/
2nd Floor, Suite 204
Charlottetown
Prince Ed
C1A 5P7

Title - Sujet Harmonic Filter Installation-JAG	
Solicitation No. - N° de l'invitation ED001-222125/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client ED001-222125	Date 2022-03-14
GETS Reference No. - N° de référence de SEAG PW-\$PWC-035-4568	
File No. - N° de dossier PWC-1-44017 (035)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Atlantic Daylight Saving Time ADT on - le 2022-03-17 Heure Avancée de l'Atlantique HAA	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Beausoleil (PWC), Timothee	Buyer Id - Id de l'acheteur pwc035
Telephone No. - N° de téléphone (902) 388-8377 ()	FAX No. - N° de FAX (902) 566-7514
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
ED001-222125
Client Ref. No. - N° de réf. du client
R.116327.001

Amd. No. - N° de la modif.
002
File No. - N° du dossier
PWC-1-44017

Buyer ID - Id de l'acheteur
PWC035
CCC No./N° CCC - FMS No./N° VME

SOLICITATION AMENDMENT 002

THE FOLLOWING AMENDMENTS/CLARIFICATIONS TO THE BID DOCUMENT ARE EFFECTIVE IMMEDIATELY. THE AMENDMENTS/CLARIFICATIONS SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

CONSTRUCTION TIME (BA06)

Notice is hereby given that the construction time deadline has been extended to: **March 31, 2023**

ADDITIONAL CLARIFICATION:

Reference Drawing E1 – Electrical Single Line Distribution Drawing (see attached)

1. Reference Detail 2/E1:
 - a. Location of existing switchgear lineup and associated new BUS N1 (Cell 7) extension to be modified as shown in attached *Sketch ESK-01*.
 - b. Location of cable tray routed between new BUS N1 (Cell 7) and AHF#1 to be located below existing cablethrough NO. 2 and NO. 4 as shown in attached *Sketch ESK-01*.

Reference Specification Section 01 14 10

1. Reference Article 1.2: For clarification purposes only, a planned facility wide temporary power shutdown is expected to occur sometime in September 2022 to facilitate maintenance within the Main Electrical Room as well as other areas of the facility. It is anticipated that work activities for this project which require a power shutdown could also be scheduled around this planned temporary power shutdown to minimize disruption to the facilities operations.

Reference Specification Section 26 35 33

1. Reference Article 2.1.1: For clarification purposes only, the facilities existing Schneider PME power monitoring software has been used to record historic power quality and harmonic distortion events at select points throughout the electrical distribution system, and can be used to monitor and record improvements in power quality after the active harmonic filters have been installed.

Solicitation No. - N° de l'invitation
ED001-222125
Client Ref. No. - N° de réf. du client
R.116327.001

Amd. No. - N° de la modif.
002
File No. - N° du dossier
PWC-1-44017

Buyer ID - Id de l'acheteur
PWC035
CCC No./N° CCC - FMS No./N° VME

2. Reference Article 2.1.1.15.1: For clarification purposes only, these additional tie breaker current transformers are to be installed on each side of the existing Square-D MasterPact NWH1 Series, 3200AF/3200AT LSIG tie breaker. In addition to the current transformers that are to be installed at each of the two (2) main breakers, there is to be a set of current transformers installed on the BUS NO #1 side of the tie breaker which are connected to AHF#1, and a set of current transformers installed on the BUS NO #2 side of the tie breaker which are to be connected to AHF#2. This arrangement is to provide all necessary current signals to control active harmonic filters both independently and automatically for all main breaker and tie breaker configurations. All field measurements required for these main and tie breaker current transformers are to be made during the first scheduled switchgear shutdown which is required to measure busbar for the for new switchgear Cell 7.

By submission of its bid, the Bidder confirms that it has read and understands the requirements expressed in all amendments and has included all costs of these requirements in the Total Bid Amount.
ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

