








# Addendum Addenda

No./No  1
-----------------

Project Description / Description de projet <b>M50 AEP Emergency Shower / M50 Douche d'urgence AEP</b>		
Project No./No de projet <b>5803</b>	Departmental Representative / représentant ministériel <b>Allan Mackenzie</b>	Date <b>6-Apr-2022</b>
Solicitation No./N° de sollicitation <b>21-58118</b>		
Notice: This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.		
Nota: Cet addenda fait partie intégrale des dossiers d'appel; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.		






Item No	Description
1	Dessin 5803-M01 Nouvelles notes de travail, supprimer la note 11 : 11. NOUVEL ENSEMBLE DE DOUCHE D'URGENCE. NORME D'ACCEPTATION : SECURITE HUGES. MODÈLE EXP-18GS/75G AVEC PULVERISATEUR CORPOREL OPTIFLEX. FOURNIR UN NOUVEAU TUYAU D'ÉVACUATION 38DN ET LE CONNECTER À LA TUYAUTERIE SANITAIRE 75DN SITUÉE DANS LE VIDE DE PLAFOND AU REZ-DE-CHAUSSÉE À L'ENTRÉE DU SIPHON EN P. FIXER LA DOUCHE AU SOL AVEC DES TIGES FILETÉS GALVANISÉS DE 4 3/8" DE DIAMETRE A UNE PROFONDEUR D'AU MOIN 75 mm. NORME D'ACCEPTATION : FABRICANT : HILTI , PARTIE : HIT-RE 500-SD
2	Dessin 5803-M01, Nouvelles notes de travail, changer la note 19 en : 19. LA NOUVELLE DOUCHE D'URGENCE NÉCESSITERA UNE MANIPULATION COMPLEX, DU CORRIDOR A LA SALLE 289B, EN PASSANT PAR LE LABORATOIRE ADJACENT DANS LA SALLE 295. L'ACCÈS AU LABORATOIRE EXISTANT DOIT ÊTRE STRICTEMENT COORDONNÉ AVEC LE CNRC. NOUVELLE DOUCHE D'URGENCE NORME D'ACCEPTATION : FABRICANT : HUGHES, MODÈLE SD32K45G AVEC LAVE-OEIL/VISAGE, ÉCRANS ET PUISARD. FIXER LA DOUCHE AU SOL AVEC DES TIGES FILETÉES GALVANISÉES DE 4 3/8" Ø D'UN EMPREINTEMENT MINIMUM DE 75 mm. NORME D'ACCEPTATION : FABRICANT : HILTI, PIÈCE : HIT-RE 500-SD. FOURNIR UN NOUVEAU TUYAU DE DRAINAGE ET LE RELIER A LA TUYAUTERIE SANITAIRE 75DN SITUEE DANS L'ESPACE DU PLAFOND AU REZ-DE-CHAUSSEE A L'ENTREE DU P-TRAP, RAPIÉCER ET FINIR TOUTES LES SURFACES AFFECTEES PAR LE TRAVAIL POUR CORRESPONDRE AUX SURFACES ADJACENTES EXISTANTES.

## Mandatory Site Visit Attendance / Visite de chantier obligatoire

Project Description / Description de projet		M50 AEP Emergency Shower		Closing Date		April 13, 2022	Closing time		2:00 PM								
Solicitation No./N° de sollicitation		21-58118		Project No./No de projet		5803	1st Showing		March 30, 2022								
Departmental Representative / représentant		Allan Mackenzie		Signature		Alternate/Questions deadline		April 4, 2022	Addendum Deadline		April 6, 2022	2nd Showing		March 31, 2022	Showing Time		9:00 AM
COMPANY/COMPAGNIE	NAME/NOM	SIGNATURE	PHONE/TELEPHONE	EMAIL/COURRIEL													
<b>30-Mar-22</b>																	
<b>9:00am</b>																	
TPH Plumbing & Heating	Sylvain Bergeron		613-914-4350	kevinmceil@tphinc.ca													
Fred Trotter Construction Ltd.	Lomas Lakra		613-745-8688	bids@trotter.ca													
Premium Construction	Sabbi Kalsi		613-301-6005	sabbi@premium-construction.ca													
<b>9:30am</b>																	
Alejandro Sanchez	Argca Associates Inc.		613-981-8233	asanchez@argcaassociates.com													
James Knight	GK Plumbing & Heating Inc.		613-241-5000	info@gkplumbingandheatinginc.ca													
Justin Gauthier	GK Plumbing & Heating Inc.		613-241-5000	info@gkplumbingandheatinginc.ca													
Victor Hoyos	Argca Associates Inc.		613-255-5403	vhoyos@argcaassociates.com													
<b>10:00am</b>																	

**Mandatory Site Visit Attendance / Visite de chantier obligatoire**

Project Description / Description de projet		M50 AEP Emergency Shower		Closing Date	April 13, 2022	Closing time	2:00 PM
Solicitation No./N° de sollicitation		21-58118		Project No./No de projet	5803	1st Showing	March 30, 2022
Departmental Representative / représentant		Allan Mackenzie		Signature		2nd Showing	March 31, 2022
				Alternate/Questions deadline	April 4, 2022	Addendum Deadline	April 6, 2022
				PHONE/TELEPHONE	31-Mar-22		

COMPANY/COMPAGNIE	NAME/NOM	SIGNATURE	PHONE/TELEPHONE	EMAIL/COURRIEL
<b>9:00am</b>				
Climate Works	Michelle Witt		613-838-9989 Ext 105	<a href="mailto:mwitt@climateworks.ca">mwitt@climateworks.ca</a>
Terlin Construction Ltd.	Nastasha Amo		613-621-2779	<a href="mailto:nastasha.amo@terlin.ca">nastasha.amo@terlin.ca</a>
Kenbay Plumbing Ltd.	Phil Bourdeau		613-850-4779	<a href="mailto:kenbayplumbing@hotmail.ca">kenbayplumbing@hotmail.ca</a>
3V Mechanical	Louis Marion		613-402-9446	<a href="mailto:louis@3vmechanical.ca">louis@3vmechanical.ca</a>
Baxtec Mechanical	Graham Finn		613-738-7450	<a href="mailto:gfinn@baxtec.com">gfinn@baxtec.com</a>
<b>9:30am</b>				
<b>10:00am</b>				

