



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving - PWGSC / Réception des soumissions -
TPSGC

11 Laurier St. / 11, rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau, Québec K1A 0S5

Bid Fax: (819) 997-9776

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Ship Refits and Conversions / Radoubss et
modifications de navires and / et

11 Laurier St. / 11, rue Laurier

6C2, Place du Portage

Gatineau, Québec K1A 0S5

Title - Sujet CCGS George R. Pearkes - VLE	
Solicitation No. - N° de l'invitation F7049-200083/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client F7049-200083	Date 2022-04-11
GETS Reference No. - N° de référence de SEAG PW-\$\$\$MD-029-28531	
File No. - N° de dossier 029md.F7049-200083	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Eastern Daylight Saving Time EDT on - le 2022-06-07 Heure Avancée de l'Est HAE	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Jeddi, Loubna	Buyer Id - Id de l'acheteur 029md
Telephone No. - N° de téléphone (873) 45--383 ()	FAX No. - N° de FAX (819) -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation Amendment # 005

This amendment is hereby raised :

- 1. To include Questions and the Responses for the solicitation.**
 - 2. To update Annex A - Statement of Work (SOW), Part B SOW Item H-32.**
-

1. Questions and the Responses for the solicitation.

Q#1: General Section - 3.11 and 4.2.7 – 4.2.8 - Is there a requirement for sheltering the vessel for lead or any hazardous abatement activities?.

A#1: It is the responsibility of the Contractor to supply and install all sheltering required to contain, abate and dispose of all grit, lead coatings and any other hazardous materials, as per Provincial Guidelines, in the areas of the vessel detailed in the Hazardous Material Matrix and the SOW. This includes specifications H-37 - H-40 that were added to the SOW in Amendments # 001 & 003. All related costs for shelters must be included in the Contractor's firm pricing for this work.

The Contractor must also supply and install all shelters necessary to carry out all coating work detailed in the SOW. The Contractor must ensure that all preparatory and coating application work strictly follows the paint manufacturer's application guidelines and NACE preparatory/application standards. Therefore, the Contractor must supply and install all sheltering around the vessel as necessary to ensure that these guidelines and standards are being strictly followed. All related costs for the supply and installation of such shelters must be included in the Contractor's firm pricing.

2. To update Annex A - Statement of Work (SOW), Part B SOW Item H-32.

Under Part B, SOW Item H-32 – Galley Upgrades

- Section 3.2.1

Delete the existing paragraph in its entirety and replace it with the following:

The Contractor must strip out a section of the forward bulkhead in the galley and cut a temporary insert in the superstructure bulkhead, a minimum of 38" wide x 70" high. The galley is already being stripped out as part of this specification, however, the Contractor must identify, temporarily remove, store and re-install upon the completion of work any remaining interference items in the galley area and on the external main deck forward of the galley as required to remove/re-install the insert. This includes all equipment, paneling, deckheads, insulation, piping, lighting, cabling, ductwork, stairwells, save-alls, vents/vent heads, firebox, labels and ladder rungs as required. This insert must be used for removing and installing all galley equipment on/off the vessel and must be securely covered over with a tarp and a temporary plywood door when not in use to keep all potential weather and debris out of the galley. A photo is below of the external main deck area where the insert must be cut for further clarification.

All work must be carried out to the satisfaction of the CCGTA, CE and ABS inspection authority. After all equipment is installed in the galley area, the temporarily removed insert, and any temporarily removed interference piping or save-all sections, must be fully welded into to the superstructure/deck by certified CWB welders with appropriate weld procedures and in accordance with IACS No. 47 Shipbuilding and

Repair Quality and CWB Standards. All welds must receive 100% MPI and 100% Visual inspection upon completion and all affected steel and welds must receive 2 coats of marine grade primer. All removed insulation must be replaced with new, marine grade equivalent upon the completion of work.



- Section 3.2.5

Delete the existing paragraph in its entirety and replace it with the following:

The Contractor must remove all of the S/S cabinets and counter tops to allow for the removal of ceiling panels and installation of new bulkhead coverings. The Contractor must provide indoor, heated, environmentally controlled storage space for the SS cabinets and countertops for the duration of the project. The Contractor must take care to protect the cabinets and countertops while removing/re-installing on the vessel and while they are in storage. Any damaged units must be repaired or replaced by the Contractor at their expense.

- In the appended document titled "Smart Galley Designs – Layout Arrt and Equipment Info," delete all references to the "Tarrison 4 Burner Induction Cooktop" and Insert "Garrison 4 Burner Induction Cooktop." All other details must stay the same.

Solicitation No. - N° de l'invitation
F7049-200083/A
Client Ref. No. - N° de réf. du client
F7049-200083

Amd. No. - N° de la modif.
005
File No. - N° du dossier
029md F7049-200083

Buyer ID - Id de l'acheteur
029md
CCC No./N° CCC - FMS No./N° VME

