

PART 1 - GENERAL

1.1 RELATED
SECTIONS

- .1 Section 01 35 43 - Environmental Procedures.
- .2 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

1.2 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.

1.3 GENERAL
REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.4 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.

1.5 MEASUREMENT FOR
PAYMENT

- .1 All cost for items in this section is to be measured in fixed price items including all plant, labour, material required to complete this work as indicated on drawings and specifications.

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.

3.2 REMOVAL

- .1 Demolition, removal and disposal of existing timber cribs and walkway structure.
- .2 Removal and disposal of existing floating docks and wooden ramp as shown on drawings.
- .3 Removal and disposal of existing reinforced concrete launchway slab as indicated on drawings.
- .4 Class B dredging to remove existing material down to elevations shown on drawings.
- .5 Remove in their entirety all materials and objects specified for removal.
- .6 Do not disturb adjacent work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, relocated or turned over to owner, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site. Refer to Sections 01 35 43 - Environmental Procedures and Section 01 74 21 - Construction/Demolition Waste Management and Disposal for disposal requirements.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.

3.4 RESTORATION
(Cont'd)

- .2 Reinstall areas and existing works outside areas of
demolition to conditions that existed prior to
commencement of work.