

PART 1 - GENERAL

1.1 RELATED
REQUIREMENTS

- .1 Section 31 22 13 - Rough Grading.
- .2 Section 31 32 19.01 - Geotextiles.
- .3 Section 31 36 19 - Gabion Mattress.

1.2 MEASUREMENT FOR
PAYMENT

- .1 Mass Excavation: Measurements for payment to be made under this section will be measured by the cubic metre (m³). Include costs in unit prices for item for which excavating and backfilling is required. Include the cost of all plant, labour, equipment required to complete the work as specified.

1.3 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
 - .1 ASTM C 117-04, Standard Test Method for Material Finer than 0.075 mm (No.200) Sieve in Mineral Aggregates by Washing.
 - .2 ASTM C 136-05, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - .3 ASTM D 422-63 2002, Standard Test Method for Particle-Size Analysis of Soils.
 - .4 ASTM D 698-00a1, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³) (600 kN-m/m³).
 - .5 ASTM D 4318-05, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.

1.4 DEFINITIONS

- .1 Excavation classes: two classes of excavation will be recognized; common excavation and rock excavation.
 - .1 Rock: solid material in excess of 0.25 m³ and which cannot be removed by means of heavy duty mechanical excavating equipment with 0.95 to 1.15 m³ bucket. Frozen material not classified as rock.
 - .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
- .2 Waste material: excavated material unsuitable for use in Work or surplus to requirements.

1.4 DEFINITIONS
(Cont'd)

- .3 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
- .4 Unsuitable materials:
- .1 Weak and compressive materials under excavated areas.
- .2 Frost susceptible materials under excavated areas.
- .3 Frost susceptible materials:
- .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D 4318, and gradation within limits specified when tested to ASTM D 422 and ASTM C 136: Sieve sizes to CAN/CGSB-8.1.
- .2 Table:
- | <u>Sieve Designation</u> | <u>% Passing</u> |
|--------------------------|------------------|
| 2.00 mm | 100 |
| 0.10 mm | 45 - 100 |
| 0.02 mm | 10 - 80 |
| 0.005 mm | 0 - 45 |
- .3 Coarse grained soils containing more than 20 % by mass passing 0.075 mm sieve.
- .5 Unshrinkable fill: very weak mixture of cement, concrete aggregates and water that resists settlement when placed in utility trenches, and capable of being readily excavated.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Type 1 fill: to the following requirements:
- .1 Crushed, pit run or screened stone, gravel or sand.
- .2 Gradations to be within limits specified when tested to ASTM C 136 . Sieve sizes to CAN/CGSB-8.1.
- .2 Type 2 fill: selected material from excavation or other sources, approved by Departmental Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.
- .1 Table:

<u>Sieve</u>	<u>% Passing</u>
<u>Designation</u>	<u>Type 1</u>

	Type 1
101.6 mm	100
50 mm	75-100
4.75 mm	25-55
1.2 mm	10-35
0.3 mm	5-20
0.075 mm	0-12

PART 3 - EXECUTION

3.1 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.

3.2 EXCAVATION

- .1 Excavate to lines, grades, elevations and dimensions as indicated.
- .2 Remove all cribwork and other obstructions encountered during excavation in accordance with Section 02 41 16 - Sitework, Demolition and Removal.
- .3 Excavation must not interfere with bearing capacity of adjacent foundations.
- .4 Dispose of surplus and unsuitable excavated material in approved location off site.
- .5 Do not obstruct flow of surface drainage.
- .6 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .7 Notify Departmental Representative's approval of excavation is reached.
- .8 Obtain Departmental Representative's approval of completed excavation.

3.3 FILL TYPES AND COMPACTION

- .1 Use fill of types as indicated.

3.4 BACKFILLING

- .1 Do not proceed with backfilling operations until Departmental Representative has inspected and approved installations.
- .2 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
- .3 Do not use backfill material which is frozen or contains ice, snow or debris.
- .4 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
- .5 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
- .6 Backfilling around installations:
 - .1 Place bedding and surround material as specified elsewhere.
 - .2 Do not backfill around or over cast-in-place concrete within 24 hours after placing of concrete.
 - .3 Place layers simultaneously on both sides of installed Work to equalize loading. Difference not to exceed 1.0 m.

3.5 RESTORATION

- .1 Upon completion of Work, remove waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.
- .2 Clean and reinstate areas affected by Work as directed by Departmental Representative.
- .3 Restore site to its normal state prior to excavation.