

PART 1 **GENERAL**

1.1 **RELATED SECTIONS**

- .1 Section 01 50 00 – Temporary Facilities

1.2 **INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 **GUARD RAILS AND BARRICADES**

- .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide barricades along wharf structure when wheelguard is removed.
- .3 Provide as required by governing authorities.

1.4 **ACCESS TO SITE**

- .1 Do not block existing site access roads, ramps and runways.
- .2 If authorized to use existing roads for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractor's use of roads.
- .3 Provide and maintain access to adjacent harbour facilities.

1.5 **PUBLIC TRAFFIC FLOW**

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect the public.

1.6 **FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.7 **PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

END OF SECTION