

1 GENERAL

1.01 REFERENCES

- .1 National Building Code of Canada, 2005.

1.02 INSTALLATION AND REMOVAL

- .1 Provide construction facilities in order to execute work expeditiously.
- .2 Prepare site plan indicating location and dimensions of area to be fenced and used by contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .3 Identify areas which have to be surfaced with Maintenance Grade 3 (MG3) gravel to prevent tracking of mud.
- .4 Indicate use of supplemental or other staging area.
- .5 Remove from site all such work after use.

1.03 SITE STORAGE/LOADING

- .1 Comply with the requirements of Section 01 35 27, Special Procedures: Airports in Use, concerning height restrictions for storage.
- .2 Do not load or permit to load any part of work with a weight or force that will endanger the work.

1.04 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work.
- .2 Provide and maintain adequate access to project site as well as adjacent roadways.
- .3 If authorized to use existing roads for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractors' use of roads.

1.05 SECURITY

- .1 Secure work site at night and other times outside of working hours as deemed necessary to protect the site against entry.
- .2 Comply with the requirements of Section 01 35 27, Special Procedures: Airports in Use.

1.06 SITE FACILITIES

- .1 The contractor shall provide all temporary facilities necessary for the

performance of all work and direct personnel requirements. This shall include, but not limited to the following:

- .1 Sanitary facilities.
- .2 Electricity/lighting.
- .3 Eye wash stations.
- .4 First aid stations.

1.07 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in a manner to cause least interference with work activities.

1.08 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.09 CONSTRUCTION SIGNAGE

- .1 Only Project Identification signboard, notices of safety or notice instructions are permitted on site.
- .2 Signs and notices for safety and instruction shall be in both official languages, Graphic symbols shall conform to CAN3-Z321.
- .3 Maintain approved signs and notices in good condition for duration of project, and dispose of off site on completion of project or earlier if directed by DR.

1.10 REMOVAL OF TEMPORARY FACILITIES

- .1 Remove temporary facilities from site when directed by DR.

1.11 MEASUREMENT FOR PAYMENT

- .1 No separate measurement for payment shall be made for items under this section. Include all costs for Temporary Facilities in the Lump Sum portion of the work on the Bid and Acceptance Form.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED

PSPC	CONSTRUCTION FACILITIES	SECTION 01 52 00
STEPHENVILLE AIRPORT		PAGE 3
ASPHALT REPAIRS		
PROJECT NO. R.112134.003		APRIL 2021

END OF SECTION