



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
PWGSC/TPSGC Acquisitions
Sherwood Business Centre
161 St. Peters Road/
161, rue St. Peters
2nd Floor, Suite 204/
2ième étage, pièce 204
Charlottetown
Prince Edward Island
C1A 5P7
Bid Fax: (902) 566-7514

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Sherwood Business Centre
161 St. Peters Road/
2nd Floor, Suite 204
Charlottetown
Prince Ed
C1A 5P7

Title - Sujet Daniel J. MacDonald (DJM) Building Daniel J. MacDonald (DJM) Building Modernization, Charlottetown, PE	
Solicitation No. - N° de l'invitation ED001-212664/B	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client ED001-212664	Date 2022-07-06
GETS Reference No. - N° de référence de SEAG PW-SPWC-034-4575	
File No. - N° de dossier PWC-2-45003 (034)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Atlantic Daylight Saving Time ADT on - le 2022-07-21 Heure Avancée de l'Atlantique HAA	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Stockman (PWC), Sonia	Buyer Id - Id de l'acheteur pwc034
Telephone No. - N° de téléphone (506) 961-7412 ()	FAX No. - N° de FAX (506) 851-6759
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment No. six (6) is raised to include the following :

1. Answer the following questions:

Q2. Every floor with window sprinklers must have a separate independent zone, by code, from the floor zone sprinklers. Again can we have (1) separate zone per floor rather (4) independent zones

A2. The Contractor is to provide a complete and operational fire protection system in compliance with all applicable codes, standards and code consultant report, as noted on the M40 series drawings and Division 21 specifications.

Q3. Are all the VFD's supplied by section 23? On the points list it shows supplied by section 25.

A3. VFDs to be supplied by Division supplying the equipment associated with the respective VFDs. VFDs to comply with requirements noted in Specification section 23 05 14 Variable Frequency Drives. Points list will be revised accordingly as part of the Addenda 2.

Q4. Are all the control valves by section 25? On the Points list is shows some valves supplied by section 23. Example: Fan coils, wall fines, FPB, Force flow heater.

A4. All the control valves to be supplied by Division 25. Points list will be revised accordingly as part of the Addenda 2.

Q5. I believe you are missing the Air flow station for Exhaust fan 3 on the point list and control details. The only place it's shown is on drawings M73-04.

A5. Air flow station is not required for exhaust fan EF-3. M73-04 will be revised accordingly as part of the Addenda 2.

Q6. Reference A21-00 to A21-06- Demountable partitions -Please provide Elevations with details as to the type of demountable walls (ex: solid, glass, working walls etc.)

A6. Elevations are not required. There are section diagrams provided on sheet A01-07 under the Glazed screen walltypes and plan details at 3/4 A53-02. The door heights (full height) are called out in the door schedule & specification

Q7. Is there any problem with running the standpipe a/o combined standpipe/sprinkler risers in the stairwells?

A7. There are currently existing slab opening for risers in the locations shown that are being reused. There are currently no such penetrations in the existing stairs slabs nor any clear information that such penetrations will be possible. The intent is to minimize construction activity in the stairwells.

Q8. Would 240KA/Phase be acceptable for TVSS Unit, versus Eaton Standard of 250KA?

A8. 240 kA/Phase is acceptable

Q9. Are all accessories listed in 26 28 16.02 2.4.1 on all MCCB, or, only if indicated on drawings?

A9. Include additional accessories if indicated on single line diagram.

Q10. In the basement area around the garage door entrances you specify dry pipe system rather than wet pipe system. Why is there a need for heat tracing? Drum drips are not required to be heat traced.

A10. Heat tracing refers to the wet standpipe section of piping in the area, not to the dry sprinkler system. Clarification in Addenda 2

Q11. Is Owner's Meter for the Fire Pump required in Switchboard AAA? It is shown on Elevation Detail 4/E03-01, but not shown on SLD 1/E04-01

A11. Digital meter required on fire pump as per detail 4/E03-01

Q12. Will the building have occupants at any point during construction? a. Can work throughout the course of the project be done during the day (assuming on schedule), b. Or will night/weekend work be required (i.e. certain areas or times, etc.)? c. Will there be a phased approach?

A12. The building will be unoccupied during construction with the exception of any Departmental Representatives for the purposes construction administration.

Q13. Reference Section 10 23 26 - Glass Partition Systems- Partition Type P-3.1A notes an STC rating of 36. These same rooms in the A02-10 Series along with the Door Hardware Schedule show STC 35 ratings. Can you please clarify?

A13. Refer to General Note 2 on drawing A01-07

Q14. Reference Section 10 23 26 - Glass Partition Systems-- Partition Type P-3.1B notes an STC rating of 46. These same rooms in the A02-10 Series along with the Door Hardware Schedule show STC 45 ratings. Can you please clarify?

A14. Refer to General Note 2 on drawing A01-07

2. The following Addendum 002 to the tender is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

Solicitation No. - N° de l'invitation
ED001-212664/B

Amd. No. - N° de la modif.
006

Buyer ID - Id de l'acheteur
pwc034

Client Ref. No. - N° de réf. du client
R.056687.005

File No. - N° du dossier
PWC-2-45003

CCC No./N° CCC - FMS No./N° VME
