



**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
PWGSC/TPSGC Acquisitions  
Sherwood Business Centre  
161 St. Peters Road/  
161, rue St. Peters  
2nd Floor, Suite 204/  
2ième étage, pièce 204  
Charlottetown  
Prince Edward Island  
C1A 5P7  
Bid Fax: (902) 566-7514

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
Public Works and Government Services Canada  
Sherwood Business Centre  
161 St. Peters Road/  
2nd Floor, Suite 204  
Charlottetown  
Prince Ed  
C1A 5P7

<b>Title - Sujet</b> Daniel J. MacDonald (DJM) Building Daniel J. MacDonald (DJM) Building Modernization, Charlottetown, PE	
<b>Solicitation No. - N° de l'invitation</b> ED001-212664/B	<b>Amendment No. - N° modif.</b> 008
<b>Client Reference No. - N° de référence du client</b> ED001-212664	<b>Date</b> 2022-07-11
<b>GETS Reference No. - N° de référence de SEAG</b> PW-SPWC-034-4575	
<b>File No. - N° de dossier</b> PWC-2-45003 (034)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> Atlantic Daylight Saving Time ADT <b>on - le 2022-08-03</b> Heure Avancée de l'Atlantique HAA	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Stockman (PWC), Sonia	<b>Buyer Id - Id de l'acheteur</b> pwc034
<b>Telephone No. - N° de téléphone</b> (506) 961-7412 ( )	<b>FAX No. - N° de FAX</b> (506) 851-6759
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

This Solicitation Amendment No. eight (8) is raised to include the following :

1. Answer the following questions:

**Q23.** Could we request of copy of the sprinkler system as-builts?

**A23.** As-builts, can be provided to the successful bidder, with the condition as noted in General Note 2 of the M40 series drawings that all existing services shown are approximate and based on existing drawings. Contractor shall verify all locations on site.

**Q24.** I would like to submit the following questions regarding Electrical Specification section 28 31 00.02 Multiplex Fire Alarm and Voice Communications Systems.

- Paragraph 2.2.4 references Beam Detectors in the Atrium; there is no symbol(s) on the legend, no description in the specification, and nothing shown in the Atrium - are beam detectors required?
- Paragraph 2.3.1.12 references 20 column, panel mounted strip printer. The Keltron VS4905/5 strip printer has been discontinued by the manufacturer.
- Paragraph 2.3.1.13 references remote serial printer, but no location shown – is a remote serial printer required?
- Paragraph 2.10.1 references 25V RMS as the voltage for the amplifiers – can we use 70V RMS for the amplifiers?
- Paragraph 2.16 references Telephone Cabinet with locking door on the floors– can we substitute with Fireman’s Phone Jack on the floors and Firefighter Phones in Cabinet at the FACP?

**A24.** There are spot smoke detectors in Atrium accessible ceiling, please follow the drawings; the printers not required; 70V RMS for amplifier is acceptable; we prefer the firefighters phones in cabinets on floors as well as at FACP.

**Q25.** The Floor boxes. On detail 6 E03-04 you show AVFS, does that also include the A,B,C,D,E,G,H as well. If not what conduit requirements do they have ?

**A25.** Detail 6 on drawing E03-04 applies to the floor box for the AV systems, refer to detail 7 and 6 on drawing E03-01

**Q26.** E08-01 parking level shows 2-4” conduit going to Jean Canfield. Jean canfield means trenching threw city streets about 800 meters, if this is correct we will need more information including a drawing showing the route etc.

**A26.** The intent is to provide 2-4" conduits inside the building up to the exterior wall at gridlines 1/B-C. There is an existing ducts between two buildings that will be used for SSC cabling.

**Q27.** E 08-01 The 103mm sleeves on all floors, is this installed as per detail 5/E03-04?

**A27.** Yes, as per detail 5 on drawing E03-04

**Q28.** 28 10 10 3.2.11.8 suggest that each CCTV location to have a home run of 1". Is this correct? Or can 1 conduit pick up more than one ?

**A28.** Home runs for cameras is separate from other security devices. Size of the conduits depends on total quantity of wires for 40% fill of conduit.

**Q29.** E09-01 the security rack/panel locations need to be identified which room they below in.

**A29.** Refer to drawing E60-02 for access control power supply (PS) and security panel (SP) locations.

**Q30.** Regarding the drawings/specifications for Division 10 14 00 (Signage): There doesn't appear to be drawings that show the signage itself, only showing locations of signage in the floor plans. The door schedule doesn't show signage requirement on each area either. The A91 set of drawings indicates to refer to the signage package for extent of locations. Please provide the signage package/schedule to determine locations and quantities.

**A30.** Signage package was issued as NORR Addendum No. 1

## **2. Reference Q10 Amendment 6- Revised answer**

**Q10.** In the basement area around the garage door entrances you specify dry pipe system rather than wet pipe system. Why is there a need for heat tracing? Drum drips are not required to be heat traced.

**A10.** Heat tracing refers to the wet standpipe section of piping in the area, not to the dry sprinkler system. Clarification will be issued as part of Addendum No. 2.

The area between the garage door entrances could be subjected to freezing temperatures, if the garage doors stayed open for a considerable amount of time in the winter, during power outages or strong wind weather.

**All other terms and conditions remain the same.**