


RETURN BIDS TO:

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-855-983-1808

Bid Email: soumissionsami-bidsrpc@pc.gc.ca

This is the only acceptable email address for responses to the bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. The Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

REVISION 003 TO A INVITATION TO TENDER

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

Issuing Office:

Parks Canada Agency
National Contracting Services
Calgary, AB

Title: Simpson Trailhead & Bow Lake Privies – Kootenay & Banff National Parks	
Solicitation No.: 5P468-22-0056/A	Date: July 15, 2022
Amendment No.: 003	
Client Reference No.:	
GETS Reference No.: PW-22-00999940	

Solicitation Closes: At: 2:00 PM On: July 21, 2022	Time Zone: MDT
---	--------------------------

F.O.B.: Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
Address Enquiries to: Jen Maheu	
Telephone No.: 587-432-8458	Fax No.: 1-855-983-1808
Email Address: jennifer.maheu@pc.gc.ca	
Destination of Goods, Services, and Construction: See Herein	

TO BE COMPLETED BY THE BIDDER

Vendor/ Firm Name:	
Address:	
Telephone No.:	Fax No.:
Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):	
Signature:	Date:

Amendment 003

This amendment is raised to distribute the answers to bidder questions and makes revisions to the tender package.

A. QUESTIONS & ANSWERS

Q5 Comment re aggregates. 1.9mm or less compacted gravel is not an available product. typically 18mm road crush or 18 mm washed rock would be used in this application

A5 PCA is not accepting product or material submission requests for approval prior to tender award. Fill and aggregate materials must be pre-approved by the Departmental Representative prior to installation (as per 5.6.2).

Pathway access to the privys must meet CSA requirements, including slope, width, maximum threshold heights.

Q6 Pathway, site grading, and final landscaping plans to be submitted to DR for review and approval prior to construction. Is PCA requesting that the contractor provide design build for site grading , landscaping and pathways? To what extent would pca expect design - is the contractor to supply surveyed existing site plans with new plan designed by geotechnical and full survey of as built conditions post construction?

A6 PCA is requesting that pathway, site grading, and final landscaping plans to be submitted to DR for review and approval prior to construction. A site survey of as-built conditions is not required.

Contractor must provide a site plan that establishes appropriate site grading and drainage plan at Bow and Simpson sites. As per 5.6.1 and 5.6.2: A site plan must include appropriate area grading and drainage plan.

Q7 Is there a geotechnical report of subsurface conditions available for this project ?

A7 No.

Q8 is there a site plan available showing the exact extent of the work described in 5.5.1 to be performed

A8 No.

As per SOW and reference documents and photos provided;

- Bow Lake site: demolish existing privy and supply and install new pre-cast vault privy in same location; re-establishing existing accessible paths with appropriate slope and drainage plan.
- Simpson Trailhead site: install new pre-cast vault privy with accessible paths with appropriate slope and drainage plan.

B. TENDER PACKAGE REVISIONS

IN: Statement of Work Under 5.4.1.

ADD: Vault size capacity to be minimum of 5800 litres (1500 US Gallons).

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED.