


1
E-2 BOILER ROOM - EXISTING ELECTRICAL PLAN
1 : 50

NOTES:

1. MAINTAIN THE INTEGRITY OF ALL EXISTING SYSTEMS REQUIRED TO REMAIN OPERATIONAL. IDENTIFY ALL CIRCUIT BREAKERS, WIRING, JUNCTION BOXES AND DEVICES PRIOR TO PROCEEDING WITH WORK. CONTACT DEPARTMENTAL REPRESENTATIVE IF UNSURE BEFORE SHUTDOWNS, DEMOLITION OR RELOCATION OF ANY DEVICES.
2. ALL ITEMS SHOWN DASHED WITH AN "E" ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A "D" ARE TO BE DISCONNECTED AND REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO SOURCE.
3. WIRE AND CONDUIT CONFLICTING SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
4. PROVIDE NEW BLANK STAINLESS STEEL COVERPLATES FOR ALL ABANDONED OUTLETS.
5. REPORT ANY DISCREPANCIES BETWEEN THE CONTRACT DOCUMENTS AND SITE OBSERVATIONS TO DEPARTMENTAL REPRESENTATIVE.
6. NOT ALL DEVICES AND ELECTRICAL EQUIPMENT IS BEING SHOWN ON ELECTRICAL DRAWINGS. REMOVE ALL EXISTING ELECTRICAL DEVICES SHOWN OR NOT LOCATED ON WALLS OR PORTIONS OF THE BUILDING BEING AFFECTED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS, INCLUDED AND NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECTED TO ANY WORK.
7. REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
8. ALL EXISTING DEVICES ON WALLS, FLOORS OR CEILING NOT BEING AFFECTED BY THIS PROJECT ARE TO REMAIN.
9. SYSTEMS AND DEVICES IN AREAS OF LIMITED SCOPE OF WORK TO REMAIN OPERATIONAL PROVIDE ALL MODIFICATIONS TO ACCOMMODATE SCOPE OF WORK.
10. TEMPORARILY DISCONNECT AND REMOVE ALL DEVICES THAT MAY OBSTRUCT THE PATH OF TRAVEL FOR NEW BOILERS. RECONNECT AND TEST ALL DEVICES UPON INSTALLATION OF NEW BOILERS. CONFIRM EXISTING DEVICES ON SITE.
11. RELOCATE ALL EXISTING DEVICES TO ACCOMMODATE ARCHITECTURAL, STRUCTURAL, ETC. MODIFICATIONS. RE-ROUTE AND RE-WIRE AS REQUIRED. CONFIRM EXISTING ON SITE.
12. PROVIDE FIRE ALARM VERIFICATION OF ALL DEVICES AND/OR LOOPS AFFECTED IN THIS PROJECT.
13. DRAWINGS ONLY SHOW APPROXIMATE LOCATION OF DEVICES. EXACT LOCATION OF DEVICES TO BE CONFIRMED ON SITE.
14. PROVIDE ALL LABOUR AND MATERIALS FOR ALL SYSTEMS TO BE FULLY OPERATIONAL.



3	ISSUED FOR CONSTRUCTION	2022-05-17
2	99% CONSTRUCTION DOCUMENT	2021-08-06
1	50% DESIGN SUBMISSION	2021-05-28

revisions	date
project	projet

Wabush - ATB Boiler Upgrade

Wabush Airport Terminal Building (ATB)

drawing	dessin
---------	--------

BOILER ROOM - EXISTING ELECTRICAL PLAN

designed BC	conçu
----------------	-------

drawn RD	dessiné
-------------	---------

approved HCC	approuvé
-----------------	----------


Tender	Soumission
--------	------------

PSPC Project Manager	Administrateur de projets TPSGC
project no.	no. du projet

R111141.001

drawing no.	no. du dessin
-------------	---------------

E-2



APPROX. NORTH