

Channel Dredging and Disposal at Sea**Cheticamp (La Digue) Small Craft Harbour****Inverness County, N.S.****R.121899.001**

Sitework, Demolition and Removals

Page 1

PART 1 - GENERAL

- 1.1 Description of Work This Section includes but is not limited to the following:
- .1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. All available plans of the existing structure are available for viewing at the Project Manager's office, 2nd floor, 1713 Bedford Row, Halifax, N.S.
 - .2 Any derricks, gas lines or buildings to be removed by others unless otherwise indicated.
- 1.2 Related Work
- .1 Refer to other specification sections for related information.
 - .2 Refer to **Section 01 33 00** for Shop Drawing/Submission requirements.
- 1.3 Submissions
- .1 Methodology:
 - .1 When requested provide methodology for carrying out the work
 - .2 Provide submission in accordance with **Section 01 33 00**.
- 1.4 Protection
- .1 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of *Departmental Representative* and at no additional cost to *Departmental Representative*.
 - .2 Prevent debris from going adrift and becoming a menace to navigation.
 - .3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the

Channel Dredging and Disposal at Sea**Cheticamp (La Digue) Small Craft Harbour****Inverness County, N.S.****R.121899.001**

Sitework, Demolition and Removals

Page 2

Contractor's cost to the satisfaction of the
Departmental Representative.

1.5 Measurement for
Payment

- .1 Sitework, demolition and removals will be measured in accordance with **Section 01 29 00.**

PART 2 - PRODUCTS

Not applicable.

PART 3 - EXECUTION3.1 Preparation

- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative.*
- .4 Existing fill and vent pipes, oil waste tanks and underground storage tanks to be protected from any damages. All repairs to damages as a result of Contractor's operations to be at his cost and to the satisfaction of the *Departmental Representative.*

3.2 Removal

- .1 Remove items indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.

3.3 Disposal of
Material

- .1 Disposal of materials not designated for salvage or re-use in work, will be the
-

Channel Dredging and Disposal at Sea**Cheticamp (La Digue) Small Craft Harbour****Inverness County, N.S.****R.121899.001**

Sitework, Demolition and Removals

Page 3

contractor's responsibility, and must be disposed of off-site.

- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.
-